

11 Sophia Street

Street Lot

4

DPS

1595

Section

15487

Block

ROTORUA CITY COUNCIL

Drainage to New Sewer
(Appn. 1182)

Owner: H. Tuck

Valuation No.: 651/748/6

Plumber:

Permit No.: 6005

Drainlayer: Goodrick & Alding

Appn No.: 4485

INSPECTIONS

Date

17-7-75

Drainage Tested (Existing drains OK)



BC

6005

18/7/75





4485

CITY OF ROTORUA

Valuation No. 651/748/6

APPLICATION FOR PERMIT TO CARRY OUT SANITARY PLUMBING AND DRAINAGE WORK
I, the undersigned, hereby apply for permission to have the work described herein and set out on the plans attached hereto, carried out in accordance with the provisions of the Drainage and Plumbing Regulations 1959 at premises situated at:

Address 11 Sophia St

Legal Description:

Lot No. Lot 4. Deposited Plan No. 1595

Section No. Block No.

Description of Work: connection to sewage

Name and address of Person for whom work is to be carried out:

Mr H Tuck 11 Sophia St.

Name and address of Registered Plumber:

Name and address of Registered Drainlayer: GOODRICK & ALDING LTD.

	VALUE	FEE
Plumbing	\$:	\$:
Drainage	\$ 135:	\$ 3 :00
TOTAL FEES	\$:	

Signature: [Signature]
Date: 16.7.75

FOR OFFICE USE ONLY

Date Received 16.7.75

Fee Paid \$2.00 R16837

Date Paid 16.7.75

Issue Approved [Signature]

Date Approved 16.7.75

Permit No. 6005

Date Issued 18/7/75

See reverse for Fees and Notes.

FOR OFFICE USE ONLY

FEES PAYABLE ON THE ISSUE OF ANY PLUMBING OR DRAINAGE PERMIT

according to the Estimated Value of Work

Value of work (including value of fittings)	
Dollars	Dollars
up to 100	1.50
101 - 200	3.00
201 - 400	6.00
401 - 600	8.00
601 - 800	10.00
801 - 1000	12.00
1001 - 1200	14.00
1201 - 1400	16.00
1401 - 1600	18.00
1601 - 1800	20.00
1801 - 2000	22.00

2001 and over, 1 dollar extra for every \$200 or part thereof in excess of 2000 dollars.

IMPORTANT

INSPECTION & TESTING REQUIREMENTS

Drainage Work: Drainlayers are required to notify the Plumbing and Drainage Inspector when all work is completed. This includes effluent disposal systems for septic tanks. All drains will be tested with a 5ft head of water. To implement this test it will be necessary for persons undertaking drainage work to have sufficient drain plugs to fill all sections of the drain prior to the Plumbing and Drainage Inspector arriving on the job, also to have available a stand pipe to apply the 5ft head pressure.

This form of testing is essential to exclude the possibility of ground water infiltration with its attendant increase in pumping charges and overloading of the sewers and treatment plant.

Plumbing Work: Plumbers are required to notify the Plumbing and Drainage Inspector when work is ready for inspection as follows:

- (a) When the building has been initially piped out and wastes are installed (before wall linings are fixed and floors laid).
- (b) When work is complete.

Plans of Drainage and Plumbing work:

In the case of single houses a preliminary drainage plan will not be required. In all other cases, however, plans of the preliminary proposal are to be submitted at the time of application for a permit. In all instances, however, an "as laid" plan must be available on site as a prerequisite to a test of the work.

In commercial buildings full plans and elevations of plumbing stacks must be provided at the time of application for a permit.

Plans MUST show figured dimensions
and distances from section boundaries

Rotorua City Council DRAINAGE PLAN

NEW SEWERAGE DRAINS—RED
STORMWATER—DOTTED BLACK
OLD DRAINS—FULL BLACK

SCALE: IN. TO A FOOT

