



Tauranga City

LIM

Land Information Memorandum



Land Information Memorandum

This Land Information Memorandum has been prepared for:

Applicant	Bower Real Estate
Client	K Steward & A Burr
Property Address	16 Okataina Street Tauranga
Legal Description	Lot 2 DP 514907 1/2 Share of Lot 3 DP 514907 1/4 Share of Lot 973 DP 507200
Application Date	2 April 2026

This Land Information Memorandum has been prepared for the purposes of Part 6 of the Local Government Official Information and Meetings Act 1987. It is based on a search of Council records only. Additional information relevant to the property may be held on Council's property file or within other Council systems; however, is not included in this Land Information Memorandum. There may be other information relating to the land which is unknown to Council. The Council has not undertaken any inspection of the land or any building on it for the purpose of preparing this Land Information Memorandum. The applicant is solely responsible for ensuring that the land is suitable for a particular purpose. This Land Information Memorandum has been prepared for the applicant only. The Council accepts no responsibility or liability for any use of this report by third parties or for any reliance placed on its contents by persons other than the applicant. This Land Information Memorandum is valid only if reproduced in full and applies only as at the date of issue.

It is recommended that the Certificate/Record of Title, which is not held by Council, be searched by the purchaser.

Contents

Services Information

Rating/Valuation Details and Levies

Building Information

City Planning

Land Development

Natural Hazard Information

Additional Information/Licences

Services Information

Land information which is likely to be relevant includes information on private and public stormwater, water and sewer details. Please refer to the appropriate authorities for further information about network utility services.

Service Record

Service Print Attached	Yes
Method of Sewer Disposal	To Public Sewer
Existing Method of Stormwater Disposal	To Connection
Drinking Water Supplied to the Land	Yes
Drinking Water Supplier Is:	
(i) Owner of the Land; or	No Information Available
(ii) Tauranga City Council [Water Supply Authority Unit (WSA)]; or	Yes
(iii) Another Networked Supplier	No Information Available
Any Information Notified under Section 206(1) Water Services Act 2021	No Information Available

Note:

1. Please note that the existence of a watermain along a property frontage does not necessarily mean that a connection is available. This may need to be provided at the applicant's expense.
2. If the land is supplied with drinking water by Tauranga City Council as a Water Supply Authority, any conditions (generally set out in Tauranga City Council's [Supply of Water Bylaw 2019](#)) applicable to that supply are included in this Land Information Memorandum.
3. If the land is supplied with drinking water by a networked supplier other than the WSA, any conditions that are applicable to that supply are included in this Land Information Memorandum.
4. If the land is supplied with drinking water by the owner of the land, any information Council has about the supply is included in this Land Information Memorandum.
5. Any information notified to the territorial authority by a drinking-water supplier under Section 206(1) Water Services Act 2021 is included in this Land Information Memorandum.
6. Water services legislation is transitioning from the Water Services Act 2021 to the local Government (Water Services) Act 2025 and associated amendments. Some information in this Land Information Memorandum may reflect the previous legislative framework and may be subject to change or reinterpretation under the new Act.

Rating and Valuation Details

Tauranga City Council rates are billed twice a year on the last business day of August and February. Unpaid rates for each instalment will incur a 10% penalty.

The valuation details below are based on a revision date of 1 May 2023. This has been used to assess the rates for Council's financial year beginning 1 July 2025.

Further information on property valuations can be found on Council's website at the following link: [Property valuations - Tauranga City Council](#).

Valuation Details

Valuation Reference	06862 046 32
Capital Value	\$955,000
Land Value	\$455,000
Improvement Value	\$500,000

Rating Details

Current Annual Rates	\$4,110.18
Balance Owing	\$Nil

Water Meter Details

Water Meter On Property	Yes
Meter Type	Individual Meter
Water Rates Owing	\$83.46

A separate account is issued for water metered properties. Residential meters are read every three months. Commercial/Industrial meters vary depending on use.

Note:

Council's Water Supply Bylaw requires a final water meter reading to be undertaken when a property is sold.

Infrastructure Funding and Financing (IFF) Levy Details

The IFF levy (under the Infrastructure Funding and Financing (Western Bay of Plenty Transport System Plan Levy) Order 2022) is payable for a period of 30 years from 1 July 2024 to 30 June 2054. The method for assessing the liability for an IFF levy on the property is set out in the 2022 Order. The annual levy (as calculated under the 2022 Order) is allocated across the levy area with 50% of the overall levy coming from commercial and industrial properties and 50% coming from residential properties and with the IFF levy on the property being based on the capital value of the property. Further information on the levy is available at the following link: [Infrastructure Levy - Tauranga City Council](#).

IFF Levy Details

Current Annual IFF Levy	\$86.98
Balance Owing	\$Nil

Building Information

This information is sourced from Council records and may not reflect the situation on site if work has been undertaken without consent or has been undertaken and was exempt from consent.

This Land Information Memorandum provides a summary of key building-related information and does not include all documents held by Council. It is recommended that the property file is viewed together with this Land Information Memorandum to satisfy any due diligence requirements. The property file may be ordered at the following link: [Order a LIM or Property File](#).

Building Permits and Consents: Information related to Permits (issued prior to 1993) and Consents (issued after 1 January 1993) is listed below. Plans and other associated documents, where held by Council, are available on the property file. Where Council holds an as-built drainage plan, it will be attached to the building appendix of this Land Information Memorandum.

Solid Fuel Heaters: It is important that any solid fuel heater has been legally installed, either as part of the original dwelling or by way of a separate permit/consent.

Granny Flats: From 15 January 2026, a small standalone dwelling may be constructed without a building consent, if all exemption conditions are met under Schedule 1A of the Building Act 2004. Further information is available at the following link: [Guidelines on Building a Granny Flat](#).

Permits and Consents

Building Consents

Date Issued	Description of Work	BC Number	CCC Issued
18/12/18	New Dwelling. 3 Bedrooms, 2 Bathrooms, Double Garage	182234	Yes

Compliance Schedule N/A

Requisitions None

City Planning

The Operative Tauranga City Plan

The Tauranga City Plan provides the rules for how people can build or develop the land they own in our city. This can be land that is residential, commercial, industrial etc. The City Plan covers all subdivision, land use and development, how and where the city grows, how infrastructure is located and how natural and physical resources are managed. It is the blueprint by which any development in Tauranga is managed. It also includes rules on other things that are covered by the Resource Management Act - including hazards, signage, reserves, noise, heritage, etc.

There are specific rules within the City Plan that cover, amongst other matters, building height, earthworks, tree protection, bulk and scale of buildings, setbacks from coastal and harbour margins, and specific residential, commercial and industrial uses depending on location within the City.

Specific rules for each suburb and property can vary depending on the underlying zone of the area and the location of a specific property within that zone.

The majority of the City Plan became 'operative in part' on 9 August 2013. The remaining parts of the City Plan subsequently became operative on 5 July 2014.

A table showing a complete list of variations and plan changes to the operative City Plan can be found in the [Table of Plan Change Dates](#).

It is advised that prospective purchasers of property review and consider all relevant planning rules for the specific property this Land Information Memorandum applies to prior to purchase.

To view the Operative Tauranga City Plan please [click here](#).

If you have any specific queries on any rules or any existing or proposed use of a property, please contact the Tauranga City Council's Duty Planner (07 577 7000) for further information.

Development Contributions

Council operates a development contributions policy under the Local Government Act 2002, and also has financial contributions provisions in its City Plan. The broad purpose of these policies is to fund infrastructure costs that relate to the city's growth from those parties that undertake subdivision, building or development. These contributions are required on building consents, resource consents, service connection authorisations, certificates of acceptance and PIMs for small standalone dwellings. Contributions may remain payable on any property in circumstances where subdivision, building and development projects have not been completed, and in rare occasions where the Council has agreed to defer payment. In addition, further subdivision, building or development of a property may trigger the requirement to pay further development and/or financial contributions.

Council's development contributions team can advise further on these matters in relation to the application of development and financial contributions to the property in question.

Transportation Strategy & Planning and Reserve Management Plans

As part of Tauranga City Council's Transport strategy and planning activities and Reserves Management Plans, properties neighbouring Council-owned or administered land may be subject to transport network development such as walkways and cycleways or other development, activities or use of the land. The Tauranga Reserves Management Plan is available online at the following link: [Reserve Management Plans](#).

Relevant Planning Information

All Planning information for this property is available online through the [City ePlan](#).

Zone: Operative Tauranga City Plan	Medium Density Residential
Identified Plan Areas	None Known
Utilities/Designations	None
Protected Heritage/Notable or Groups of Trees, or Protected Buildings	None Known
Archaeological or Heritage Sites	None Known

Certificates, Notices, or Orders Affecting the Land

Description	Date Issued
Consent Notice	30/03/17*

Resource Consents *(Resource Management Act 1991)*

Description	Date Granted	RC Number
Subdivision and Land Use Consent	21/12/12	21332
Change Conditions of RC21332	11/04/14	21332-04
Change Conditions of RC21332	13/07/15	21332-08
Resource Consent – 2-Lot Subdivision	25/07/17	25903

Comments:

*Lots 2 and 3 DP 514907 being a subdivision of Lot 237 DP 507200.

Land Development

The following information relates to land development and landform characteristics. It is based on information held by council and may include reports, assessments, and other documentation relevant to site development. This information may not reflect the current on-site conditions, or any work undertaken that is not known to council.

The Tauranga City Council does not act as agent for network utility operators.

The landform and geology within Tauranga City have some features which demand particular attention. These features, which may or may not be relevant to the property in question, are outlined in "General Description of Landform within Tauranga District" as attached.

Comments:

Consent Notice

Refer Consent Notice dated 30 March 2017 together with Geotechnical Completion Report by Coffey Services (NZ) Limited, reference GENZTAUC13086AP-AK, dated 17 February 2017.

Documentation Relevant to the Subject Property

Refer the following documentation:

1. Retaining Wall Design report by The Engineer Limited, dated 27 March 2018.
2. Retaining Wall Review Report by CHS Engineers Limited, reference 062/18, dated 11 December 2018.
3. Geotechnical Plan Review by Coffey Services (NZ) Limited, reference 773-TRGGE226846, dated 9 February 2019.
4. Addendum to Geotechnical Plan Review by Coffey Services (NZ) Limited, reference 773-TRGGE226846AB, dated 22 February 2019.

Natural Hazards

This information relates to nation-wide, city-wide, or region-wide studies and may not reflect the on-site situation or natural hazard investigations and mitigation done on a site-specific property level. It is recommended that hazards identified in this section of the Land Information Memorandum be considered both individually and in combination, as their cumulative effects may influence the overall level of risk.

Flooding

Flood hazard information referenced here includes modelling produced at a nation-wide scale by Earth Sciences New Zealand (ESNZ). The national tool provides consistent flood hazard data across New Zealand and is zoomable to street level, but not to individual properties. For property-specific flood hazard information that may affect this property please refer to the following section of this Land Information Memorandum titled, "Natural Hazards Relevant to the Subject Property". The modelling produced by ESNZ is available to view at the following link: [Flood Hazard Modelling](#).

Microzoning for Earthquake Hazards

The Council has received reports and results that assessed Tauranga City's liquefaction vulnerability during earthquakes.

Different properties face varying probability levels of liquefaction damage. The maps assess natural ground conditions only and don't consider recent human activities like earthworks, ground improvements, or foundation design that may reduce liquefaction risk. Detailed, site-specific studies by qualified practitioners may take precedence over these city-wide assessments.

Liquefaction information may affect property use and development, including building consent requirements (Building Act 2004, NZ Standard AS/NZ 1170, TCC Infrastructure Development Code Chapter 10.10.6), subdivision consents (Resource Management Act), and infrastructure design.

Further information and reports are available at: [Earthquakes and Liquefaction](#).

Landslide Susceptibility

Council has received an assessment of Tauranga City's susceptibility to landslides. Two maps have been prepared, one showing areas susceptible to land sliding triggered by rainfall, and the other by earthquakes. A report detailing the assessment and maps are available by accessing the following link: [Landslide Susceptibility](#).

Shallow Groundwater

Council has received an assessment of shallow groundwater conditions in Tauranga City. The assessment analysed groundwater monitoring data from 2015-2021 across 97 monitoring sites and developed predictive models for future conditions under sea level rise.

Shallow groundwater occurs close to the surface throughout Tauranga's low-lying areas. Groundwater levels fluctuate with tides, rainfall, and seasonal variations. In some areas, groundwater sits less than 1 meter below ground surface. The assessment forecasts that rising groundwater levels will occur as sea levels rise.

Development Implications: This information may affect property use and development, including building consent requirements (Building Act 2004), subdivision consents (Resource Management Act), and infrastructure design. Site-specific geotechnical investigations may be required to assess local groundwater conditions and mitigation measures.

The full technical report and spatial datasets are available at: [Groundwater](#).

Bay of Plenty Regional Council

Further information regarding natural hazards held by the Bay of Plenty Regional Council that may be relevant to this property can be found at the below links. Further enquiries may also be made by contacting the Bay of Plenty Regional Council on 0800 884 880.

[Bay of Plenty Regional Council – Natural Hazards](#)

[Bay Hazards](#)

[Bay Explorer](#)

Natural Hazards Relevant to the Subject Property

The following information relates to natural hazards identified at a site-specific scale. It is based on information held by Council and may not reflect the current on-site conditions or any hazard investigations or mitigation measures that have occurred since, or that are not known to Council.

Further information about natural hazards held by Tauranga City Council can be found at the following link: [Tauranga City Council – Natural Hazards](#) and may also be identified on Council's mapping website, [Mapi](#).

Council is not aware of any natural hazards identified at a site-specific scale for this property.

Additional Information

Licences Affecting the Land or Buildings

None

Signed for and on behalf of the Council:

A handwritten signature in black ink, appearing to be 'ALW'.


Position held: Senior LIM & Property Files Officer

Date: 20 April 2026




Services Plan





Services Plan



Scale 1: 500 @A4

















Information shown on this plan is indicative only. The Council accepts no liability for its accuracy and it is your responsibility to ensure that the data contained herein is appropriate and applicable to the end use intended.

















Services Key












Water

-  Water Service Line
-  Water Meter
-  Rider Main
-  Reticulation Main
-  Trunk Water Main
-  Asbestos Pipe (Abandoned)
-  Asbestos Pipe (Operational)
-  Hydrant
-  Valve
-  Water Reservoir
-  Backflow - Double Check
-  RPZ
-  Valve
-  Private Water Bore




Stormwater

-  Service Line
-  Rising Main
-  Gravity Main
-  Stormwater Drain
-  Subsoil Drain
-  Stormwater Overland Flow Path
-  Culvert
-  Inlet
-  Outlet
-  Stormwater Manhole
-  Stormwater Sump
-  Stormwater Rodding Eye
-  Large Sump
-  Storage Pond

Wastewater

-  Service Line
-  Rising Main
-  Gravity Main
-  Asbestos Pipe (Abandoned)
-  Asbestos Pipe (Operational)
-  Node
-  Rodding Eye (Inspection Point)
-  Manhole
-  Valve
-  Chamber
-  Pump Station


Other

-  Abandoned assets and lines
-  Private assets and lines
-  Geotech Utility Buffer

More symbols may appear on the Services Plan than are shown here. For a full key please contact the [Tauranga City Council LIM Office](#).

Building Information






VENTURE Lot 2
No 16 OKATAINA St
AS BUILT UNDERFLOOR PLUMBING

BC 182234

- AREAS**
 AREA DV
 AREA OV
 ROOF PL
- NOTE 1**
 INTERN
 STACKE
- NOTE 2**
 HJ COC
- NOTE 3**
 GAS HC
 SPLASH
 TO FRID
- NOTE 4**
 TILED S
 90mm l
 CONFIF
- NOTE 5**
 SMART
 BE INS



MACGREGORS PLUMBING
REC 19698

Drainage as built plan

0705

Date: 13/3/19

Lot or Street No: LA02

Suburb: The Lakes


Consent No: BC182234

Drainlayer: James Elliston

Street Name: 16 Okataina st


Owner/Developer: venture developments

Registration No: 18782



James Elliston
M 027 552 1637

E james@baydrainage.co.nz



Planning Information



TAURANGA CITY COUNCIL

CONSENT NOTICE PURSUANT TO SECTION 221 RESOURCE MANAGEMENT ACT 1991

TCC Reference: RC21332

IN THE MATTER OF Plan DP 507200

AND

IN THE MATTER OF Subdivision Consent pursuant to
Sections 104, 108, 220 & 221 of the
Resource Management Act 1991

Pursuant to section 221 of the Resource Management Act 1991, the Tauranga City Council hereby certifies that by way of resolutions passed under delegated authority on the 21st of December 2012, 24th of July 2013, 7th of November 2013, 28th of January 2014, 11th of April 2014, 16th of March 2015 and the 19th of May 2016 the following conditions were imposed on the subdivision consent for Lot 1004 DP 501173:

That a Consent Notice be registered on the Certificate of Title advising the owner and subsequent owners thereof, of the following requirements to be complied with on a continuing basis:

For Lots 236 to 239 (inclusive) and 413 to 503 (inclusive), requiring that:

- a) *All development within these Lots, including but limited to the design and construction of any building or structure requiring a Building Consent in accordance with the Building Act 2004, shall be undertaken in accordance with the requirements and recommendations in the Geotechnical Completion Report prepared by Coffey Geotechnics (NZ) Limited entitled 'The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D) – Geotechnical Completion Report', referenced GENZTAUC13086AP-AK (Revision 'Final') and dated the 17th of February 2017. Tauranga City Council reference TL9666.*

For Lots 413, 441 & 442, 444 to 455 (inclusive), 457, 458, 460, and 493 to 503 (inclusive), requiring that:

- b) *These Lots contain building restriction areas labelled F to N (inclusive), RR to RZ (inclusive) and SA to SL (inclusive) as shown on the survey plan and within the Geotechnical Completion Report prepared by C Geotechnical Completion Report prepared by Coffey Geotechnics (NZ) Limited entitled 'The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D) – Geotechnical Completion Report', referenced GENZTAUC13086AP-AK (Revision 'Final') and dated the 17th of February 2017 (see plan number 13086AP-AK within Appendix A). All buildings or structures requiring a Building Consent in accordance with the Building Act 2004, shall be located outside of the identified building restriction areas unless a specific design is certified by a Category 1 geo-professional.*

For Lots 236 to 239 (inclusive), 413, 458 to 460 (inclusive), and 493 to 503 (inclusive), requiring that:

- c) *The owners are required to meet the full cost of fencing along any common boundary between the Lot and the adjoining land that is vested in Tauranga City Council as local purpose reserve or recreation reserve.*

For Lots 238 and 239, requiring that:

- d) *Any new dwelling being constructed, or any existing dwelling being extended greater than 25% of the existing floor area, that is above the ground floor level (i.e. being second and/or third storey), shall be designed and constructed to achieve an internal road-traffic design sound level of $40\text{dB}_{\text{Leq}(24\text{h})}$ inside all habitable rooms with the ventilating windows open.*

At the time of building consent application an acoustic design report shall be provided to Council from a suitably qualified and experienced acoustics expert demonstrating compliance with the abovementioned sound level requirement. If this cannot be achieved, then:

The windows of all habitable rooms shall be constructed with glazing that includes a laminated pane that is at least 6.38 millimetre thick and covers the glazed area, and a ventilation system shall be installed to either:

Consist of an air conditioning unit(s) provided that the noise level generated by the unit(s) must not exceed $40\text{dB}_{\text{Leq}(30\text{s})}$ in the largest habitable room (excluding bedrooms) and $35\text{dB}_{\text{Leq}(30\text{s})}$ in all other habitable rooms; when measured 1 metre from any grille or diffuser, or

- A system capable of providing a least 15 air changes per hour in the largest habitable room (excluding bedrooms) and at least 5 air changes per hour in all other habitable rooms, and*
- The noise level generated by the system must not exceed $40\text{dB}_{\text{Leq}(30\text{s})}$ in the largest habitable room (excluding bedrooms) and $35\text{dB}_{\text{Leq}(30\text{s})}$ in all other habitable rooms; when measured 1 metre from any grille or diffuser, and*
- The internal air pressure must be no more than 10 Pa above ambient air pressure due to the mechanical ventilation, and*
- Where a high air flow rate setting is provided, the system must be controllable by the occupants to be able to alter the ventilation rate with at least three equal progressive stages up to the high setting.*

The above requirements do not apply if it can be demonstrated by way of prediction or measurement by a suitably qualified and experienced acoustic expert that the road-traffic noise level from State Highway 36 is less than $55\text{dB}_{\text{Leq}(24\text{h})}$ on all facades of any addition, extension or alteration, or new dwelling which fronts State Highway 36.

For Lots 237 to 239 (inclusive), requiring that:

- e) *An acoustic fence constituting a close board timber fence with battens over the joins as illustrated within Figure 2 of the Hegley Acoustics Consultant's report dated 2 June 2015 shall be maintained on the boundary of the lot in the location as shown within Figure 1 of the Hegley Acoustics Consultants report dated 2 June 2015 (Tauranga City Council Objective reference A1424053). The fencing shall be maintained at all times to ensure its acoustic integrity is maintained.*

For Lots 493 to 503 (inclusive), requiring that:

- f) *The disposal of wastewater effluent from the site shall be by way of privately-owned on-site pumped connection to Council's reticulated wastewater infrastructure.*

All costs associated with the installation, operation, maintenance and replacement of this pumped system shall be met by the landowner.

DATED at Tauranga this **30th** day of **March** **2017**



.....
Authorising Officer
Tauranga City Council

The Lakes 2012 Limited
C/- Harrison Grierson Consultants Limited
PO Box 1199
Tauranga 3140

Attention: David Needham

**RESOURCE MANAGEMENT ACT 1991
SUBDIVISION AND LAND USE RESOURCE CONSENT DECISION – RC21332**

Tauranga City Council resolves:

That pursuant to Sections 104, 104B and 104D of the Resource Management Act 1991:

The Non-Complying Subdivision being a 859 lot subdivision (inclusive of one large lot) and 33 access lots, with an alternative Stage K subdivision option layout that will create 857 lots (large lot inclusive) and 34 access lots, along with 22 roads, 19 reserves and service infrastructure to be vest in Council on land that is potentially contaminated and zoned Greenbelt, Passive Open Space, Large Lot Residential and Suburban Residential

And;

The Land Use Activity application for future residential development on proposed lots 508 to 512 and 562 to 564 to develop in accordance with the Suburban Residential permitted activity conditions

By The Lakes 2012 Limited on land comprising the balance of The Lakes Stage 2 and Stage 3 legally described as Pt Lots 9, 10 and 11 DP 364444 and Pt Lot 103 DP 40802, is granted consent.

That pursuant to Section 113 of the RMA – the reasons for the decision are as per the recommendation:

The proposed activity will not be contrary to the purposes and principles of the RMA.

The actual and potential adverse effects of the proposal on the environment are considered to be less than minor.

The proposal will be reasonably consistent with the relevant objectives and policies of the Tauranga District Plan and Proposed Tauranga City Plan.

The proposal will be reasonably consistent with the relevant objectives and policies of the Regional Policy Statement and Proposed Regional Policy Statement.

There were no principle issues in contention.

That pursuant to Sections 108 and 220 of the RMA, this consent is subject to the following conditions:

1. *The proposal shall proceed in accordance with the application submitted including:*
 - *The Assessment of Environmental Effects prepared by Harrison Grierson Consultants Limited entitled "The Lakes – Balance Stage 2 and Stage 3", referenced 1520-132631-01, dated October 2012;*
 - *Further Information prepared by Harrison Grierson Consultants Limited entitled "RC21332 – The Lakes – Stage 2/3 Further Information Response", referenced 1520-132631-01, dated 23 November 2012;*
 - *Further Information prepared by Harrison Grierson Consultants Limited entitled "Stage 2/3 at The Lakes", referenced 1520-132631-01, dated 16 December 2012;*
 - *The Landscape Design Company Report dated 26 November 2012;*
 - *The Shrimpton & Lipinski Report entitled "Pyes Pa West Urbanisation Development, Tauranga – Geotechnical Assessment Report" referenced 16944, dated October 2003;*
 - *The Coffey Geotechnics Report entitled "Geotechnical Assessment Report – Suitability of Site for Residential Subdivision The Lakes Subdivision – Stages 2 & 3, Tauriko, Tauranga", referenced GENZTAUC13086AD, dated 17 August 2012;*
 - *The Archaeology Report prepared by Heritage Consultants entitled "Preliminary Archaeological Survey and Assessment of Effects – Proposed Residential Subdivision and Roading Development", dated April 2003;*
 - *The Emails received by Council from David Needham sent at;*
 - *3:41pm on 26 November 2012;*
 - *8:30am on 27 November 2012;*
 - *11:23am on 28 November 2012;*
 - *11:08am on 28 November 2012;*
 - *10:14am on 18 December 2012;*
 - *2:54pm on 19 December 2012;*
 - *9:51am on 21 December 2012;*
 - *The Scheme Plans prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042" referenced;*
 - *132631-23-RC100, rev 4, dated 17 December 2012;*
 - *132631-23-RC101, rev 3, dated 17 December 2012;*
 - *132631-23-RC102, rev 2, dated 23 November 2012;*
 - *132631-23-RC103, rev 2, dated 23 November 2012;*
 - *132631-23-RC104, rev 2, dated 23 November 2012;*
 - *132631-23-RC105, rev 2, dated 23 November 2012;*

- 132631-23-RC106, rev 2, dated 23 November 2012;
- 132631-23-RC107, rev 3, dated 5 December 2012;
- 132631-23-RC108, rev 4, dated 14 December 2012;
- 132631-23-RC109, rev 4, dated 19 December 2012;
- 132631-23-RC110, rev 3, dated 17 December 2012;
- 132631-23-RC112, rev 2, dated 23 November 2012;

And comply with either one of the following Scheme Plan options;

Option A

- The Scheme Plan prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042 referenced 132631-23-RC111, rev 2, dated 23 November 2012; or

Option B

- The Scheme Plans prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042 referenced 132631-23-RC400, rev 2, dated 5 December 2012 (disregarding Lot 951 which has been subject to area increase);
- The following Plans prepared by Harrison Grierson Consultants Limited;
 - "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012;
 - "Proposed Pedestrian and Shared Pedestrian/Cycleway Network", referenced 132631-23-RC202, rev 2, dated 27 November 2012;
 - "Proposed Road Profiles", referenced 132631-23-RC203, rev 2 dated 19 November 2012;
 - "Proposed Finish Contours", referenced 132631-23-RC200, rev 1, dated 19 October 2012;
 - "Indicative Earthworks Remaining Cut/ Fill Depths", referenced 132631-23-RC201, rev 1, dated 19 October 2012;
 - "Bus Tracking Curves 12.5m Rigid Bus", referenced 132631-23-RC204, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Stormwater Plan", referenced 132631-23-RC210, rev 2, dated 18 December 2012;
 - "Proposed Trunk Services Sanitary Sewer Plan", referenced 132631-23-RC211, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Potable Water Plan", referenced 132631-23-RC212, rev 1, dated 19 October 2012;
 - "Proposed Layout Overlaying City Plan L86", referenced 132631-23-RC300, rev 1, dated 19 October 2012;
 - "Proposed Layout Overlaying City Plan L95", referenced 132631-23-RC301, rev 1, dated 19 October 2012;
 - "Stage 2 and 3 Developable Areas", referenced 132631-23-RC302, rev 1, dated 19 October 2012;

Subject to any changes required through compliance with the following conditions

2. Any staging of subdivision consent by way of s223 / 224 certificates issued on separate survey for this subdivision is appropriate subject to that staging complying with all relevant conditions as listed for that stage within this subdivision consent.

3. *All matters and works relating to the servicing and accessing of the subdivision, shall be designed, supervised, constructed and certified in accordance with requirements of the Council's' Infrastructure Development Code.*
4. *Prior to any works commencing on the site (exclusive of site clearance or bulk earthworks associated with any Bay of Plenty Regional Council earthworks consent) the consent holder shall submit, to the Council, plans of the proposed activity to and obtain plan approval. Including the following:*
 - *The information and plans required by the Infrastructure Development Code;*
 - *All potential run out areas;*
 - *All flood risk areas;*
 - *Details of any overland flowpaths;*
 - *Details of the works to establish a suitable building platform on each proposed lot;*
 - *Details of the construction of the road to vest and the proposed traffic management measures;*
 - *Details of the construction for all Right of Way lots;*
 - *Details of the sewer extension that is required to service the upstream catchment;*
 - *Details of proposed temporary sanitary sewer pump station;*
 - *Details of design and construction of Detention Ponds and Dams demonstrating the peak flow mitigation required, and how maintenance access is achieved;*
 - *Details of the extent of ponding in extreme rainfall events;*
 - *Details of any culvert upgrade required under proposed roads to vest;*
 - *Details of Fire Fighting system;*
 - *Details of landscaping and planting within Road to vest;*
 - *Details of landscaping and planting of Greenbelt Reserves to vest;*
 - *Details of Recreation Reserves to vest, including development of playgrounds and landscaping (with structural retaining of slopes, accessibility of pathways, featured paving and structural and play equipment to similar standard as illustrated in Photographs received by Council on 18 December 2012)*
5. *All residential lots shall be provided with a separate underground connection to the sanitary sewer, stormwater, water and electricity reticulation system in accordance with the Council's Infrastructure Development Code*
6. *The proposed Right of Way lots 934, 960-991 inclusive (and lot 992 if Scheme Plan Option B prepared by Harrison Grierson Consultants Limited referenced 132631-23-RC400, rev 2, dated 5 December 2012 proceeds) shall be constructed in accordance with the Infrastructure Development Code.*
7. *Prior to the first application for s224 approval, the Kennedy Road Waste Water Pump Station shall be complete and operational.*
8. *All lots with a building platform higher than RL40m Moturiki Datum shall be fed from the Joyce Road water supply.*
9. *Where landscaping is proposed on land to be vested as local purpose Greenbelt reserve or Recreation reserve, the landscaping shall be established and maintained at the consent holders expense. The landscaping shall be maintained for not less than 36 months for Greenbelt and 18 months for Recreation reserve from the date of completion. The date of completion shall be agreed with Council. A maintenance*

bond shall be entered into should vesting occur prior to completion of the maintenance period.

10. *The consent holder shall supply to the Council a set of 'as built' plans of all engineering works in accordance with the Council's Infrastructure Development Code.*
11. *The location of any subsoil drains shall be shown on the as-built drawings submitted to the Council and within the geotechnical completion report required by Condition 16.*
12. *All earthworks design, testing and construction shall be undertaken in accordance with Infrastructure Development Code and the specific requirements of the consent holders appointed Geo-Professional.*
13. *Where earthworks and/or pre-load operations occur over the Council's mains the consent holder shall undertake a CCTV survey of the mains prior to, and upon completion of the earthworks and/or pre-load operations. Monitoring shall continue at regular intervals during the earthworks and pre-load phases of the project as an ongoing check of the condition of the mains and to ensure their serviceability. If damage occurs to the mains during the earthworks and/or pre-load operations the Council will repair the mains at the consent holder's expense, with any payment for repairs or losses arising as a result of the damage shall be paid prior to certification pursuant to Section 224.*
14. *The Consent Holder shall construct a building platform on each proposed lot to avoid the effects of inundation. The platform shall be a minimum of 500mm above the calculated 50 year (2%AEP) storm level.*
15. *Prior to any earthworks which will increase the stormwater runoff into adjoining catchments, the detention dams and/or ponds required to provide peak flow attenuation shall be in operation.*
16. *The Consent Holder shall provide to the Council a "Geotechnical Completion Report" complied by a Category 1 Geo-Professional. The report shall:*
 - *Comply with the Council's Infrastructure Development Code QA4 requirements;*
 - *Display the position of all designated building platforms and building restriction lines where applicable;*
 - *Certify the provision of debris protection bunds where required;*
 - *Provide recommendations for the disposal of stormwater;*
 - *Provide recommendations for the on going development of the lots (i.e. maximum cut/fill heights, management of steep slopes, etc.);*
 - *Confirm earthworks and/or building platforms have been constructed to comply with the New Zealand Building Code requirements;*
 - *Determine minimum floor level requirements for lots adjacent to stormwater ponding areas;*
 - *Certify that any residual settlement or differential settlement that may still occur shall not exceed the manufacturer's recommendations with respect to the installed underground pipe networks to be vested in Council or exceed accepted design techniques with respect to road settlement or long term deflection, or exceed the settlement limitations as detailed in the New Zealand Building Code;*
 - *Comment on removal or amendment of existing land feature/s displayed on Council's GIS.*

17. Pursuant to Section 128 of the Resource Management Act 1991, the Council may review this condition, upon receipt of the "Geotechnical Completion Report", and require a Consent Notice to be registered on the Certificate of Title of any allotments to which the recommendations of the "Geotechnical Completion Report" relate to.
 18. All building line restrictions or designated building platforms shall be clearly identified and dimensioned on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.
 19. The consent holder shall, prior to the release of the s223 certificate for the subdivision or any stage of the subdivision, submit to Council's Corporate Information Section three alternative street names for authorisation in accordance with Council's Street Naming Policy (including lwi consultation), for each proposed new street and lane in the subdivision. The authorised street name signs will be manufactured and erected by the consent holder at the consent holder's expense. All traffic and pedestrian access signage shall be manufactured by an approved certifier and erected by the consent holder at the consent holder's expense.
 20. All easements required for underground services and rights of way serving lots within the subdivision shall be duly granted or reserved.
 21. The consent holder shall register an easement in gross in favour of the Council over any stormwater overland flowpath located on private property, including those resulting from overload of the roading primary stormwater system under extreme rainfall conditions.
 22. The overland flowpath easement shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 and shall be shown as the "Right to Drain Stormwater" and shall be registered on the survey plan under a "Memorandum of Easements in Gross".
 23. The consent holder shall vest in the Council the following lots as shown on the scheme plan:
 - Lots 900-921 inclusive as Road;
 - Lots 930, 935, 938, 940, 944, 950 and 952 as Recreation Reserves;
 - Lots 933, 943, 945, 948, 949, 951 and Pt Lot 9 DP364444 as Local Purpose: Greenbelt Reserves;
 - Lots 931, 936, 937 and 941 as Local Purpose: Accessway Reserves;
 - Lot 947 as Local Purpose: Waste Water Reserve;
- The lots to vest shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.
24. Prior to vesting of lot 947, the consent holder shall enter into a bond for removal of the temporary waste water pump station and associated Infrastructure. Should modification of the structure plan result in the pump station forming part of the permanent network, then a bond will not be required.
 25. Pursuant to Section 221 of the Resource Management Act 1991, a consent notice shall be registered on the Certificate of Title of any property that shares a common boundary with any of the following local purpose reserves:
 - Accessway
 - Recreation
 - Drainage
 - Waste Water

- Stormwater
- Greenbelt

The consent notice shall advise the owners and subsequent owners thereof, of the following requirement to be complied with on a continuing basis: The owners are required to meet the full cost of any fencing along the common boundary between the lot and adjoining land that are intended to be vested in Tauranga City Council as local purpose reserve.

26. *Upon application for the s223 certificate for the subdivision the consent holder shall confirm in writing to Council which property boundaries require a fencing consent notice to be registered on its title.*
27. *Prior to bulk earthworks being undertaken within 100m of the area marked potential "HAIL Site" on the Harrison Grierson Plan entitled "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012, a site investigation report prepared by a suitably qualified professional in accordance with 'Guideline No.1 – Reporting on Contaminated Sites in New Zealand, Ministry for the Environment' is required to be provided to Council's Manager of Environmental Planning. The site investigation report shall identify and quantify any soil contamination, and any remediation works necessary (if any). Prior to lodgement of s224 application in relation to the above land area, any remediation works required to address contaminated soil shall be undertaken. Note, that a land use consent under the City Plan addressing contaminated soil will be required if the site investigation report determines it to be contaminated.*
28. *That before the commencement of any ground disturbance associated with the proposed development within Stages 3H, 3F and Lot 949 (Local Purpose Reserve:Greenbelt), an authority to modify damage or destroy U14/_1915 and U14_2166 and possible unrecorded subsurface archaeological sites from the New Zealand Historical Places Trust is to be obtained under the provisions of Section 12 of the Historic Places Act 1993. Ngai Tamarawaho Iwi representatives shall also be given 48 hours notice in writing prior to the commencement of earthworks within the abovementioned locations within the subdivision.*
29. *The amalgamation conditions referenced within the Scheme Plans listed within Condition 1 shall be recorded on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 (LINZ Request: 1114213).*
30. *That a shared cycleway/walkway is to be constructed within the State Highway designation from Pyes Pa Road to link with the Collector Road within the site which is denoted as part of a potential future cycleway/walkway within the Harrison Grierson Plan entitled "Proposed Pedestrian and Shared Pedestrian/Cycleway Network", referenced 132631-23-RC202, rev 2, dated 27 November 2012. The timing and design of construction of the cycleway /walkway within the State Highway (Pyes Pa Bypass) will require approval under s176 of the Resource Management Act 1991. The final approval of construction drawings will be required from New Zealand Transport Agency State Highway Manager. Bay of Plenty.*
31. *The subdivision consent has a term of 15 years to complete from the date in which it has been granted.*
32. *All costs associated with the conditions of this consent, including those required under the Council's' Infrastructure Development Code, shall be met by the consent holder.*

Recommended and Assessed by:


James Jacobs
Intermediate Environmental Planner

Delegated Authorisation by:


Natalie Rutland
Team Leader: Environmental Planning

Date: 21 December 2012

Advice Notes

1. Under RMA s357, you can object to this consent by serving written notice on the Council within 15 working days of receiving this decision, detailing the reasons for the objection.
2. Should the actual processing cost exceed the deposit fee paid at lodgement, if not already accompanying this decision, an invoice may be sent at a later date.
3. Development contributions under LGA 2002 –

Requirement for development contribution: Pursuant to section 198(1)(a) of the Local Government Act 2002, Council requires that a development contribution provided for and in accordance with Council's Development Contributions Policy (which is subject to change), be made (paid) by the consent holder to Council.

Calculation and payment: Council's Development Contributions Policy currently provides that the required development contribution (in part in relation to any stage of a staged subdivision) is:

- calculated in accordance with Council's Development Contributions Policy in force at the time the section 224 completion certificate under the Resource Management Act 1991 is granted by Council; and


- payable immediately before the section 224 completion certificate is released, and that the certificate will not be released until the contribution is paid in full to Council.

*To avoid doubt, **granted** means the time when Council has approved the survey plan under section 223 and is satisfied that all or any of the conditions of the subdivision consent have been complied with and that in respect of such conditions that have not been complied with that the appropriate completion certificate and/or consent notice has been issued and/or bond been entered into.*

Postponement or remission: Council's Development Contributions Policy currently provides that there will be no postponement or remission of development contributions except in exceptional circumstances at the discretion of Council's Chief Executive or in the special circumstances outlined in Council's Development Contributions Policy.

4. All archaeological sites whether recorded or unrecorded under Part 1 of the Historic Places Act 1993 cannot be destroyed, damaged or modified without the consent of the Historic Places Trust of New Zealand. In the event that an archaeological site(s) and/or koiwi are unearthed, the consent holder is advised to immediately stop work on the part of the site that the archaeological site(s) is located, and contact the Historic Places Trust for advice.

5. *Construction noise from starting up and operation of construction equipment and all other construction activities on the site of the subdivision are required to meet the limits recommended in Table 1 in NZS6803:1999, and shall be measured and assessed in accordance with, NZS6803P:1984 - "The measurement and assessment of noise from construction, maintenance and demolition work". Adjustments provided in Clause 6.1 of NZS6803P:1984 shall apply for the full duration of the project, and references in the tables to NZS6802 shall read as references to Clause 4.2.2 of NZS6802:1991.*
6. *Where any building or drainage works are required to satisfy conditions of this consent, all consents required under the Building Act 2004 must be obtained prior to the works being carried out.*
7. *Dust management and silt runoff is to be controlled in accordance with the City Plan and the Infrastructure Development Code. The Consent Holder is advised that they are required by Bay of Plenty Regional Councils Land Management Plan to take the appropriate measures to prevent or minimise sediment generation and yield (sediment discharge).*
8. *Noise attenuation treatment within State Highway 36 shall be implemented in accordance with the 'Agreement in respect of the Funding and Construction of Noise Attenuation Barriers along Pyes Pa Bypass (Takitimu Drive Extension)' dated November 2010.*
9. *Where land to be vested is subject to a specified interest that is proposed to remain, the Council may certify that interest on the survey plan, pursuant to section 239(2) of the Resource Management Act 1991.*
10. *The consent provides approvals to both layouts in Stage 3K. Should Tauranga City Council wish the applicant to pursue Option B then they recognise that they will need to confirm this to the applicant and confirm how the consent holder will be compensated for implementing this option. The consent holder is under no obligation under this consent to pursue Option B.*
11. *Acknowledged is an agreement relating to works in Lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 19 May 2004 and deed of variation of agreement relating to works in lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 3 March 2006.*
12. *It is considered that the subdivision will be consistent with the Consent Notice 6592047.2 registered on the title of Lot 9 – 11 DP 364444*



NOTES:

- EXISTING TITLES**
 PT LOTS 9-11 DP 364444
 CT 261821
 THE LAKES 2012 LTD 84.8420ha
 PT LOT 103 DP 408042
 CT 428562
 THE LAKES 2012 LTD 19.0821ha
TOTAL 103.9041ha
- PROPOSED TITLES**
 LOTS 801-893 & 1-766
 (85B RESIDENTIAL LOTS) 51.2799ha
 LOTS 900-921
 (22 ROADS TO VEST) 18.9272ha
 LOTS 930-953
 (19 RESERVES TO VEST) 29.4346ha
 LOTS 960-991
 (32 PRIVATE ACCESS LOTS) 0.8955ha
 LOT 780
 (LARGE LOT) 3.168ha
 STAGE 2N LOTS FROM PARENT
 TITLE (1061 & 1065) 0.1331ha
TOTAL 103.9342ha
- AREAS & DIMENSIONS ARE APPROXIMATE ONLY & ARE SUBJECT TO RESOURCE CONSENT AND LAND TRANSFER SURVEY.
- REFER SHEETS RC101-RC112 FOR AMALGAMATION CONDITIONS AND MEMORANDUM OF EASEMENTS.
- STAGING LAYOUT SHOWN IS INDICATIVE ONLY. FINAL NUMBER, SIZE AND SEQUENCE OF STAGES MAY VARY.



APPROVED
 RC21332
 21 DEC 2012
PLAN



ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
 ISO 9001 QUALITY ASSURED

Office of Origin: Tauranga
 Level 1 Heron Creek House
 141 Cameron Road Tauranga 3110
 P +64 7 578 8023
 www.herrisonengineers.com

4	LOTS 565 & 946 REMOVED SEE DWGS RC106 - RC110	RJM	14.12.12
3	RESERVE LOTS 332 & 942 REMOVED	RJM	11.12.12
2	DETAILS OF REVISIONS DESCRIBED ON FOLLOWING SHEETS	RJM	29.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	28.10.12
REF	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

ORIGINATOR:	RJM	DATE:	1.0.12	SIGNED:		PLOTTED BY:	RJM
DRAWN:	RJM	DATE:	1.0.12	ENGINEER:		PLOTTED DATE:	17.12.12
CHECKED:		DATE:	19.10.12	SIGNED:		SURVEY BY:	
APPROVED:	DCN	DATE:	19.10.12	SIGNED:		SURVEY DATE:	

ISSUE STATUS:	RESOURCE CONSENT
PROJECT No:	13261-132631-01
SCALE:	1:2500 (A1) 1:5000 (A3)
DRAWING No:	132631-23-RC100
	A1
	REV
	4



NOTES:


1. AMALGAMATION CONDITIONS
 THAT LOT 960 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 803, 804 AND 805 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 961 HEREON BE HELD AS TO NINE UNDIVIDED ONE NINTH SHARES BY THE OWNERS OF LOTS 836-839 AND 842-846 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 962 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 856-859 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PT 2
 DPS 29192

APPROVED
Real3337
 21 DEC 2012
 PLAN



PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN, STORAGE WATER AND SEWAGE, LIGHT TO COINITY ELECTRICITY, TELECOM, WATER & GAS	LOT 960 HEREON	LOT 960 HEREON	LOT 803 LOT 804 LOT 805
	LOT 961 HEREON	LOT 961 HEREON	LOT 836 LOT 837 LOT 838 LOT 839 LOT 842 LOT 843 LOT 844 LOT 845 LOT 846 LOT 847 LOT 848 LOT 849
	LOT 962 HEREON	LOT 962 HEREON	LOT 856 LOT 857 LOT 858 LOT 859

HG
 HARRISON GRIMSON
 Office of Origin: Tauranga
 Level 1 Harrison Grimson House
 141 Cameron Road Tauranga 3110
 P 441 7 578 0033
 www.harrisongrimson.com

REF	REVISIONS	BY	DATE
3	LOT 932 REMOVED, LOT 933 AREA INCREASED	RJM	5.12.12
2	ACCESS LOT 961 WIDENED TO 6m	RJM	19.10.12
1	ISSUED FOR RESOURCE CONSENT	RJM	19.10.12

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

DISCIPLINE	DATE	SIGNED	PLLOT BY
DRAWN	10.10.12		RJM
CHECKED	10.10.12		
APPROVED	19.10.12		

RESOURCE CONSENT		
PROJECT No: 132631-01	SCALE: 1:3000 (A1) 1:6000 (A3)	A1
DRAWING No:		REV
132631-23-RC101		3

SEC 1
SO 416677

PT 2
DPS 29192

APPROVED
RC21332
21 DEC 2012
PLAN

933
LOCAL PURPOSE
RESERVE TO VEST
(GREEN BELT)

900
1.755ha
ROAD TO
VEST

TAKITIMU DRIVE (SH 36)
LEGAL ROAD

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

- NOTES:**
1. AMALGAMATION CONDITIONS THAT LOT 963 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 863 AND 864 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 2. THAT LOT 964 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 867 AND 868 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 3. THAT LOT 965 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 887 AND 888 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 963 HEREON	LOT 963 HEREON	LOT 863 LOT 864
	LOT 964 HEREON	LOT 964 HEREON	LOT 867 LOT 868
	LOT 965 HEREON	LOT 965 HEREON	LOT 887 LOT 888

HG
HARRISON
GRIERSON

ADVISORS AND DESIGNERS
Office of Origin: Tauranga
Level 1, Harbour Green House
141 Cameron Road, Tauranga 3110
P. 464 7 578 0023
www.harrisongrierson.com

REP	REVISIONS	BY	DATE
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	31.12.12

**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042**

OPERATOR:	DATE:	SIGNED:	PLUT BY:
RJM	10.12		RJM
DRAWN:	DATE:	SIGNED:	PLUT DATE:
RJM	10.12		23.11.12
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.10.12		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.10.12		

RESOURCE CONSENT		
PROJECT No:	SCALES:	A1
1520132631-01	1:625 (A1) 1:1250 (A5)	REV
DRAWING No:		

132631-23-RC102 **2**

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 966 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 34 AND 35 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 967 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 30 AND 31 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 968 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 127 AND 128 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 966 HEREOF LOT 967 HEREOF LOT 968 HEREOF	LOT 966 HEREOF LOT 967 HEREOF LOT 968 HEREOF	LOT 34 LOT 35 LOT 30 LOT 31 LOT 127 LOT 128

HARRISON ENGINEERS
ADVISORS AND DESIGNERS
Office of Origin: Tauranga
Level 1, Harbour Gateway Plaza
341 Cameron Road, Tauranga 3110
P +64 7 578 0023
www.harrisonengineers.com

2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	19.10.12
REF:	REVISIONS	BY	DATE

**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**


**TITLE:
PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042**

OWNER:	DATE: 1.0.12	SIGNED:	PLAT BY:	RJM
DRAWN:	DATE: 1.0.12	SIGNED:	PLAT DATE:	23.11.12
CHECKED:	DATE: 19.10.12	SIGNED:	SURVEY BY:	
APPROVED:	DATE: 19.10.12	SIGNED:	SURVEY DATE:	

RESOURCE CONSENT

PROJECT No: 1520-132631-01
DRAWING No: 132631-23-RC103

SCALES: 1:625 (A1)
1:1250 (A3)
A1
2



**APPROVED
RC21332
21 DEC 2012
PLAN**

**PT LOT 9
DP 364444
8019m²
LOCAL PURPOSE
RESERVE TO VEST
(GREEN BELT)**



NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 934 HEREON BE AMALGAMATED WITH SECTION 2 SO 416877 AND ONE COMPUTER REGISTER BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
 RC21832
 21 DEC 2012
PLAN

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOM., WATER & GAS	LOT 934 HEREON	LOT 934 HEREON	LOT 47 SEC 2 SO 416577

HG HARRISON GRIERSON
 ADVISORS AND DESIGNERS
 Office of Origin: Tauranga
 Level 1 Harrison Giereson House
 341 Cameron Road, Tauranga 3110
 P +64 7 578 0023
 www.harrisongiereson.com


REV	DESCRIPTION	DATE	BY	DATE
1	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES		RJM	23.11.12
2	ISSUED FOR RESOURCE CONSENT		RJM	28.11.12

THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042

DATE	SIGNED	DATE	SIGNED	DATE	SIGNED
10.12.12	RJM	10.12.12	RJM	23.11.12	RJM
19.10.12	DCN	19.10.12	DCN		

RESOURCE CONSENT
 PROJECT No: 132631-23-RC101
 DRAWING No: 132631-23-RC104
 SCALE: 1:625 (A1)
 1:1250 (A3)



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

1. AMALGAMATION CONDITIONS THAT LOT 969 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 149 AND 150 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
2. THAT LOT 970 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 244 AND 245 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENTS IN GROSS			
PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	A	LOT 242 HEREOF	TAURANGA CITY COUNCIL

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
S.W.V. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 969 HEREOF	LOT 969 HEREOF	LOT 149
	LOT 970 HEREOF	LOT 970 HEREOF	LOT 150

HG HARRISON GRIERSON
 ADVISORS AND DESIGNERS
 Office of Origin: Tauranga
 Level 1 Harbour Gateway House
 141 Cameron Road Tauranga 3110
 P +64 7 578 0023
 www.harrisongrierson.com

2	NEW EASEMENT A PROPOSED OVER LOT 242	RJM	13.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	13.12.12
REP	REVISIONS	BY	DATE

THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M


TITLE:
PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042

ORIGINATOR:	DATE: 10.12	SIGNED:	PLUT BY:	RJM
DRAWN:	DATE: 10.12	SIGNED:	PLUT DATE:	23.11.12
CHECKED:	DATE: 19.10.12	SIGNED:	SURVEY BY:	
APPROVED:	DATE: 19.10.12	SIGNED:	SURVEY DATE:	

ISSUE STATUS: **RESOURCE CONSENT**

PROJECT NO:	1520-132631-01	SCALES:	1:625 (A1) 1:1250 (A3)	A1
DRAWING NO:				REV

132631-23-RC105 **2**



APPROVED
 RC21332
 21 DEC 2012
PLAN

2
 DP 348694



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 971 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 248 AND 249 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 972 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 229 AND 230 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 973 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 225 AND 226 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.


THAT LOT 974 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 217 AND 218 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 975 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 217 AND 218 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 977 HEREOF BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 378, 379 AND 380 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM, WATER & GAS	LOT 971 HEREOF	LOT 971 HEREOF	LOT 248
	LOT 971 HEREOF	LOT 971 HEREOF	LOT 249
	LOT 972 HEREOF	LOT 972 HEREOF	LOT 229
	LOT 972 HEREOF	LOT 972 HEREOF	LOT 230
	LOT 973 HEREOF	LOT 973 HEREOF	LOT 225
	LOT 973 HEREOF	LOT 973 HEREOF	LOT 226
	LOT 975 HEREOF	LOT 975 HEREOF	LOT 217
		LOT 218	
	LOT 977 HEREOF	LOT 977 HEREOF	LOT 378
	LOT 977 HEREOF	LOT 977 HEREOF	LOT 379
			LOT 380

APPROVED
 RC1332
 21 DEC 2012
 PLAN



HG
 HARRISON
 GRIERSON
 ADVISORS AND DESIGNERS
 Office of Origin: Tauranga
 Level 1, Harbour Gateway House
 141 Cameron Road, Tauranga 3110
 P +64 7 578 0022
 www.harrisongrierson.com

1	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
2	ISSUED FOR RESOURCE CONSENT	RJM	18.12.12
REF	REVISIONS	BY	DATE

THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M

TITLE:
 PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 36444
 & PT LOT 103 DP 408042

DESIGNER:	DATE:	SIGNED:	PLAT BY:
RJM	12.12.12		RJM
DRAWN:	DATE:	SIGNED:	PLAT DATE:
RJM	10.12.12		23.11.12
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.10.12		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.10.12		


RESOURCE CONSENT		
PROJECT NO:	SCALE:	REV
1320-132631-01	1:625 (A1) 1:1250 (A2)	1
DRAWING NO:		REV
132631-23-RC106		2



PT 2
DPS 30316

SEC 9
SO 344242

2
DPS 53649



NOTES:

- 1. AMALGAMATION CONDITIONS
THAT LOT 976 HEREOF BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 370, 371 AND 372 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
RC21332
21 DEC 2012
PLAN

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W., RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 976 HEREOF	LOT 976 HEREOF	LOT 370 LOT 371 LOT 372

HC
HARRISON CONSULTANTS
Office of Origin: Tauranga
Level 1 Harrison Offices House
141 Cameron Road Tauranga 3110
P 464 7 578 0223
www.harrisonengineers.com

REF	REVISIONS	BY	DATE
3	LOT 942 REMOVED, LOT 460 REVISED FOR RESERVE	RJM	5.5.12
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	19.10.12

PROJECT:
THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

TITLE:
PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042

ORIGINATOR:	DATE:	SIGNED:	PLLOT BY:
RJM	1.0.12		RJM
DRAWN:	DATE:	SIGNED:	PLLOT DATE:
RJM	1.0.12		05.12.12
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.10.12		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.10.12		

ISSUE STATUS: **RESOURCE CONSENT**

PROJECT NO:	SCALE:	DATE:	REV
1320-132631-01	1:625 (A1) 1:1250 (A3)	15.10.12	A1
DRAWING NO:	DATE:	REV	
132631-23-RC107	15.10.12	3	




THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

NOTES:

1. **AMALGAMATION CONDITIONS**

THAT LOT 980 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 508, 509 AND 510 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
RC 21332
21 DEC 2012
PLAN



PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 980 HEREON	LOT 980 HEREON	LOT 508 LOT 509 LOT 510

HARRISON CONSULTANTS
Office of Origin: Tauranga
Level 1, Harrison Grison House
241 Cameron Road Tauranga 3110
P +64 7 578 0023
www.harrisonconsultants.com

NO.	REVISIONS	BY	DATE
4	LOT 946 REMOVED NOW PART OF LOT 790	RJM	14.12.12
3	AREA OF LOT 946 INCREASED	RJM	5.12.12
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	28.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	18.10.12

PROJECT: **THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M**

TITLE: **PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042**

ORGANISATION	DATE	SIGNED	PLotted BY
RJM	13.10.12		RJM
RJM	13.10.12		17.12.12
DCM	19.10.12		
DCM	19.10.12		

ISSUE STATUS: **RESOURCE CONSENT**

PROJECT No: 1520-132631-01	SCALE: 1:1625 (A1) 1:1250 (A3)	A1
DRAWING No: 132631-23-RC108		REV 4

APPROVED
RC21332
21 DEC 2012
PLAN

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
ISO 9001 QUALITY ASSURED

NOTES:
1. AMALGAMATION CONDITIONS

THAT LOT 978 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 486 AND 487 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 979 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 490 AND 491 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 981 HEREOF BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 548 TO 555 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENT IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
PEDESTRIAN ACCESSWAY	8	LOT 790 HEREOF	TAURANGA CITY COUNCIL
		LOT 981 HEREOF	LOT 981 HEREOF

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMS, WATER & GAS	K.O.V.	LOT 978 HEREOF	LOT 978 HEREOF LOT 486 LOT 487
		LOT 979 HEREOF	LOT 979 HEREOF LOT 490 LOT 491
		LOT 981 HEREOF	LOT 548 LOT 549 LOT 550 LOT 551 LOT 552 LOT 553 LOT 554 LOT 555
		LOT 981 HEREOF	LOT 981 HEREOF
		LOT 981 HEREOF	LOT 551 LOT 552 LOT 553 LOT 554 LOT 555
		LOT 981 HEREOF	LOT 551 LOT 552 LOT 553 LOT 554 LOT 555
		LOT 981 HEREOF	LOT 551 LOT 552 LOT 553 LOT 554 LOT 555

HC
HARRISON ORLSON
ENGINEERS

NO.	DESCRIPTION	DATE	BY
4	PEDESTRIAN ACCESS OVER LOT 981 PROVIDED	RJM	19.12.12
3	LOT 946 REMOVED NOW PART OF LOT 790	RJM	14.12.12
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	19.10.12

PROJECT:
THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

TITLE:
PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042

ORIGINATOR	DATE	SIGNED	PLLOT BY
RJM	10.12		RJM
DRAWN	DATE	SIGNED	PLLOT DATE
RJM	10.12		19.12.12
CHECKED	DATE	SIGNED	SURVEY BY
DCM	19.10.12		
APPROVED	DATE	SIGNED	SURVEY DATE
DCM	19.10.12		

ISSUE STATUS:
RESOURCE CONSENT

PROJECT NO: 1520-132631-01
SCALE: 1:625 (A1)
1:1250 (A3)

DRAWING No: 132631-23-RC109
REV: 4

Handwritten: Pedestrian Access easement removed from proposal - confirmed by applicant 21/12/12

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 982 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 575 TO 578 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.


 THAT LOT 983 HEREON BE HELD AS TO TWELVE UNDIVIDED ONE TWELFTH SHARES BY THE OWNERS OF LOTS 591 TO 602 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 984 HEREON BE HELD AS TO SEVEN UNDIVIDED ONE SEVENTH SHARES BY THE OWNERS OF LOTS 606 TO 612 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
 RC21332
 21 DEC 2012
PLAN

HARRISON GREENSON
 Office of Origin: Tauranga
 Level 1, Harrison Greenson House
 141 Cameron Road Tauranga 3110
 P 461 378 0023
 www.harrisongreenson.com

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 982 HEREON	LOT 982 HEREON	LOT 575
			LOT 576
			LOT 577
	LOT 983 HEREON	LOT 983 HEREON	LOT 578
			LOT 591
			LOT 592
	LOT 984 HEREON	LOT 984 HEREON	LOT 593
			LOT 594
			LOT 595
	LOT 964 HEREON	LOT 984 HEREON	LOT 596
			LOT 597
			LOT 598
LOT 964 HEREON	LOT 984 HEREON	LOT 599	
		LOT 600	
		LOT 601	
LOT 964 HEREON	LOT 984 HEREON	LOT 602	
		LOT 606	
		LOT 607	
LOT 964 HEREON	LOT 984 HEREON	LOT 608	
		LOT 609	
		LOT 610	
LOT 964 HEREON	LOT 984 HEREON	LOT 611	
		LOT 612	
		LOT 612	



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 985 HERON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 629, 630 AND 631 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 986 HERON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 650 AND 651 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
 RC21332
 21 DEC 2012
PLAN

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 985 HERON	LOT 985 HERON	LOT 629 LOT 630
	LOT 986 HERON	LOT 986 HERON	LOT 631
			LOT 650 LOT 651

HG
 HARRISON GRIERSON
 ADVISORS AND DESIGNERS
 Office of Origin: Tauranga
 Level 1, Harrison Grierison House
 141 Cameron Road Tauranga 3110
 P +64 7 578 0023
 www.harrisongrierison.com


2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	15.12.12
REF	REVISIONS	BY	DATE

**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
 PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042

DESIGNER: RJM	DATE: 1.0.12	ENGINEER:	PLLOT BY: RJM
DRAWN: RJM	DATE: 1.0.12	ENGINEER:	PLLOT DATE: 23.11.12
CHECKED: DCN	DATE: 19.10.12	ENGINEER:	SURVEY BY:
APPROVED: DCN	DATE: 19.10.12	ENGINEER:	SURVEY DATE:

RESOURCE CONSENT	
PROJECT No: 13261-23-RC111-01	SCALE: 1:625 (A1) 1:1250 (A3)
DRAWING No:	REV 2




2
 DPS 69452

2
 DPS 84552



PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE RIGHT TO CONVEY ELECTRICITY, TELECOMM, WATER & GAS	LOT 987 HEREON	LOT 987 HEREON	LOT 681 LOT 682
	LOT 988 HEREON	LOT 988 HEREON	LOT 685 LOT 686
	LOT 989 HEREON	LOT 989 HEREON	LOT 699 LOT 700
	LOT 990 HEREON	LOT 990 HEREON	LOT 703 LOT 704 LOT 713
	LOT 991 HEREON	LOT 991 HEREON	LOT 708 LOT 709 LOT 710 LOT 711



NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 987 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 681 AND 682 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 988 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 685 AND 686 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 989 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 699 AND 700 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 990 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 703, 704 & 713 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 991 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 708 TO 711 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
 RC21332
 21 DEC 2012
PLAN

HARRISON GRIERSON
ADVISORS AND DESIGNERS
Office of Origin: Tauranga
Level 1 Harrison Grierison House
141 Cameron Road Tauranga 3110
P +64 7 578 0823
www.harrisongrierison.com

2	REVISED LOT LAYOUT	RJM	18.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	18.10.12
REF	REVISIONS	BY	DATE

PROJECT:
THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

TITLE: PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042			
ORIGINATOR:	DATE:	SIGNED:	FLY BY:
RJM	1.0.12		RJM
DRAWN:	DATE:	SIGNED:	FLY DATE:
RJM	1.0.12		23.11.12
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN			
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN			

RESOURCE CONSENT			
PROJECT No:	1320-132631-01	SCALE:	1:625 (A1) 1:1250 (A3)
DRAWING No:	132631-23-RC112		
			A1
			2

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 985 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 629 TO 632 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 986 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 652 AND 653 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 992 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 635 AND 636 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
RC 21332
21 DEC 2012
PLAN

HARRISON ENGINEERING CONSULTANTS
 Office of Origin: Tauranga
 Level 1, Harrison Glenpark House
 141 Cameron Road, Tauranga 3110
 P: +64 7 578 0023
 www.harrisoneng.co.nz


REF	REVISIONS	DATE
2	REVISED COLLECTOR ROAD AND LOT LAYOUT	RJM 5.12.12
1	ISSUED FOR RESOURCE CONSENT	RJM 20.11.12

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGE 3K - OPTION B**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**


ORIGINATOR	DATE	SIGNED	PLAT BY	RJM
RJM	20.11.12			
DRAWN	DATE	SIGNED	PLAT DATE	05.12.12
RJM	20.11.12			
CHECKED	DATE	SIGNED	SURVEY BY	
DCN	20.11.12			
APPROVED	DATE	SIGNED	SURVEY DATE	
DCN	20.11.12			

ISSUE STATUS:		
RESOURCE CONSENT		
PROJECT No:	1:625 (A1)	A1
1520-132631-01	1:1250 (A3)	
DRAWING No:		REV
132631-23-RC400		2



2
DPS 69452

2
DPS 84552



APPROVED
RC21332
21 DEC 2012
PLAN

CYCLEWAY TO UTILISE CONSTRUCTED PATH ON BRIDGE AND CONTINUE UP TO PYLES PA RD INSIDE TRANSIT LAND BEHIND SAFETY BARRIER

		Office of Origin: Tauranga Level 1 Harrison Grierson House 141 Commerce Road Tauranga 3110 P. 44 7 578 0023 www.harrisongrierson.com	
		ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND	
<small>THIS DRAWING AND THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.</small>		ISO 9001 QUALITY ASSURED	
2	AMENDMENTS MADE TO CYCLE LANES FOR CLARITY	RJM	27.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	26.11.12
REF	REVISIONS	BY	DATE
PROJECT:			
THE LAKES 2012 LTD TAURANGA			
TITLE:			
PROPOSED PEDESTRIAN AND SHARED PEDESTRIAN/CYCLEWAY NETWORK			
DESIGNED BY	DATE	SIGNED	PROJECT BY
RJM	1.0.12		RJM
DRAWN BY	DATE	SIGNED	PROJECT DATE
RJM	1.0.12		27.11.12
CHECKED BY	DATE	SIGNED	SCALE
DCM	19.10.12		AS SHOWN
APPROVED BY	DATE	SIGNED	SUPPLY DATE
DCM	19.10.12		
RESOURCE CONSENT PROJECT No: 1520-122631-01 PAGES: 1-2200 (A1) DRAWING No: 1520-122631-01 PAGES: 1-5000 (A3)			
DRAWING No:			REV
132631-23-RC202			2

- NOTES:**
1. PATHS SHOWN ARE INDICATIVE ONLY. FINAL LAYOUTS TO BE AGREED UPON AT TIME OF ENGINEERING APPROVAL
 2. THE COLLECTOR ROADS WILL PROVIDE STANDARD FOOTPATHS AND CYCLE LANES WITHIN THE CARRIAGEWAY
- DENOTES SHARED CYCLEWAY/WALKWAY
 - DENOTES WALKWAY ONLY
 - DENOTES CYCLE LANES ON COLLECTOR ROADS
 - DENOTES POTENTIAL FUTURE CYCLEWAY/WALKWAY BY OTHERS

The Lakes 2012 Limited
C/- Harrison Grierson Consultants Limited
PO Box 1199
Tauranga 3140

DECISION ON CHANGE OF CONDITIONS APPLICATION – RC21332-04
Under the Resource Management Act 1991

That pursuant to Sections 104, 104B, 127 and 108 of the Resource Management Act 1991, the discretionary activity application by The Lakes 2012 Limited to carry out a redesign of the road layout and changes to access lots within stage 3 as well as the reconfiguration of some residential lots with an increase of nine (inclusive of the subdivision of Lot 6 DP 348694) relating to The Lakes Pyes Pa, Balance Stage 2 and Stage 3 legally described as Pt Lots 9, 10 and 11 DP 364444 and Pt Lot 103 DP 40802 be granted.

That pursuant to Section 113 of the RMA – the reasons for the decision are as per the recommendation:

The actual and potential effects on the environment of the change have been determined as being acceptable and approving the application will be consistent with the relevant provisions of the Regional Policy Statement and Operative City Plan. Overall the application will be consistent with the purpose and principles of the Act.

Condition 1, 4 and 29 amendments are highlighted in bold to read:

1. *The proposal shall proceed in accordance with the application submitted including:*
 - *The Assessment of Environmental Effects prepared by Harrison Grierson Consultants Limited entitled “The Lakes – Balance Stage 2 and Stage 3”, referenced 1520-132631-01, dated October 2012;*
 - *Further Information prepared by Harrison Grierson Consultants Limited entitled “RC21332 – The Lakes – Stage 2/3 Further Information Response”, referenced 1520-132631-01, dated 23 November 2012;*
 - *Further Information prepared by Harrison Grierson Consultants Limited entitled “Stage 2/3 at The Lakes”, referenced 1520-132631-01, dated 16 December 2012;*
 - *The Landscape Design Company Report dated 26 November 2012;*

- *The Shrimpton & Lipinski Report entitled "Pyes Pa West Urbanisation Development, Tauranga – Geotechnical Assessment Report" referenced 16944, dated October 2003;*
- *The Coffey Geotechnics Report entitled "Geotechnical Assessment Report – Suitability of Site for Residential Subdivision The Lakes Subdivision – Stages 2 & 3, Tauriko, Tauranga", referenced GENZTAUC13086AD, dated 17 August 2012;*
- *The Archaeology Report prepared by Heritage Consultants entitled "Preliminary Archaeological Survey and Assessment of Effects – Proposed Residential Subdivision and Roading Development", dated April 2003;*
- *The Emails received by Council from David Needham sent at;*
 - *3:41pm on 26 November 2012;*
 - *8:30am on 27 November 2012;*
 - *11:23am on 28 November 2012;*
 - *11:08am on 28 November 2012;*
 - *10:14am on 18 December 2012;*
 - *2:54pm on 19 December 2012;*
 - *9:51am on 21 December 012;*
- *Except where varied by the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-132631-01, dated June 2013 and Further Information received by Council dated 19 July 2013; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-133562-02 dated 9 October 2013 and the Further Information email received by Council from David Needham sent at 12:44pm on 31 October 2013; and the Hegley Acoustic Consultants report dated 1 July 2013; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1510-133562-02 dated 9 December 2013; and s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-135959-01 dated March 2014;*
- *The Scheme Plans prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042" referenced;*
 - *132631-23-RC100, rev ~~6-7~~, dated ~~17 June 2013~~ **25 February 2014;***
 - *132631-23-RC101, rev ~~8-9~~ dated ~~6 December 2013~~ **25 February 2014;***
 - *132631-23-RC102, rev ~~6-7~~ dated ~~17 June 2013~~ **25 February 2014;***
 - *132631-23-RC103, rev ~~2 3~~ dated ~~23 November 2012~~ **25 February 2014;***
 - *132631-23-RC104, rev ~~2 3~~ dated ~~23 November 2012~~ **25 February 2014;***
 - *132631-23-RC105, rev ~~2 3~~ dated ~~23 November 2012~~ **25 February 2014;***
 - *132631-23-RC106, rev ~~2 3~~ dated ~~23 November 2012~~ **25 February 2014;***
 - *132631-23-RC107, rev ~~3 4~~ dated ~~5 December 2012~~ **25 February 2014;***
 - *132631-23-RC108, rev ~~4 5~~ dated ~~14 December 2012~~ **25 February 2014;***
 - *132631-23-RC109, rev ~~4-5~~ dated ~~19 December 2012~~ **25 February 2014;***
 - *132631-23-RC110, rev ~~3 4~~ dated ~~17 December 2012~~ **25 February 2014;***
 - *132631-23-RC112, rev ~~2-3~~ dated ~~23 November 2012~~ **25 February 2014;***
 - ***132631-23-RC500, rev 1, dated 2 March 2014;***

And comply with either one of the following Scheme Plan options;

Option A

- The Scheme Plan prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042 referenced 132631-23-RC111, rev 2 3, dated ~~23 November 2012~~ **25 February 2014**; or

Option B

- The Scheme Plans prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042 referenced 132631-23-RC400, rev 2, dated 5 December 2012 (disregarding Lot 951 which has been subject to area increase);
- The following Plans prepared by Harrison Grierson Consultants Limited;
 - "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012;
 - "Proposed Pedestrian and Shared Pedestrian/Cycleway Network", referenced 132631-23-RC202, rev 2, dated 27 November 2012;
 - "Proposed Road Profiles", referenced 132631-23-RC203, rev 2 dated 19 November 2012;
 - "Proposed Finish Contours", referenced 132631-23-RC200, rev 1, dated 19 October 2012;
 - "Indicative Earthworks Remaining Cut/ Fill Depths", referenced 132631-23-RC201, rev 1, dated 19 October 2012;
 - "Bus Tracking Curves 12.5m Rigid Bus", referenced 132631-23-RC204, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Stormwater Plan", referenced 132631-23-RC210, rev 2, dated 18 December 2012;
 - "Proposed Trunk Services Sanitary Sewer Plan", referenced 132631-23-RC211, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Potable Water Plan", referenced 132631-23-RC212, rev 1, dated 19 October 2012;
 - "Proposed Layout Overlaying City Plan L86", referenced 132631-23-RC300, rev 2, dated 17 June 2013;
 - "Proposed Layout Overlaying City Plan L95", referenced 132631-23-RC301, rev 2, dated 17 June 2013;
 - Stage 2 and 3 Reduced Developable Areas Based on Revised Reserve Slopes referenced 132631-23-RC303, rev 2, dated 17 June 2013.

Subject to any changes required through compliance with the following conditions

Noting Condition 1 as amended through s127 Variation to Resource Consent granted 24 July 2013 – TCC Ref 21332*01 and subsequent s127 Variations to Consent granted 7 November 2013 – TCC Ref 21332*02 and 28 January 2014 – TCC Ref 21332*03 with amendments to consent condition underlined.

2. *Any staging of subdivision consent by way of s223/224 certificates issued on separate survey for this subdivision is appropriate subject to that staging complying with all relevant conditions as listed for that stage within this subdivision consent.*
3. *All matters and works relating to the servicing and accessing of the subdivision, shall be designed, supervised, constructed and certified in accordance with requirements of the Council's' Infrastructure Development Code.*
4. *Prior to any works commencing on the site (exclusive of site clearance or bulk earthworks associated with any Bay of Plenty Regional Council earthworks consent) the consent holder shall submit, to the Council, plans of the proposed activity to and obtain plan approval. Including the following:*
 - *The information and plans required by the Infrastructure Development Code;*
 - *All potential run out areas;*
 - *All flood risk areas;*
 - *Details of any overland flowpaths;*
 - *Details of the works to establish a suitable building platform on each proposed lot;*
 - *Details of the construction of the road to vest and the proposed traffic management measures;*
 - *Details of the construction for all Right of Way lots;*
 - *Details of the sewer extension that is required to service the upstream catchment;*
 - *Details of proposed temporary sanitary sewer pump station;*
 - *Details of design and construction of Detention Ponds and Dams demonstrating the peak flow mitigation required, and how maintenance access is achieved;*
 - *Details of the extent of ponding in extreme rainfall events;*
 - *Details of any culvert upgrade required under proposed roads to vest;*
 - *Details of Fire Fighting system;*
 - *Details of landscaping and planting within Road to vest;*
 - *Details of landscaping and planting of Greenbelt Reserves to vest;*
 - *Details of Recreation Reserves to vest, including development of playgrounds and landscaping (with structural retaining of slopes, accessibility of pathways, featured paving and structural and play equipment to similar standard as illustrated in Photographs received by Council on 18 December 2012);*
 - **Details of construction of pedestrian accessways**
5. *All residential lots shall be provided with a separate underground connection to the sanitary sewer, stormwater, water and electricity reticulation system in accordance with the Council's' Infrastructure Development Code*
6. *The proposed Right of Way lots 934, 960-991 inclusive (and lot 992 if Scheme Plan Option B prepared by Harrison Grierson Consultants Limited referenced 132631-23-RC400, rev 2, dated 5 December 2012 proceeds) shall be constructed in accordance with the Infrastructure Development Code.*
7. *Prior to the first application for s224 approval, the Kennedy Road Waste Water Pump Station shall be complete and operational.*

8. *All lots with a building platform higher than RL40m Moturiki Datum shall be fed from the Joyce Road water supply.*
9. *Where landscaping is proposed on land to be vested as local purpose Greenbelt reserve or Recreation reserve, the landscaping shall be established and maintained at the consent holders expense. The landscaping shall be maintained for not less than 36 months for Greenbelt and 18 months for Recreation reserve from the date of completion. The date of completion shall be agreed with Council. A maintenance bond shall be entered into should vesting occur prior to completion of the maintenance period.*
10. *The consent holder shall supply to the Council a set of 'as built' plans of all engineering works in accordance with the Council's Infrastructure Development Code.*
11. *The location of any subsoil drains shall be shown on the as-built drawings submitted to the Council and within the geotechnical completion report required by Condition 16.*
12. *All earthworks design, testing and construction shall be undertaken in accordance with Infrastructure Development Code and the specific requirements of the consent holders appointed Geo-Professional.*
13. *Where earthworks and/or pre-load operations occur over the Council's mains the consent holder shall undertake a CCTV survey of the mains prior to, and upon completion of the earthworks and/or pre-load operations. Monitoring shall continue at regular intervals during the earthworks and pre-load phases of the project as an ongoing check of the condition of the mains and to ensure their serviceability. If damage occurs to the mains during the earthworks and/or pre-load operations the Council will repair the mains at the consent holder's expense, with any payment for repairs or losses arising as a result of the damage shall be paid prior to certification pursuant to Section 224.*
14. *The Consent Holder shall construct a building platform on each proposed lot to avoid the effects of inundation. The platform shall be a minimum of 500mm above the calculated 50 year (2%AEP) storm level.*
15. *Prior to any earthworks which will increase the stormwater runoff into adjoining catchments, the detention dams and/or ponds required to provide peak flow attenuation shall be in operation.*
16. *The Consent Holder shall provide to the Council a "Geotechnical Completion Report" complied by a Category 1 Geo-Professional. The report shall:*
 - *Comply with the Council's Infrastructure Development Code QA4 requirements;*
 - *Display the position of all designated building platforms and building restriction lines where applicable;*
 - *Certify the provision of debris protection bunds where required;*
 - *Provide recommendations for the disposal of stormwater;*
 - *Provide recommendations for the on going development of the lots (i.e. maximum cut/fill heights, management of steep slopes, etc.);*

- Confirm earthworks and/or building platforms have been constructed to comply with the New Zealand Building Code requirements;
 - Determine minimum floor level requirements for lots adjacent to stormwater ponding areas;
 - Certify that any residual settlement or differential settlement that may still occur shall not exceed the manufacturer's recommendations with respect to the installed underground pipe networks to be vested in Council or exceed accepted design techniques with respect to road settlement or long term deflection, or exceed the settlement limitations as detailed in the New Zealand Building Code;
 - Comment on removal or amendment of existing land feature/s displayed on Council's GIS.
17. Pursuant to Section 128 of the Resource Management Act 1991, the Council may review this condition, upon receipt of the "Geotechnical Completion Report", and require a Consent Notice to be registered on the Certificate of Title of any allotments to which the recommendations of the "Geotechnical Completion Report" relate to.
18. All building line restrictions or designated building platforms shall be clearly identified and dimensioned on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.
19. The consent holder shall, prior to the release of the s223 certificate for the subdivision or any stage of the subdivision, submit to Council's Corporate Information Section three alternative street names for authorisation in accordance with Council's Street Naming Policy (including Iwi consultation), for each proposed new street and lane in the subdivision. The authorised street name signs will be manufactured and erected by the consent holder at the consent holder's expense. All traffic and pedestrian access signage shall be manufactured by an approved certifier and erected by the consent holder at the consent holder's expense.
20. All easements required for underground services and rights of way serving lots within the subdivision shall be duly granted or reserved.
21. The consent holder shall register an easement in gross in favour of the Council over any stormwater overland flowpath located on private property, including those resulting from overload of the roading primary stormwater system under extreme rainfall conditions.
22. The overland flowpath easement shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 and shall be shown as the "Right to Drain Stormwater" and shall be registered on the survey plan under a "Memorandum of Easements in Gross".
23. The consent holder shall vest in the Council the following lots as shown on the scheme plan:
- Lots 900-~~924~~ 919 inclusive as Road;
 - Lots 930, 935, 938, 940, 944, 950 and 952 as Recreation Reserves;
 - Lots 932, 933, 943, 945, 948, 949, 951 and Pt Lot 9 DP364444 as Local Purpose: Greenbelt Reserves;
 - Lots 931, 936, 937 and 941 as Local Purpose: Accessway Reserves;
 - Lot 947 as Local Purpose: Waste Water Reserve;

The lots to vest shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.

*Condition 23 as amended through s127 Variation to Resource Consent granted 24 July 2013 – TCC Ref 21332*01. Amendments to consent condition underlined.*

24. *Prior to vesting of lot 947, the consent holder shall enter into a bond for removal of the temporary waste water pump station and associated Infrastructure. Should modification of the structure plan result in the pump station forming part of the permanent network, then a bond will not be required.*
25. *Pursuant to Section 221 of the Resource Management Act 1991, a consent notice shall be registered on the Certificate of Title of any property that shares a common boundary with any of the following local purpose reserves:*
- *Accessway*
 - *Recreation*
 - *Drainage*
 - *Waste Water*
 - *Stormwater*
 - *Greenbelt*

The consent notice shall advise the owners and subsequent owners thereof, of the following requirement to be complied with on a continuing basis: The owners are required to meet the full cost of any fencing along the common boundary between the lot and adjoining land that are intended to be vested in Tauranga City Council as local purpose reserve.

26. *Upon application for the s223 certificate for the subdivision the consent holder shall confirm in writing to Council which property boundaries require a fencing consent notice to be registered on its title.*
27. *Prior to bulk earthworks being undertaken within 100m of the area marked potential "HAIL Site" on the Harrison Grierson Plan entitled "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012, a site investigation report prepared by a suitably qualified professional in accordance with 'Guideline No.1 – Reporting on Contaminated Sites in New Zealand, Ministry for the Environment' is required to be provided to Council's Manager of Environmental Planning. The site investigation report shall identify and quantify any soil contamination, and any remediation works necessary (if any). Prior to lodgement of s224 application in relation to the above land area, any remediation works required to address contaminated soil shall be undertaken. Note, that a land use consent under the City Plan addressing contaminated soil will be required if the site investigation report determines it to be contaminated.*
28. *That before the commencement of any ground disturbance associated with the proposed development within Stages 3H, 3F and Lot 949 (Local Purpose Reserve:Greenbelt), an authority to modify damage or destroy U14/_1915 and U14_2166 and possible unrecorded subsurface archaeological sites from the New Zealand Historical Places Trust is to be obtained under the provisions of Section 12 of the Historic Places Act 1993. Ngai Tamarawaho Iwi representatives shall also be*

given 48 hours notice in writing prior to the commencement of earthworks within the abovementioned locations within the subdivision.

29. *The amalgamation conditions referenced within the Scheme Plans listed within Condition 1 shall be recorded on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 (LINZ Requests: 1114213 & subsequent LINZ Requests 1152384 & 1191724 & 1204864 for plans associated with consent variations).*

*Condition 29 as amended through s127 Variation to Resource Consent granted 24 July 2013 – TCC Ref 21332*01 and 28 January 2014 – TCC Ref 21332*03 with amendments to consent condition underlined.*

30. *That a shared cycleway/walkway is to be constructed within the State Highway designation from Pyes Pa Road to link with the Collector Road within the site which is denoted as part of a potential future cycleway/walkway within the Harrison Grierson Plan entitled "Proposed Pedestrian and Shared Pedestrian/Cycleway Network", referenced 132631-23-RC202, rev 2, dated 27 November 2012. The timing and design of construction of the cycleway /walkway within the State Highway (Pyes Pa Bypass) will require approval under s176 of the Resource Management Act 1991. The final approval of construction drawings will be required from New Zealand Transport Agency State Highway Manager: Bay of Plenty.*
31. *The subdivision consent has a term of 15 years to complete from the date in which it has been granted.*
32. *All costs associated with the conditions of this consent, including those required under the Council's' Infrastructure Development Code, shall be met by the consent holder.*
33. *Pursuant to Section 221 of the Resource Management Act 1991, a consent notice shall be registered on the Certificate of Titles of the following Lots advising the owners and subsequent owners thereof of the requirements to be complied with on a continuing basis:*

For Lots 855, 856, 860, 861, 864, 865, 867, 868, 869 and 870

- a) An acoustic fence constituting a close board timber fence with battens over the joins as illustrated within Figure 2 of the Hegley Acoustics Consultants report dated 1 July 2013 shall be maintained on the boundary of the lot and the reserve adjacent to State Highway 36 in the location as shown within Figure 1 of the Hegley Acoustics Consultants report dated 1 July 2013. The fencing shall be maintained at all times to ensure its acoustic integrity is maintained.

For Lots 848, 849, 854, 855, 856, 860, 861, 864, 865, 867, 868, 869, 870, 879 and 890

- b) Any new dwelling being constructed, or any existing dwelling being extended greater than 25% of the existing floor area, that is above the ground floor level (i.e. being second and/or third storey), shall be designed and constructed to achieve an internal road-traffic design sound level of 40dBL _{Aeq(24h)} inside all habitable rooms with the ventilating windows open.

At the time of building consent application an acoustic design report shall be provided to Council from a suitably qualified and experienced acoustics expert demonstrating compliance with the abovementioned sound level requirement. If this cannot be achieved, then:

The windows of all habitable rooms shall be constructed with glazing that includes a laminated pane that is at least 6.38mm thick and covers the glazed area, and a ventilation system shall be installed to either:

- Consist of an air conditioning unit(s) provided that the noise level generated by the unit(s) must not exceed 40dB_{L_{Aeq(30s)}} in the largest habitable room (excluding bedrooms) and 35dB_{L_{Aeq(30s)}} in all other habitable rooms; when measured 1 metre from any grille or diffuser, or
- A system capable of providing a least 15 air changes per hour in the largest habitable room (excluding bedrooms) and at least 5 air changes per hour in all other habitable rooms, and
- The noise level generated by the system must not exceed 40dB_{L_{Aeq(30s)}} in the largest habitable room (excluding bedrooms) and 35dB_{L_{Aeq(30s)}} in all other habitable rooms; when measured 1 metre from any grille or diffuser, and
- The internal air pressure must be no more than 10 Pa above ambient air pressure due to the mechanical ventilation, and
- Where a high air flow rate setting is provided, the system must be controllable by the occupants to be able to alter the ventilation rate with at least three equal progressive stages up to the high setting.

The above requirements do not apply if it can be demonstrated by way of prediction or measurement by a suitably qualified and experienced acoustic expert that the road-traffic noise level from State Highway 36 is less than 55 dB_{L_{Aeq(24h)}} on all facades of any addition, extension or alteration, or new dwelling which fronts State Highway 36.

Condition 33 Imposed through s127 Variation to Consent granted 7 November 2013 TCC Ref 21332*02. Consent condition underlined.

Recommended and Assessed by:

HA 

James Jacobs
Intermediate Environmental Planner

Delegated Authorisation by:



Brad Bellamy
Acting Team Leader: Consents

Date: 11th April 2014

Advice Notes

1. Under RMA s357, you can object to this consent by serving written notice on the Council within 15 working days of receiving this decision, detailing the reasons for the objection.
2. Should the actual processing cost exceed the deposit fee paid at lodgement, if not already accompanying this decision, an invoice may be sent at a later date.
3. Development contributions under LGA 2002 –

Requirement for development contribution: Pursuant to section 198(1)(a) of the Local Government Act 2002, Council requires that a development contribution provided for and in accordance with Council's Development Contributions Policy (which is subject to change), be made (paid) by the consent holder to Council.

Calculation and payment: Council's Development Contributions Policy currently provides that the required development contribution is:

- determined in accordance with Table 2 of Schedule 1 of the Policy in force at the time this subdivision consent is granted; and
- payable immediately before the section 224 completion certificate is released, and that the certificate will not be released until the contribution is paid in full to Council.

Postponement or remission: Council's Development Contributions Policy currently provides that there will be no postponement or remission of development contributions except in exceptional circumstances at the discretion of Council's Chief Executive or in the special circumstances outlined in Council's Development Contributions Policy.

Advice Note 3 as amended through s127 Variation to Resource Consent granted 28 January 2014 – TCC Ref 21332*03.


4. All archaeological sites whether recorded or unrecorded under Part 1 of the Historic Places Act 1993 cannot be destroyed, damaged or modified without the consent of the Historic Places Trust of New Zealand. In the event that an archaeological site(s) and/or koiwi are unearthed, the consent holder is advised to immediately stop work on the part of the site that the archaeological site(s) is located, and contact the Historic Places Trust for advice.
5. Construction noise from starting up and operation of construction equipment and all other construction activities on the site of the subdivision are required to meet the limits recommended in Table 1 in NZS6803:1999, and shall be measured and assessed in accordance with, NZS6803P:1984 - "The measurement and assessment of noise from construction, maintenance and demolition work". Adjustments provided in Clause 6.1 of NZS6803P:1984 shall apply for the full duration of the project, and references in the tables to NZS6802 shall read as references to Clause 4.2.2 of NZS6802:1991.
6. Where any building or drainage works are required to satisfy conditions of this consent, all consents required under the Building Act 2004 must be obtained prior to the works being carried out.
7. Dust management and silt runoff is to be controlled in accordance with the City Plan and the Infrastructure Development Code. The Consent Holder is advised that they are required by Bay of Plenty Regional Councils Land Management Plan to take the

appropriate measures to prevent or minimise sediment generation and yield (sediment discharge).

8. *Noise attenuation treatment within State Highway 36 shall be implemented in accordance with the 'Agreement in respect of the Funding and Construction of Noise Attenuation Barriers along Pyes Pa Bypass (Takitimu Drive Extension)' dated November 2010.*
9. *Where land to be vested is subject to a specified interest that is proposed to remain, the Council may certify that interest on the survey plan, pursuant to section 239(2) of the Resource Management Act 1991.*
10. *The consent provides approvals to both layouts in Stage 3K. Should Tauranga City Council wish the applicant to pursue Option B then they recognise that they will need to confirm this to the applicant and confirm how the consent holder will be compensated for implementing this option. The consent holder is under no obligation under this consent to pursue Option B.*
11. *Acknowledged is an agreement relating to works in Lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 19 May 2004 and deed of variation of agreement relating to works in lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 3 March 2006.*
12. *It is considered that the subdivision will be consistent with the Consent Notice 6592047.2 registered on the title of Lot 9 – 11 DP 364444.*



PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM., WATER & GAS	LOT 971 HERON	LOT 971 HERON	LOT 285 LOT 286
	LOT 972 HERON	LOT 972 HERON	LOT 217 LOT 218 LOT 219 LOT 220 LOT 221 LOT 222 LOT 230 LOT 231 LOT 232
	LOT 973 HERON	LOT 973 HERON	LOT 233 LOT 234 LOT 235 LOT 236 LOT 237
	LOT 977 HERON	LOT 977 HERON	LOT 386 LOT 387 LOT 388



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERING CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 971 HERON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 285 AND 286 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 972 HERON BE HELD AS TO SIX UNDIVIDED ONE SIXTH SHARES BY THE OWNERS OF LOTS 217 TO 222 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 973 HERON BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 230 TO 237 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 977 HERON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 386, 387 AND 388 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

RC2132-04
RC24045
APPROVED
11 APR 2014
PLAN
Schem

HC
HARRISON
ENGINEERS

Tauranga Office
Level 1 Harbour Centre House
345 Cameron Road Tauranga 3110
P +64 7 578 0023
www.harrisonengineers.com

1	REVISED STAGE 2A & 2B LAYOUT & ALL LOT NUMBERS	RM	25/03/14
2	REVISED DRAWING FOR VISTING OF OPEN SPACE RESERVES	RM	25/03/14
3	ISSUED FOR RESOURCE CONSENT	RM	25/03/14
REV	REVISIONS	BY	DATE

PROJECT: **THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M**

TITLE: **PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042**


DESIGNED BY:	DATE:	ENGINEER:	PLANT BY:
DRAWN BY:	DATE:	ENGINEER:	PLANT DATE:
CHECKED BY:	DATE:	ENGINEER:	SURVEY BY:
APPROVED BY:	DATE:	ENGINEER:	SURVEY DATE:

RESOURCE CONSENT	
PROJECT No: 132631-23-RC106	SCALE: 1:625 (A3) 1:1250 (A4)
DRAWING No:	REV



NOTES:

- EXISTING TITLES**
 PT LOTS 9-11 DP 364444
 CT 261821
 THE LAKES 2012 LTD 84.8420ha
 LOT 6 DP 348694
 CT 208364
 THE LAKES 2012 LTD 0.8700ha
 PT LOT 103 DP 408042
 CT 428562
 THE LAKES 2012 LTD 19.0821ha
TOTAL 104.7741ha
- PROPOSED TITLES**
 LOTS 801-890 & 1-774
 (864 RESIDENTIAL LOTS) 51.8939ha
 LOTS 900-919
 (20 ROADS TO WEST) 18.8563ha
 LOTS 930-952 & PT LOT 9
 (18 RESERVES TO WEST) 29.4958ha
 LOTS 960-991
 (28 PRIVATE ACCESS LOTS) 1.0528ha
 LOT 790
 (LARGE LOT) 3.1990ha
 STAGE 2N LOTS FROM PARENT
 TITLE (1061 & 1065) 0.1331ha
TOTAL 104.6009ha
- AREAS & DIMENSIONS ARE APPROXIMATE ONLY & ARE SUBJECT TO RESOURCE CONSENT AND LAND TRANSFER SURVEY.
- REFER SHEETS RC101-RC112 FOR AMALGAMATION CONDITIONS AND MEMORANDUM OF EASEMENTS.
- STAGING LAYOUT SHOWN IS INDICATIVE ONLY. FINAL NUMBER, SIZE AND SEQUENCE OF STAGES MAY VARY.



ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
 ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERS CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

REV	REVISIONS	BY	DATE
7	REVISED LOT LAYOUTS IN STAGES 3A, B, C, D, & N	RJM	25.03.14
6	MINOR CHANGES TO STAGE PLANS	RJM	15.02.14
5	REVISED DORSET LOT LAYOUT	RJM	16.04.13
4	LOTS 5 & 946 REMOVED SEE DWG'S RC108 - RC110	RJM	14.12.13
3	RESERVE LOTS 932 & 942 REMOVED	RJM	13.12.13
2	DETAILS OF REVISIONS DESCRIBED ON FOLLOWING SHEET FROM	RJM	28.11.13

**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

**PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

DATE:	SCALE:	BY:	PLAT BY:
10.12.12	1:2500 (A1)	RJM	RJM
10.12.12	1:5000 (A3)	RJM	RJM

DATE:	SCALE:	BY:	PLAT DATE:
15.10.12	1:2500 (A1)	RJM	25.02.14
15.10.12	1:5000 (A3)	RJM	25.02.14

DATE:	SCALE:	BY:	PLAT DATE:
15.10.12	1:2500 (A1)	RJM	25.02.14
15.10.12	1:5000 (A3)	RJM	25.02.14

PROJECT No:	SCALE:	BY:	PLAT No:
132631-23-RC101	1:2500 (A1)	RJM	132631-23-RC100
132631-23-RC102	1:5000 (A3)	RJM	132631-23-RC101

APPROVED
 11 APR 2014
PLAN
Selwyn Plan



PT 2
DPS 28192

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 960 HEREON	LOT 960	LOT 802
		LOT 804	
		LOT 805	
		LOT 833	
		LOT 836	
		LOT 837	
		LOT 838	
		LOT 839	
		LOT 840	
		LOT 841	
LOT 842			
LOT 843			
LOT 854			
LOT 855			

PROPOSED MEMORANDUM OF EASEMENT IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
RIGHT OF WAY	LOT 961 HEREON	LOT 965 HEREON	TAURANGA CITY COUNCIL

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 960 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 803, 804, 805 AND 806 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 961 HEREON BE HELD AS TO TEN UNDIVIDED ONE TENTH SHARES BY THE OWNERS OF LOTS 835 - 842, 844 AND 845 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 962 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 854-856 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- BUILDING RESTRICTIONS:**
AREAS SHOWN C - K ARE SUBJECT TO BUILDING RESTRICTIONS. THE LINES SHOWN ARE INDICATIVE ONLY. FINAL BUILDING LINE RESTRICTIONS WILL BE CONFIRMED AT THE TIME OF LEGAL SURVEY.

APPROVED
11 APR 2014
PLAN

R21332-04

HARRISON GRIERSON
Tauranga Office
Level 1, Harbour Centre House
241 Cameron Road, Tauranga 3110
P +64 7 578 0022
www.harrisongrierson.com

9	NEW LOT 933 AREA DUE TO REVISED STAGE 2B LOT BOUNDARY	RUN	30.12.13
8	AMALGAMATION CONDITIONS AND R.O.W. SCHEDULE AMENDED	RUN	01.12.13
7	REMOVAL CHANGES TO ZORST PLANS	RUN	12.07.13
6	EXTENT OF HOUSE WALL AMENDED	RUN	1.07.13
5	REVISED ZORST LOT LAYOUT	RUN	20.04.13
4	BUILDING RESTRICTION LINES ADDED	RUN	20.04.13
3	LOT 912 REMOVED, LOT 933 AREA INCREASED	RUN	11.11.12
REV	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**


TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042**

REGISTRAR	DATE	REGISTERED	FLAT NO	RUN
RUN	30.1.12			
CHANGED	30.1.12			
CHECKED	18.10.12			
APPROVED	DATE	REGISTERED	SURVEY NO	
DCN	18.10.12			

RESOURCE CONSENT
PROJECT No: 1320-132631-01
SCALE: 1:1225 (A3)
1:12250 (A5)
DRAWING No: A1

132631-23-RC101 9

FILE: TAU-RANGA-N:\339\132631_L\CAD\STAGE 2 AND 3\REVISED-23-RC101.DWG



SEC 1
SO 416677

PT 2
DPS 29192

ASSOCIATION OF CONSULTING
ENGINEERS NEW ZEALAND
ISO 9001
QUALITY
ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERS CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 963 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 860 AND 861 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 864 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 864 AND 865 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 965 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 884 AND 885 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- BUILDING RESTRICTIONS:**
AREAS SHOWN G - P ARE SUBJECT TO BUILDING RESTRICTIONS. THE LINES SHOWN ARE INDICATIVE ONLY. FINAL BUILDING LINE RESTRICTIONS WILL BE CONFIRMED AT THE TIME OF LEGAL SURVEY.

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOM, WATER & GAS	LOT 963 HEREOF	LOT 963 HEREOF	LOT 860 LOT 861
	LOT 964 HEREOF	LOT 964 HEREOF	LOT 864 LOT 865
	LOT 965 HEREOF	LOT 965 HEREOF	LOT 884 LOT 885

HC
HARRISON
ENGINEERS
CONSULTANTS
LIMITED

Technical Office
Level 1 Huxford Grifone House
241 Commerce Road Tauranga 3199
P 447 576 000
www.harrisonengineers.com

NO.	DESCRIPTION	BY	DATE
7	NEW LOT 933 AREA DUE TO REVERSED STAGE 2B LOT BOUNDARY	RJM	25.02.14
6	WORK CHANGES TO ASSET PLANS	RJM	11.07.13
5	EXTENT OF FENCE WALL AMENDED	RJM	11.07.13
4	REVERSED 20ST LOT LAYOUT	RJM	18.04.13
3	BUILDING RESTRICTION LINES ADDED	RJM	18.04.13
2	REVERSED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	21.11.12
1	REVISED	BY	DATE

THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M


TITLE:
PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042

OWNER:	DATE:	OWNER:	DATE:
RJM	10.03.12	RJM	25.02.14
RJM	10.03.12	RJM	25.02.14
DNH	19.10.12	DNH	19.10.12
DNH	19.10.12	DNH	19.10.12

RESOURCE CONSENT	
PROJECT NO: 1320-132631-01	SCALE: 1:625 (A1) 1:1250 (A3)
DRAWING NO: 132631-23-RC102	REV 7


APPROVED
11 APR 2014
PLAN
Steve Mc

5
DP 348694



NOTES:

- AMALGAMATION CONDITIONS** THAT LOT 966 HEREOFON BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 29 TO 36 HEREOFON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.



PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 966 HEREOFON	LOT 966 HEREOFON	LOT 29
			LOT 30
			LOT 31
			LOT 32
			LOT 34
			LOT 35
			LOT 36

HC HARRISON ENGINEERS

Tauranga Office
Level 1, Horizon Grange House
341 Cameron Road Tauranga 3110
P 434 7 518 0023
www.harrison-engineers.com

NO	DESCRIPTION	DATE	BY
3	REVISED STAGE 2A, B, C, D & H LAYOUT & ALL LOT NUMBERS	20.02.14	
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVE	20.02.14	
1	ISSUED FOR RESOURCE CONSENT	19.10.12	
REF	REVISIONS		BY DATE

PROJECT: **THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M**

TITLE: **PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042**

NO	DATE	SCORED	FLY BY
REVISION	10.12		RJM
REVISION	10.12		FLY DATE: 25.02.14
DCN	19.10.12		SURVEY BY
DCN	19.10.12		SURVEY DATE

RESOURCE CONSENT

PROJECT No: 1300-132631-01	SCALE: 1:625 (A1)	A1
DRAWING No:	1:1250 (A3)	REV
132631-23-RC103		3

APPROVED
11 APR 2014
PLAN

Selene Pan



ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
 130 0001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF AEC AND MAY NOT BE REPRODUCED OR ADAPTED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIBERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 934 HEREON BE AMALGAMATED WITH SECTION 2 SO 416677 AND ONE COMPUTER REGISTER BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
 11 APR 2014
PLAN

RC2132-04

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOM, WATER & GAS	LOT 934 HEREON	LOT 934 HEREON	LOT 51 SEC 2 SO 416677

HARRISON GRIBERSON
 Tauranga Office
 Level 1 Heritage Greenway House
 141 Coleridge Road Tauranga 3180
 P 0447 578 0023
 www.harrisongriberson.com

THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042

QUANTITY	DATE	DESIGNED	FLY BY
RDW	1.0.12		RDW
RDW	1.0.12		RDW
CHKD	19.10.12		CHKD
APPROVED	19.10.12		APPROVED

RESOURCE CONSENT


13
 6555

PROJECT No: 13263 (A1)
 13263-132631-01
 DRAWING No: 1:1250 (A3)

132631-23-RC104

3

FILE: TAURANGA \P13263\92831_A\CAD\STAGE 2 AND 3\132631-23-RC104.DWG



NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 968 HEREOF BE HELD AS TO TWO UNDIVIDED ONE-HALF SHARES BY THE OWNERS OF LOTS 164 AND 165 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- THAT LOT 970 HEREOF BE HELD AS TO TWO UNDIVIDED ONE-HALF SHARES BY THE OWNERS OF LOTS 251 AND 252 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENTS IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	A	LOT 249 HEREOF	TAURANGA CITY COUNCIL

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 969 HEREOF	LOT 969 HEREOF	LOT 164 LOT 165
	LOT 970 HEREOF	LOT 970 HEREOF	LOT 251 LOT 252

HG HARRISON GRIERSON

Tauranga Office
 Level 1, Harbour Grace House
 241 Cameron Road Tauranga 3110
 P: +64 7 178 9023
 www.harrisongrierson.com

NO	REVISIONS	BY	DATE
1	REVISED STAGE 2A, B, C, D & M LAYOUT & ALL LOT NUMBERS	RJM	25.02.14
2	NEW EASEMENT A PROPOSED OVER WAY 242	RJM	25.02.14
3	REVISED FOR RESOURCE CONSENT	RJM	25.02.14

**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

**TITLE:
 PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

DATE	BY	DATE	BY
DATE: 10.1.12	BY: [Signature]	DATE: 10.3.12	BY: [Signature]
DATE: 19.10.12	BY: [Signature]	DATE: 19.10.12	BY: [Signature]

RESOURCE CONSENT

PROJECT NO: 1320-132631-01	SCALE: 1:625 (A1) 1:1250 (A3)	A1
DRAWING NO: 132631-23-RC105		3

APPROVED
 11 APR 2014
PLAN

132631-23-04

Scheme Plan



PT 2
DPS 30316

SEC 9
SO 344242

2
DPS 53649

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED
OR ALTERED WITHOUT THE WRITTEN PERMISSION OF HARRISON GRADIENT CONSULTANTS
LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

1. AMALGAMATION CONDITIONS

THAT LOT 976 HEREON BE HELD AS TO
THREE UNDIVIDED ONE THIRD SHARES BY
THE OWNERS OF LOTS 378, 379 AND 380
HEREON AS TENANTS IN COMMON IN THE
SAID SHARES AND THAT INDIVIDUAL
COMPUTER REGISTERS BE ISSUED IN
ACCORDANCE THEREWITH.

APPROVED
11 APR 2014
PLAN

**PROPOSED MEMORANDUM OF
EASEMENTS**

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W., RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 976 HEREON	LOT 976 HEREON	LOT 378 LOT 379 LOT 380

HARRISON
ENGINEERS
Tauranga Office
Level 1, Harbour Gateway House
341 Crown Road, Tauranga 3110
P 044 7 59 003
www.harrisoneng.co.nz

NO	DESCRIPTION	DATE	BY
1	REVISED STAGE 3A, 3B & 3M LAYOUT & ALL LOT NUMBERS	25.02.14	RM
2	LOT 942 REMOVED, LOT 468 REVISED FOR RESERVE	25.02.14	RM
3	REVISED WINDING FOR VESTING OF OPEN SPACE RESERVES	25.02.14	RM
4	REVISED FOR RESOURCE CONSENT	19.10.12	RM


**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**

**PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042**

NO	DATE	BY	NO	DATE	BY
DESIGNED	19.10.12	RM	FLAT BY		RM
CHECKED	19.10.12	RM	FLAT DATE		25.02.14
APPROVED	19.10.12	DCM	SURVEY BY		
ISSUED	19.10.12	DCM	SURVEY DATE		

PROJECT No	SCALE	DATE	REV
132631-23-RC101	1:625 (A3) 1:1250 (A4)	19.10.12	A1

132631-23-RC107






NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 980 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 524, 525 AND 526 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

R221332-04
APPROVED
 11 APR 2014
PLAN
Steve Plan



PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELEPHONE, WATER & GAS	LOT 980 HEREON	LOT 980 HEREON	LOT 524 LOT 525 LOT 526

HC HARRISON ENGINEERS
 Thauranga Office
 Level 1, Harbour Gravelton House
 241 Cameron Road Thauranga 3110
 P 441 778 000
 www.harrisoengineers.com

NO	REVISIONS	BY	DATE
1	REVISED STAGE 1A, B, C, D & H LAYOUT & ALL LOT NUMBERS	RJM	25.01.14
2	REVISED STAGE 1A, B, C, D & H LAYOUT & ALL LOT NUMBERS	RJM	14.02.14
3	AREA OF LOT 945 INCREASED	RJM	13.02.14
4	REVISED WORKING FOR VESTING CIP OPEN SPACE RESERVES	RJM	21.01.14
5	ISSUED FOR RESOURCE CONSENT	RJM	18.01.14

**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

**TITLE:
 PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

DESIGNER	DATE	SIGNED	FLAT BY
RJM	10.12		RJM
DRAWN	DATE	SIGNED	FLAT DATE
RJM	10.12		25.02.14
CHECKED	DATE	SIGNED	SURVEY BY
DCK	18.10.12		
APPROVED	DATE	SIGNED	SURVEY DATE
DCK	29.10.12		

RESOURCE CONSENT

PROJECT NO:	SCALE:	REV
1820-122651-01	1:625 (A1) 1:1250 (A0)	A1
DRAWING NO:		REV
132631-23-RC108		5

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERING CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

1. AMALGAMATION CONDITIONS

THAT LOT 978 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 502 AND 503 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 979 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 506 AND 507 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 981 HEREON BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 564 TO 571 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENT IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
PEDESTRIAN ACCESSWAY	E	LOT 790 HEREON	TAURANGA CITY COUNCIL
		LOT 981 HEREON	

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM, WATER & GAS		LOT 978 HEREON	LOT 892 LOT 893
		LOT 979 HEREON	LOT 896 LOT 897
		LOT 981 HEREON	LOT 564 LOT 565 LOT 566 LOT 567 LOT 568 LOT 569 LOT 570 LOT 571
		LOT 981 HEREON	LOT 564 LOT 565 LOT 566 LOT 567 LOT 568 LOT 569 LOT 570 LOT 571
		LOT 981 HEREON	LOT 564 LOT 565 LOT 566 LOT 567 LOT 568 LOT 569 LOT 570 LOT 571
		LOT 981 HEREON	LOT 564 LOT 565 LOT 566 LOT 567 LOT 568 LOT 569 LOT 570 LOT 571

HC
HARRISON ENGINEERING

Tauranga Office
Level 4, Harbour Gateway House
241 Cameron Road Tauranga 3110
P +64 7 576 8025
www.harrison-engineering.com


NO	REVISIONS	DATE	BY	DATE
5	REVISED STAGE 2A, C, D, G & H LAYOUT & ALL LOT NUMBERS		RJM	28.02.14
4	PEDESTRIAN ACCESS OVER LOT 981 PROVIDED		RJM	21.02.14
3	LOT 981 REFINED FROM THAT OF LOT 790		RJM	21.02.14
2	REVISED WORKING FOR VISIBILITY OF OPEN SPACE RESERVE		RJM	21.02.14
1	ISSUED FOR RESOURCE CONSENT		RJM	21.02.14


PROJECT: **THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M**

TITLE: **PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042**

CONTRIBUTOR	DATE	APPROVED	FLAT BY	DATE
RJM	10.12.12		RJM	
RJM	10.12.12			28.02.14
RJM	15.08.12			
DCM	15.10.12			
DCM	15.10.12			

RESOURCE CONSENT			
PROJECT No:	132631-01	SCALE:	1:625 (A3)
DRAWING No:	132631-23-RC109	SCALE:	1:1250 (A3)
			A1
			REV 5





THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERING CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 982 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 580 TO 593 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 983 HEREON BE HELD AS TO TWELVE UNDIVIDED ONE TWELFTH SHARES BY THE OWNERS OF LOTS 607 TO 618 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 984 HEREON BE HELD AS TO SEVEN UNDIVIDED ONE SEVENTH SHARES BY THE OWNERS OF LOTS 621 TO 627 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.


APPROVED
 11 APR 2014
 PLAN



Teanga Office:
 Level 1 Harrison Greenway House
 241 Casswell Road Teanga 3119
 P +64 7 518 0023
 www.harrisonengineers.com

PROPOSED MEMORANDUM OF EASEMENTS			
PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W. RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOMM, WATER & GAS	LOT 982 HEREON	LOT 982 HEREON	LOT 590
			LOT 591
			LOT 592
			LOT 593
			LOT 607
			LOT 608
			LOT 609
			LOT 610
			LOT 611
			LOT 612
LOT 983 HEREON	LOT 983 HEREON	LOT 613	
		LOT 614	
		LOT 615	
		LOT 616	
		LOT 617	
		LOT 618	
		LOT 621	
		LOT 622	
		LOT 623	
		LOT 624	
LOT 984 HEREON	LOT 984 HEREON	LOT 625	
		LOT 626	
		LOT 627	

4	REVISED STAGE 3A, C, D & H LAYOUT & ALL LOT NUMBERS	RUN	25.08.14
3	LOT 982 REMOVED, NOW PART OF LOT 981	RUN	24.10.13
2	AREA 8 ADDED AS GREEN BELT LAND CONTAMINANT	RUN	23.10.13
1	ISSUED FOR RESOURCE CONSENT	RUN	04.10.13
DATE			
PROJECT:			
THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M			
TITLE: PROPOSED SUBDIVISION OF PT LOTS 10 & 11 DP 364444 & PT LOT 103 DP 408042			
ORIGINATOR:	DATE:	DRAWN:	PILOT BY:
RUN	1.0.12	RUN	RUN
DRAWN:	DATE:	ISSUED:	PILOT DATE:
RUN	3.0.12	RUN	25.02.14
CHECKED:	DATE:	ISSUED:	ISSUED BY:
DCN	19.10.12	RUN	RUN
APPROVED:	DATE:	ISSUED:	ISSUED DATE:
DCI	19.10.12	RUN	RUN
ISSUE BY/DATE:			
RESOURCE CONSENT			
PROJECT No:	SCALE:	DATE:	REV
132631-23-RC110	1:625 (A3)	1:1250 (A3)	A1
DRAWING No:			REV
132631-23-RC110			4



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GREENBERG CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 985 HEREOF BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 644, 645 AND 646 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 986 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 665 AND 666 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

AC21372-04
APPROVED
 11 APR 2014
PLAN
S. L. M. Plan

PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOM., WATER & GAS	LOT 985 HEREOF	LOT 986 HEREOF	LOT 644 LOT 645 LOT 646
	LOT 986 HEREOF	LOT 986 HEREOF	LOT 665 LOT 666
		LOT 661	LOT 660
		LOT 659	LOT 658
		LOT 657	

HG
 HARRISON GREENBERG
 Tauranga Office
 Level 1, Harrison Greenberg House
 241 Cameron Road Tauranga 3100
 P +64 7 576 0023
 www.harrisongreenberg.com

REV	REVISIONS	BY	DATE
3	REVISED STAGE 3A, B, C, D & N LAYOUT & ALL LOT NUMBERS	RJM	25.02.14
2	REVISED WORKING FOR VERIFYING OF OPEN SPACE RESERVES	RJM	21.11.13
1	ISSUED FOR RESOURCE CONSENT	RJM	18.10.13

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 10 & 11 DP 364444
 & PT LOT 103 DP 408042**

DESIGNED:	DATE:	SCALE:	FLY BY:
RJM	1.0.12		RJM
DRAWN:	DATE:	SCALE:	FLY DATE:
RJM	1.0.12		25.02.14
CHECKED:	DATE:	SCALE:	SURVEY BY:
DCN	19.10.13		
APPROVED:	DATE:	SCALE:	SURVEY DATE:
DCN	19.10.13		

RESOURCE CONSENT		
PROJECT No:	SCALE:	A1
1520-132631-01	1:625 (A1) 1:1250 (A3)	
DRAWING No:		REV
132631-23-RC111		3



PYES PA RD (SH 36)
LEGAL ROAD

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIBBSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 987 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 696 AND 697 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 988 HEREOF BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 700 AND 701 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 989 HEREOF BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 718, 719 & 720 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 991 HEREOF BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 724 TO 727 HEREOF AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

APPROVED
11 APR 2014
PLAN

HARRISON GRIBBSON
Tauranga Office
Level 1, Harbour Grison House
141 Cameron Road, Tauranga 3110
P: 04 7 576 9023
www.harrisongribbson.com

3	REVISED STAGE 2A, B, C, D & E LAYOUT & ALL LOT DIMENSIONS	RJM	25.02.14
2	REVISED LOT LAYOUT	RJM	25.02.14
1	ISSUED FOR RESOURCE CONSENT	RJM	25.02.14
REF	REVISIONS	BY	DATE


PROJECT:
**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 10 & 11 DP 364444
& PT LOT 103 DP 408042**

OWNER:	DATE:	ISSUED:	PLUT BY:
RJM	1.0.12		RJM
DRAWN:	DRAWN:	DATE:	PLUT DATE:
RJM	RJM	1.0.12	25.02.14
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCH	28.10.12		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCH	15.10.12		

RESOURCE CONSENT
PROJECT NO: 1590-132631-01
SCALE: 1:625 (A1)
1:1250 (A3)
DRAWING NO: 132631-23-RC112

REV 3




PROPOSED MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
R.O.W, RIGHT TO DRAIN STORMWATER AND SEWAGE, RIGHT TO CONVEY ELECTRICITY, TELECOM, WATER & GAS	LOT 987 HEREOF	LOT 987 HEREOF	LOT 696 HEREOF
	LOT 988 HEREOF	LOT 988 HEREOF	LOT 700 HEREOF
	LOT 989 HEREOF	LOT 989 HEREOF	LOT 714 HEREOF
	LOT 990 HEREOF	LOT 990 HEREOF	LOT 718 HEREOF
	LOT 991 HEREOF	LOT 991 HEREOF	LOT 724 HEREOF
			LOT 720 HEREOF
			LOT 725 HEREOF
			LOT 726 HEREOF
			LOT 727 HEREOF
			LOT 728 HEREOF

1
DP 370187

NOTES:

- EXISTING TITLES**
 PT LOTS 9-11 DP 364444
 CT 261821
 THE LAKES 2012 LTD 04.8420ha
 LOT 6 DP 348694
 CT 209384
 THE LAKES 2012 LTD 0.8700ha
 PT LOT 103 DP 408042
 CT 428562
 THE LAKES 2012 LTD 18.0621ha
TOTAL 104.7741ha
- PROPOSED TITLES**
 LOTS 801-890 & 1-774
 (864 RESIDENTIAL LOTS) 51.8939ha
 LOTS 900-919
 (20 ROADS TO WEST) 18.8563ha
 LOTS 920-932 & PT LOT 9
 (19 RESERVES TO WEST) 29.4958ha
 LOTS 960-991
 (29 PRIVATE ACCESS LOTS) 1.0528ha
 LOT 790
 (LARGE LOT) 3.1690ha
 STAGE 2N LOTS FROM PARENT
 TITLE (1061 & 1065) 0.1331ha
TOTAL 104.6009ha
- AREAS & DIMENSIONS ARE APPROXIMATE ONLY & ARE SUBJECT TO RESOURCE CONSENT AND LAND TRANSFER SURVEY.
- REFER SHEETS RC101-RC112 FOR AMALGAMATION CONDITIONS AND MEMORANDUM OF EASEMENTS.
- STAGING LAYOUT SHOWN IS INDICATIVE ONLY. FINAL NUMBER, SIZE AND SEQUENCE OF STAGES MAY VARY.



APPROVED
 11 APR 2014
 PLAN

Schnee Plan

HC HARRISON ENGINEERING

Tauranga Office
 Level 1 Harrison Office House
 141 Cameron Road Tauranga 3110
 P +64 7 578 9023
 www.harrisoneng.co.nz

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALIENED, WITHOUT THE WRITTEN PERMISSION OF HARRISON ENGINEERING CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NO	ISSUED WITH VARIATION TO SHOW EXTENT OF REVISIONS	BY	DATE
1	ISSUED WITH VARIATION TO SHOW EXTENT OF REVISIONS	RHJ	03.03.14

PROJECT: THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M

TITLE: RC21332 SUMMARY OF REVISIONS FOR VARIATION SUBMITTED MARCH 2014

DESCRIPTION	DATE	DESIGNED	FLIGHT BY	R2M
R2M	03.03.14			
DRAWN	03.03.14			
CHECKED	03.03.14			
APPROVED	03.03.14			

ISSUE STATUS: RESOURCE CONSENT

PROJECT NO:	SCALE:	DATE:	REV
1320-132631-01	1:2500 (A1) 1:5000 (A3)	11 APR 2014	1

DRAWING NO: 132631-23-RC500

The Lakes 2012 Limited
C/- Harrison Grierson Consultants Limited
PO Box 1199
Tauranga 3140

DECISION ON CHANGE OF CONDITIONS APPLICATION – RC21332*08
Under the Resource Management Act 1991

That pursuant to Sections 104, 104B, 127 and 108 of the Resource Management Act 1991, the application by The Lakes 2012 Limited to change conditions of subdivision consent RC21332 to provide for a reconfiguration of residential lots with three additional lots created, a revised road and access lot layout, re-alignment of greenbelt and recreation reserve and to impose consent notices on titles to address reverse sensitivity noise effects;

And

To vary the land use consent to allow for future residential development on lots 236, 237 and 238 to be developed in accordance with the Suburban Residential permitted activity rules;

As it relates to land with The Lakes Stage 2 and Stage 3 legally described as Pt Lots 9, 10 and 11 DP 364444 and Pt Lot 103 DP 40802 is granted.

That pursuant to Section 113 of the RMA – the reasons for the decision are as per the recommendation:

The actual and potential effects on the environment of the change have been determined as being acceptable and approving the application will be consistent with the relevant provisions of the Regional Policy Statement and Operative City Plan. Overall the application will be consistent with the purpose and principles of the Act.

Condition 1, 6, 23, 29 and 33 amendments are highlighted as bold red:

1. *The proposal shall proceed in accordance with the application submitted including:*
 - *The Assessment of Environmental Effects prepared by Harrison Grierson Consultants Limited entitled “The Lakes – Balance Stage 2 and Stage 3”, referenced 1520-132631-01, dated October 2012;*
 - *Further Information prepared by Harrison Grierson Consultants Limited entitled “RC21332 – The Lakes – Stage 2/3 Further Information Response”, referenced 1520-132631-01, dated 23 November 2012;*

- Further Information prepared by Harrison Grierson Consultants Limited entitled “Stage 2/3 at The Lakes”, referenced 1520-132631-01, dated 16 December 2012;
- The Landscape Design Company Report dated 26 November 2012;
- The Shrimpton & Lipinski Report entitled “Pyes Pa West Urbanisation Development, Tauranga – Geotechnical Assessment Report” referenced 16944, dated October 2003;
- The Coffey Geotechnics Report entitled “Geotechnical Assessment Report – Suitability of Site for Residential Subdivision The Lakes Subdivision – Stages 2 & 3, Tauriko, Tauranga”, referenced GENZTAUC13086AD, dated 17 August 2012;
- The Archaeology Report prepared by Heritage Consultants entitled “Preliminary Archaeological Survey and Assessment of Effects – Proposed Residential Subdivision and Roding Development”, dated April 2003;
- The Emails received by Council from David Needham sent at;
 - 3:41pm on 26 November 2012;
 - 8:30am on 27 November 2012;
 - 11:23am on 28 November 2012;
 - 11:08am on 28 November 2012;
 - 10:14am on 18 December 2012;
 - 2:54pm on 19 December 2012;
 - 9:51am on 21 December 012;
- Except where varied by the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-132631-01, dated June 2013 and Further Information received by Council dated 19 July 2013; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-133562-02 dated 9 October 2013 and the Further Information email received by Council from David Needham sent at 12:44pm on 31 October 2013; and the Hegley Acoustic Consultants report dated 1 July 2013; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1510-133562-02 dated 9 December 2013; and s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-135959-01 dated March 2014; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1510-135959-01 dated 10 February 2015; and the Hegley Acoustic Consultants report dated 10 December 2015; and the s127 Variation to Consent Application prepared by Harrison Grierson Consultants Limited referenced 1520-137966-01, dated May 2015; and the Hegley Acoustic Consultants report dated 2 June 2015;
- The Scheme Plans prepared by Harrison Grierson Consultants Limited ~~entitled “Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042”~~ referenced;
 - 132631-23-RC100, ~~rev 7 8, dated 25 February 2014~~ **26 May 2015;**
 - 132631-23-RC101, ~~rev 9 10 dated 25 February 2014~~ **26 May 2015;**
 - 132631-23-RC102, ~~rev 7 8 dated 25 February 2014~~ **26 May 2015;**
 - 132631-23-RC103, ~~rev 3 4 dated 25 February 2014~~ **26 May 2015;**
 - 132631-23-RC104, ~~rev 3 5 dated 25 February 2014~~ **26 June 2015;**

- 132631-23-RC105, rev 3 4 dated 25 February 2014 26 May 2015;
- 132631-23-RC106, rev 3 5 dated 25 February 2014 24 June 2015;
- 132631-23-RC107, rev 4 5 dated 25 February 2014 26 May 2015;
- 132631-23-RC108, rev 5 7 dated 25 February 2014 24 June 2015;
- 132631-23-RC109, rev 5 7 dated 25 February 2014 24 June 2015;
- 132631-23-RC110, rev 4 6 dated 25 February 2014 24 June 2015;
- 132631-23-RC112, rev 3 5 dated 25 February 2014 24 June 2015;
- 132631-23-RC500 502, rev 1 dated 2 March 2014 20 May 2015;

And comply with either one of the following Scheme Plan options;

Option A

- The Scheme Plan prepared by Harrison Grierson Consultants Limited entitled "~~Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042~~ referenced 132631-23-RC111, rev 3 5, dated 25 February 2014 24 June 2015; or

Option B

- The Scheme Plan prepared by Harrison Grierson Consultants Limited entitled "Proposed Subdivision of Part Lots 10 & 11 DP 364444 & Pt Lot 103 DP 408042 referenced 132631-23-RC400, rev 2, dated 5 December 2012 (disregarding Lot 951 which has been subject to area increase);
- The following Plans prepared by Harrison Grierson Consultants Limited;
 - "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012;
 - "Proposed Pedestrian and Shared Pedestrian/Cycleway Network", referenced 132631-23-RC202, rev 2, dated 27 November 2012;
 - "Proposed Road Profiles", referenced 132631-23-RC203, rev 2 dated 19 November 2012;
 - "Proposed Finish Contours", referenced 132631-23-RC200, rev 1, dated 19 October 2012;
 - "Indicative Earthworks Remaining Cut/ Fill Depths", referenced 132631-23-RC201, rev 1, dated 19 October 2012;
 - "Bus Tracking Curves 12.5m Rigid Bus", referenced 132631-23-RC204, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Stormwater Plan", referenced 132631-23-RC210, rev 2, dated 18 December 2012;
 - "Proposed Trunk Services Sanitary Sewer Plan", referenced 132631-23-RC211, rev 1, dated 19 October 2012;
 - "Proposed Trunk Services Potable Water Plan", referenced 132631-23-RC212, rev 1, dated 19 October 2012;
 - "Proposed Layout Overlaying City Plan L86", referenced 132631-23-RC300, rev 2, dated 17 June 2013;
 - "Proposed Layout Overlaying City Plan L95", referenced 132631-23-RC301, rev 2, dated 17 June 2013;
 - Stage 2 and 3 Reduced Developable Areas Based on Revised Reserve Slopes" referenced 132631-23-RC303, rev 2, dated 17 June 2013.

Subject to any changes required through compliance with the following conditions

*Noting Condition 1 as amended through s127 Variation to Resource Consent granted 24 July 2013 – TCC Ref 21332*01 and subsequent s127 Variations to Consent granted 7 November 2013 – TCC Ref 21332*02 and 28 January 2014 – TCC Ref 21332*03, and 11 April 2014 – RCC Ref 21332*04 and 16 March 2015 – TCC Ref 21332*06 with amendments to consent condition underlined. New changes to the condition are highlighted in bold red.*

2. *Any staging of subdivision consent by way of s223/224 certificates issued on separate survey for this subdivision is appropriate subject to that staging complying with all relevant conditions as listed for that stage within this subdivision consent.*
3. *All matters and works relating to the servicing and accessing of the subdivision, shall be designed, supervised, constructed and certified in accordance with requirements of the Council's' Infrastructure Development Code.*
4. *Prior to any works commencing on the site (exclusive of site clearance or bulk earthworks associated with any Bay of Plenty Regional Council earthworks consent) the consent holder shall submit, to the Council, plans of the proposed activity to and obtain plan approval. Including the following:*
 - *The information and plans required by the Infrastructure Development Code;*
 - *All potential run out areas;*
 - *All flood risk areas;*
 - *Details of any overland flowpaths;*
 - *Details of the works to establish a suitable building platform on each proposed lot;*
 - *Details of the construction of the road to vest and the proposed traffic management measures;*
 - *Details of the construction for all Right of Way lots;*
 - *Details of the sewer extension that is required to service the upstream catchment;*
 - *Details of proposed temporary sanitary sewer pump station;*
 - *Details of design and construction of Detention Ponds and Dams demonstrating the peak flow mitigation required, and how maintenance access is achieved;*
 - *Details of the extent of ponding in extreme rainfall events;*
 - *Details of any culvert upgrade required under proposed roads to vest;*
 - *Details of Fire Fighting system;*
 - *Details of landscaping and planting within Road to vest;*
 - *Details of landscaping and planting of Greenbelt Reserves to vest;*
 - *Details of Recreation Reserves to vest, including development of playgrounds and landscaping (with structural retaining of slopes, accessibility of pathways, featured paving and structural and play equipment to similar standard as illustrated in Photographs received by Council on 18 December 2012);*
 - *Details of construction of pedestrian accessways*

*Condition 4 as amended through s127 Variation to Resource Consent granted 11 April 2014 – TCC Ref 21332*04. Amendments to consent condition underlined.*

5. *All residential lots shall be provided with a separate underground connection to the sanitary sewer, stormwater, water and electricity reticulation system in accordance with the Council's Infrastructure Development Code*
6. *The proposed Right of Way lots 934, 960-9942 inclusive (and lot 992 if Scheme Plan Option B prepared by Harrison Grierson Consultants Limited referenced 132631-23-RC400, rev 2, dated 5 December 2012 proceeds) shall be constructed in accordance with the Infrastructure Development Code.*
7. *Prior to the first application for s224 approval, the Kennedy Road Waste Water Pump Station shall be complete and operational.*
8. *All lots with a building platform higher than RL40m Moturiki Datum shall be fed from the Joyce Road water supply.*
9. *Where landscaping is proposed on land to be vested as local purpose Greenbelt reserve or Recreation reserve, the landscaping shall be established and maintained at the consent holders expense. The landscaping shall be maintained for not less than 36 months for Greenbelt and 18 months for Recreation reserve from the date of completion. The date of completion shall be agreed with Council. A maintenance bond shall be entered into should vesting occur prior to completion of the maintenance period.*
10. *The consent holder shall supply to the Council a set of 'as built' plans of all engineering works in accordance with the Council's Infrastructure Development Code.*
11. *The location of any subsoil drains shall be shown on the as-built drawings submitted to the Council and within the geotechnical completion report required by Condition 16.*
12. *All earthworks design, testing and construction shall be undertaken in accordance with Infrastructure Development Code and the specific requirements of the consent holders appointed Geo-Professional.*
13. *Where earthworks and/or pre-load operations occur over the Council's mains the consent holder shall undertake a CCTV survey of the mains prior to, and upon completion of the earthworks and/or pre-load operations. Monitoring shall continue at regular intervals during the earthworks and pre-load phases of the project as an ongoing check of the condition of the mains and to ensure their serviceability. If damage occurs to the mains during the earthworks and/or pre-load operations the Council will repair the mains at the consent holder's expense, with any payment for repairs or losses arising as a result of the damage shall be paid prior to certification pursuant to Section 224.*
14. *The Consent Holder shall construct a building platform on each proposed lot to avoid the effects of inundation. The platform shall be a minimum of 500mm above the calculated 50 year (2%AEP) storm level.*
15. *Prior to any earthworks which will increase the stormwater runoff into adjoining catchments, the detention dams and/or ponds required to provide peak flow attenuation shall be in operation.*

16. *The Consent Holder shall provide to the Council a "Geotechnical Completion Report" complied by a Category 1 Geo-Professional. The report shall:*
- *Comply with the Council's Infrastructure Development Code QA4 requirements;*
 - *Display the position of all designated building platforms and building restriction lines where applicable;*
 - *Certify the provision of debris protection bunds where required;*
 - *Provide recommendations for the disposal of stormwater;*
 - *Provide recommendations for the on going development of the lots (i.e. maximum cut/fill heights, management of steep slopes, etc.);*
 - *Confirm earthworks and/or building platforms have been constructed to comply with the New Zealand Building Code requirements;*
 - *Determine minimum floor level requirements for lots adjacent to stormwater ponding areas;*
 - *Certify that any residual settlement or differential settlement that may still occur shall not exceed the manufacturer's recommendations with respect to the installed underground pipe networks to be vested in Council or exceed accepted design techniques with respect to road settlement or long term deflection, or exceed the settlement limitations as detailed in the New Zealand Building Code;*
 - *Comment on removal or amendment of existing land feature/s displayed on Council's GIS.*
17. *Pursuant to Section 128 of the Resource Management Act 1991, the Council may review this condition, upon receipt of the "Geotechnical Completion Report", and require a Consent Notice to be registered on the Certificate of Title of any allotments to which the recommendations of the "Geotechnical Completion Report" relate to.*
18. *All building line restrictions or designated building platforms shall be clearly identified and dimensioned on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.*
19. *The consent holder shall, prior to the release of the s223 certificate for the subdivision or any stage of the subdivision, submit to Council's Corporate Information Section three alternative street names for authorisation in accordance with Council's Street Naming Policy (including Iwi consultation), for each proposed new street and lane in the subdivision. The authorised street name signs will be manufactured and erected by the consent holder at the consent holder's expense. All traffic and pedestrian access signage shall be manufactured by an approved certifier and erected by the consent holder at the consent holder's expense.*
20. *All easements required for underground services and rights of way serving lots within the subdivision shall be duly granted or reserved.*
21. *The consent holder shall register an easement in gross in favour of the Council over any stormwater overland flowpath located on private property, including those resulting from overload of the roading primary stormwater system under extreme rainfall conditions.*
22. *The overland flowpath easement shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 and shall be shown as the "Right to Drain Stormwater" and shall be registered on the survey plan under a "Memorandum of Easements in Gross".*

23. The consent holder shall vest in the Council the following lots as shown on the scheme plan:

- Lots 900 to 919 920 inclusive as Road;
- Lots 930, 935, 938, 940, 944, 950 and 952 as Recreation Reserves;
- Lots 932, 933, 943, 945, 948, 949, 951 and Pt Lot 9 DP364444 as Local Purpose: Greenbelt Reserves;
- Lots 931, 936, 937 and 941 as Local Purpose: Accessway Reserves;
- Lot 947 as Local Purpose: Waste Water Reserve;

The lots to vest shall be shown on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991.

Condition 23 as amended through s127 Variations to Resource Consent granted 24 July 2013 – TCC Ref 21332*01 and 11 April 2014 TCC Ref 21332*04. Amendments to consent condition underlined.

24. Prior to vesting of lot 947, the consent holder shall enter into a bond for removal of the temporary waste water pump station and associated Infrastructure. Should modification of the structure plan result in the pump station forming part of the permanent network, then a bond will not be required.

25. Pursuant to Section 221 of the Resource Management Act 1991, a consent notice shall be registered on the Certificate of Title of any property that shares a common boundary with any of the following local purpose reserves:

- Accessway
- Recreation
- Drainage
- Waste Water
- Stormwater
- Greenbelt

The consent notice shall advise the owners and subsequent owners thereof, of the following requirement to be complied with on a continuing basis: The owners are required to meet the full cost of any fencing along the common boundary between the lot and adjoining land that are intended to be vested in Tauranga City Council as local purpose reserve.

26. Upon application for the s223 certificate for the subdivision the consent holder shall confirm in writing to Council which property boundaries require a fencing consent notice to be registered on its title.

27. Prior to bulk earthworks being undertaken within 100m of the area marked potential "HAIL Site" on the Harrison Grierson Plan entitled "Plan of Previous Buildings and Proposed Buffer Zone For Contamination Assessment", referenced 132631-23-RC205, rev 1, dated 23 November 2012, a site investigation report prepared by a suitably qualified professional in accordance with 'Guideline No.1 – Reporting on Contaminated Sites in New Zealand, Ministry for the Environment' is required to be provided to Council's Manager of Environmental Planning. The site investigation report shall identify and quantify any soil contamination, and any remediation works necessary (if any). Prior to lodgement of s224 application in relation

to the above land area, any remediation works required to address contaminated soil shall be undertaken. Note, that a land use consent under the City Plan addressing contaminated soil will be required if the site investigation report determines it to be contaminated.

28. That before the commencement of any ground disturbance associated with the proposed development within Stages 3H, 3F and Lot 949 (Local Purpose Reserve:Greenbelt), an authority to modify damage or destroy U14/_1915 and U14_2166 and possible unrecorded subsurface archaeological sites from the New Zealand Historical Places Trust is to be obtained under the provisions of Section 12 of the Historic Places Act 1993. Ngai Tamarawaho Iwi representatives shall also be given 48 hours notice in writing prior to the commencement of earthworks within the abovementioned locations within the subdivision.
29. The amalgamation conditions referenced within the Scheme Plans listed within Condition 1 shall be recorded on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 (LINZ Request~~s~~: **1300709 1114213 & subsequent LINZ Requests 1152384 & 1191724 & 1204864 for plans associated with consent variations.**)

The following amalgamation condition shall also be recorded on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act 1991 (LINZ Request 1276588):

“That Lot 890 be transferred to the owner of Lot 1 DP 474511 (CT651657) and that one computer register be issued to include both parcels.”

Note, the amalgamation of Lot 1 DP 474511 and Lot 890 is only required until subsequent s223/s224 certification has occurred to create consented lots 868, 869, 870 and 890.

Condition 29 as amended through s127 Variation to Resource Consent granted 24 July 2013 – TCC Ref 21332*01, 28 January 2014 – TCC Ref 21332*03 and 11 April 2014 – TCC Ref 21332*04 and 16 March 2015 – TCC Ref 21332*06 with amendments to consent condition underlined. New changes to the condition are highlighted in bold red.

30. That a shared cycleway/walkway is to be constructed within the State Highway designation from Pyes Pa Road to link with the Collector Road within the site which is denoted as part of a potential future cycleway/walkway within the Harrison Grierson Plan entitled “Proposed Pedestrian and Shared Pedestrian/Cycleway Network”, referenced 132631-23-RC202, rev 2, dated 27 November 2012. The timing and design of construction of the cycleway /walkway within the State Highway (Pyes Pa Bypass) will require approval under s176 of the Resource Management Act 1991. The final approval of construction drawings will be required from New Zealand Transport Agency State Highway Manager: Bay of Plenty.
31. The subdivision consent has a term of 15 years to complete from the date in which it has been granted.
32. All costs associated with the conditions of this consent, including those required under the Council's' Infrastructure Development Code, shall be met by the consent holder.

33. Pursuant to Section 221 of the Resource Management Act 1991, a consent notice shall be registered on the Certificate of Titles of the following Lots advising the owners and subsequent owners thereof of the requirements to be complied with on a continuing basis:

For Lots 855, 856, 860, 861, 864, 865, 867, 868, 869 and 870

- a) An acoustic fence constituting a close board timber fence with battens over the joins as illustrated within Figure 2 of the Hegley Acoustics Consultants report dated 1 July 2013 shall be maintained on the boundary of the lot and the reserve adjacent to State Highway 36 in the location as shown within Figure 1 of the Hegley Acoustics Consultants report dated 1 July 2013. The fencing shall be maintained at all times to ensure its acoustic integrity is maintained.

For Lots 105, 106, 848, 849, 854, 855, 856, 860, 861, 864, 865, 867, 868, 869, 870, 879, ~~and 890~~, 148 to 158, 163, 166, 167, 224, 238 to 248, 255, 258 and 259

- b) Any new dwelling being constructed, or any existing dwelling being extended greater than 25% of the existing floor area, that is above the ground floor level (i.e. being second and/or third storey), shall be designed and constructed to achieve an internal road-traffic design sound level of 40dB_{L_{Aeq(24h)}} inside all habitable rooms with the ventilating windows open.

At the time of building consent application an acoustic design report shall be provided to Council from a suitably qualified and experienced acoustics expert demonstrating compliance with the abovementioned sound level requirement. If this cannot be achieved, then:

The windows of all habitable rooms shall be constructed with glazing that includes a laminated pane that is at least 6.38mm thick and covers the glazed area, and a ventilation system shall be installed to either:

- Consist of an air conditioning unit(s) provided that the noise level generated by the unit(s) must not exceed 40dB_{L_{Aeq(30s)}} in the largest habitable room (excluding bedrooms) and 35dB_{L_{Aeq(30s)}} in all other habitable rooms; when measured 1 metre from any grille or diffuser, or
- A system capable of providing a least 15 air changes per hour in the largest habitable room (excluding bedrooms) and at least 5 air changes per hour in all other habitable rooms, and
- The noise level generated by the system must not exceed 40dB_{L_{Aeq(30s)}} in the largest habitable room (excluding bedrooms) and 35dB_{L_{Aeq(30s)}} in all other habitable rooms; when measured 1 metre from any grille or diffuser, and
- The internal air pressure must be no more than 10 Pa above ambient air pressure due to the mechanical ventilation, and
- Where a high air flow rate setting is provided, the system must be controllable by the occupants to be able to alter the ventilation rate with at least three equal progressive stages up to the high setting.

The above requirements do not apply if it can be demonstrated by way of prediction or measurement by a suitably qualified and experienced acoustic expert that the road-traffic noise level from State Highway 36 is less than 55 dBL_{Aeq(24h)} on all facades of any addition, extension or alteration, or new dwelling which fronts State Highway 36.

For Lots 105 and 106

- c) An acoustic fence constituting a close board timber fence with battens over the joins as illustrated within Figure 2 of the Hegley Acoustics Consultant's report dated 10 December 2014 shall be maintained on the boundary of the lot and the reserve adjacent to State Highway 36 in the location as shown within Figure 1 of the Hegley Acoustics Consultants report dated 10 December 2014. The fencing shall be maintained at all times to ensure its acoustic integrity is maintained.

For Lots 148 to 162 and Lots 237 to 254

- d) **An acoustic fence constituting a close board timber fence with battens over the joins as illustrated within Figure 2 of the Hegley Acoustics Consultant's report dated 2 June 2015 shall be maintained on the boundary of the lot in the location as shown within Figure 1 of the Hegley Acoustics Consultants report dated 2 June 2015. The fencing shall be maintained at all times to ensure its acoustic integrity is maintained.**

For lots 159 to 162 and 249 to 254

- e) **Any new dwelling being constructed, or any existing dwelling being extended greater than 25% shall be designed and constructed to achieve an internal road-traffic design sound level of 40dBL_{Aeq(24h)} inside all habitable rooms with the ventilating windows open.**

At the time of building consent application an acoustic design report shall be provided to Council from a suitably qualified and experienced acoustics expert demonstrating compliance with the abovementioned sound level requirement. If this cannot be achieved, then:

The windows of all habitable rooms shall be constructed with glazing that includes a laminated pane that is at least 6.38mm thick and covers the glazed area, and a ventilation system shall be installed to either:


- Consist of an air conditioning unit(s) provided that the noise level generated by the unit(s) must not exceed 40dBL_{Aeq(30s)} in the largest habitable room (excluding bedrooms) and 35dBL_{Aeq(30s)} in all other habitable rooms; when measured 1 metre from any grille or diffuser, or**
- A system capable of providing a least 15 air changes per hour in the largest habitable room (excluding bedrooms) and at least 5 air changes per hour in all other habitable rooms, and**

- **The noise level generated by the system must not exceed 40dBL_{Aeq(30s)} in the largest habitable room (excluding bedrooms) and 35dBL_{Aeq(30s)} in all other habitable rooms; when measured 1 metre from any grille or diffuser, and**
- **The internal air pressure must be no more than 10 Pa above ambient air pressure due to the mechanical ventilation, and**
- **Where a high air flow rate setting is provided, the system must be controllable by the occupants to be able to alter the ventilation rate with at least three equal progressive stages up to the high setting.**

The above requirements do not apply if it can be demonstrated by way of prediction or measurement by a suitably qualified and experienced acoustic expert that the road-traffic noise level from State Highway 36 is less than 55 dBL_{Aeq(24h)} on all facades of any addition, extension or alteration, or new dwelling which fronts State Highway 36.

*Condition 33 Imposed through s127 Variation to Consent granted 7 November 2013 - TCC Ref 21332*02, and 16 March 2015 – TCC Ref 21332*06 with amendments to consent condition underlined. Consent condition underlined. The new changes to condition are highlighted in bold red.*

Recommended and Assessed by:


James Jacobs
Intermediate Environmental Planner

Delegated Authorisation by:


Lee Dove
Senior Environmental Planner

Date: 13/7/2015

Advice Notes

1. Under RMA s357, you can object to this consent by serving written notice on the Council within 15 working days of receiving this decision, detailing the reasons for the objection.
2. Should the actual processing cost exceed the deposit fee paid at lodgement, if not already accompanying this decision, an invoice may be sent at a later date.
3. Development contributions under LGA 2002 –

Requirement for development contribution: Pursuant to section 198(1)(a) of the Local Government Act 2002, Council requires that a development contribution provided for and in accordance with Council's Development Contributions Policy (which is subject to change), be made (paid) by the consent holder to Council.

Calculation and payment: Council's Development Contributions Policy currently provides that the required development contribution is:


- determined in accordance with Table 2 of Schedule 1 of the Policy in force at the time this subdivision consent is granted; and
- payable immediately before the section 224 completion certificate is released, and that the certificate will not be released until the contribution is paid in full to Council.

Postponement or remission: Council's Development Contributions Policy currently provides that there will be no postponement or remission of development contributions except in exceptional circumstances at the discretion of Council's Chief Executive or in the special circumstances outlined in Council's Development Contributions Policy.

*Advice Note 3 as amended through s127 Variation to Resource Consent granted 28 January 2014 – TCC Ref 21332*03.*


4. *All archaeological sites whether recorded or unrecorded under Part 1 of the Historic Places Act 1993 cannot be destroyed, damaged or modified without the consent of the Historic Places Trust of New Zealand. In the event that an archaeological site(s) and/or koiwi are unearthed, the consent holder is advised to immediately stop work on the part of the site that the archaeological site(s) is located, and contact the Historic Places Trust for advice.*
5. *Construction noise from starting up and operation of construction equipment and all other construction activities on the site of the subdivision are required to meet the limits recommended in Table 1 in NZS6803:1999, and shall be measured and assessed in accordance with, NZS6803P:1984 - "The measurement and assessment of noise from construction, maintenance and demolition work". Adjustments provided in Clause 6.1 of NZS6803P:1984 shall apply for the full duration of the project, and references in the tables to NZS6802 shall read as references to Clause 4.2.2 of NZS6802:1991.*
6. *Where any building or drainage works are required to satisfy conditions of this consent, all consents required under the Building Act 2004 must be obtained prior to the works being carried out.*
7. *Dust management and silt runoff is to be controlled in accordance with the City Plan and the Infrastructure Development Code. The Consent Holder is advised that they are required by Bay of Plenty Regional Councils Land Management Plan to take the appropriate measures to prevent or minimise sediment generation and yield (sediment discharge).*
8. *Noise attenuation treatment within State Highway 36 shall be implemented in accordance with the 'Agreement in respect of the Funding and Construction of Noise Attenuation Barriers along Pyes Pa Bypass (Takitimu Drive Extension)' dated November 2010.*
9. *Where land to be vested is subject to a specified interest that is proposed to remain, the Council may certify that interest on the survey plan, pursuant to section 239(2) of the Resource Management Act 1991.*
10. *The consent provides approvals to both layouts in Stage 3K. Should Tauranga City Council wish the applicant to pursue Option B then they recognise that they will need to confirm this to the applicant and confirm how the consent holder will be compensated for implementing this option. The consent holder is under no obligation under this consent to pursue Option B.*

11. *Acknowledged is an agreement relating to works in Lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 19 May 2004 and deed of variation of agreement relating to works in lieu of financial contributions and forward funding of infrastructure for Pyes Pa West between TCC and Grasshopper dated 3 March 2006.*
12. *It is considered that the subdivision will be consistent with the Consent Notice 6592047.2 registered on the title of Lot 9 – 11 DP 364444.*



NOTES:

- EXISTING TITLES
PT LOTS 9-11 DP 364444
CT 261821
THE LAKES 2012 LTD 84.8420ha
LOT 6 DP 348694
CT 209384
THE LAKES 2012 LTD 0.8700ha
PT LOT 103 DP 408042
CT 428562
THE LAKES 2012 LTD 19.0621ha
TOTAL 104.7741ha
- PROPOSED TITLES
LOTS 801-890 & 1-777
(867 RESIDENTIAL LOTS) 51.8308ha
LOTS 900-920
(21 ROADS TO VEST) 18.9657ha
LOTS 930-952 & PT LOT 9
(21 RESERVES TO VEST) 29.6506ha
LOTS 960-992
(30 PRIVATE ACCESS LOTS) 1.0023ha
LOT 790 3.1678ha
STAGE 2N LOTS FROM PARENT
TITLE (1061 & 1065) 0.1331ha
TOTAL 104.7703ha
- AREAS & DIMENSIONS ARE APPROXIMATE ONLY & ARE SUBJECT TO RESURVEY CONSENT AND LAND TRANSFER SURVEY.
- REFER SHEETS RC101-RC112 FOR AMALGAMATION CONDITIONS AND MEMORANDUM OF EASEMENTS.
- STAGING LAYOUT SHOWN IS INDICATIVE ONLY. FINAL NUMBER, SIZE AND SEQUENCE OF STAGES MAY VARY.



HG TAURANGA OFFICE
LEVEL 1 HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 978 9022
W www.harrisongrison.com

ACENZ ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NO	REVISION	DATE	BY	DATE
8	REVISED LOT AND ROAD LAYOUTS IN STAGES 2Q, 2T & 3A & 3B	HEH	15/05/15	
7	REVISED LOT LAYOUTS IN STAGES 3A, B, C, D, G & M	RJM	25/04/14	
6	MINOR CHANGES TO 20ST PLANS	RJM	12/07/13	
5	REVISED 20ST LOT LAYOUT	RJM	10/06/13	
4	LOTS 555 & 946 REMOVED SEE DWGS RC108 - RC110	RJM	14/12/12	
3	RESERVE LOTS 932 & 942 REMOVED	RJM	5/12/12	
REF	REVISIONS	BY	DATE	


PROJECT: THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M

TITLE: PROPOSED SUBDIVISION OF PT LOTS 9, 10 & 11 DP 364444, PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR:	DATE:	SIGNED:	PLLOT BY:
RJM	10.1.12		HEH
DRAWN:	DATE:	SIGNED:	PLLOT DATE:
RJM	10.1.12		26.05.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.05.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.05.15		

ISSUE STATUS:		RESOURCE CONSENT	
PROJECT No:	1520-132631-01	SCALES:	1:2500 - A1 1:5000 - A3
DRAWING No:	RC21332-08	PLAN	13 July 2015
			REV 8

Tauranga City Council
APPROVED
Subdivision Consent
PLAN
13 July 2015





PT 2
DPS 29192

NOTES:

1. AMALGAMATION CONDITIONS
 THAT LOT 960 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 803, 804, 805 AND 806 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 961 HEREON BE HELD AS TO TEN UNDIVIDED ONE TENTH SHARES BY THE OWNERS OF LOTS 835 - 842, 844 AND 845 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 962 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 854-856 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
2. BUILDING RESTRICTIONS:
 AREAS SHOWN C - K ARE SUBJECT TO BUILDING RESTRICTIONS. THE LINES SHOWN ARE INDICATIVE ONLY. FINAL BUILDING LINE RESTRICTIONS WILL BE CONFIRMED AT THE TIME OF LEGAL SURVEY.



HG HARRISON GRISSON CONSULTANTS
 TAURANGA OFFICE
 LEVEL 1 HARBOR HARRISON HOUSE
 141 CAMERON ROAD, TAURANGA 3110
 T +64 7 578 0023
 W www.harrisongrisson.com

NO	REVISION	DATE	BY
10	REVISED LOT AND ROAD LAYOUTS IN STAGES 2C, D, E & W, 3 LOT NUMBERS	19/05/15	RJM
9	NEW LOT 933 AREA DUE TO REVISED STAGE 3B LOT BOUNDARY	25/02/14	RJM
8	AMALGAMATION CONDITIONS AND R.O.W. SCHEDULE AMENDED	06/12/13	RJM
7	MINOR CHANGES TO ZQST PLANS	17/07/13	RJM
6	EXTENT OF NOISE WALL AMENDED	13/07/13	RJM
5	REVISED ZQST LOT LAYOUT	10/06/13	RJM
4	BUILDING RESTRICTION LINES ADDED	16/04/13	RJM
REF	REVISIONS	BY	DATE


PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 9, 10 & 11 DP 364444,
 PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR:	DATE:	SIGNED:	PILOT BY:
RJM	10.1.12		MEH
DRAWN:	DATE:	SIGNED:	PILOT DATE:
RJM	10.1.12		26.05.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.05.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.05.15		

ISSUE STATUS:
RESOURCE CONSENT

PROJECT NO:	SCALES:	A1
1520-132631-01	1:625 - A1 1:1250 - A3	
DRAWING NO:	REV	
132631-23-RC101	10	



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 963 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 860 AND 861 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 964 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 864 AND 865 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 965 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 884 AND 885 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
- BUILDING RESTRICTIONS:**
AREAS SHOWN G - P ARE SUBJECT TO BUILDING RESTRICTIONS. THE LINES SHOWN ARE INDICATIVE ONLY. FINAL BUILDING LINE RESTRICTIONS WILL BE CONFIRMED AT THE TIME OF LEGAL SURVEY.

Tauranga City Council

APPROVED
Subdivision Consent
RC21332-08 **PLAN** 13 July 2015

HG TAURANGA OFFICE
LEVEL 1 HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 9023
W www.harrisongrison.com

REV	DESCRIPTION	DATE	BY
8	REVISED LOT AND ROAD LAYOUTS IN STAGES 2Q, 2T, 3A, 3B, 3C, 3D, 3E, 3F, 3G, 3H, 3I, 3J, 3K, 3L, 3M, 3N, 3O, 3P, 3Q, 3R, 3S, 3T, 3U, 3V, 3W, 3X, 3Y, 3Z	15/06/15	HEH
7	NEW LOT 533 AREA DUE TO REVISED STAGE 3B LOT BOUNDARY	25/04/14	RJM
6	MINOR CHANGES TO ZONE PLANS	17/07/13	RJM
5	EXTENT OF NOISE WALL AMENDED	1/07/13	RJM
4	REVISED ZONE LOT LAYOUT	10/06/13	RJM
3	BUILDING RESTRICTION LINES ADDED	16/04/13	RJM
REF	REVISIONS		

PROJECT: THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

TITLE: PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR:	DATE:	SIGNED:	PLOT BY:
RJM	10.1.12		HEH
DRAWN:	DATE:	SIGNED:	PLOT DATE:
RJM	10.1.12		26.05.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	19.05.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	19.05.15		

ISSUE STATUS: **RESOURCE CONSENT**

PROJECT No:	SCALES:	A1
1520-132631-01	1:625 - A1 1:1250 - A3	
DRAWING No:		REV
132631-23-RC102		8



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 966 HEREON BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 29 TO 36 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council

APPROVED
Subdivision Consent
PLAN

RC21332-08 13 July 2015

HG HARRISON GRIERSON
TAURANGA OFFICE
LEVEL 1 HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 0023
W www.harrisongrierson.com


REV	REVISIONS	BY	DATE
4	REVISED LOT AND ROAD LAYOUTS IN STAGES 2Q, D, E & F. 8 LOT NUMBERS	HEH	15.05.15
3	REVISED STAGE 3A, B, C, D & F LAYOUT & ALL LOT NUMBERS	RJM	25.02.14
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	15.10.12


PROJECT: THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M

TITLE: PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR: RJM	DATE: 10.1.2	SIGNED:	PLLOT BY: HEH
DRAWN: RJM	DATE: 10.1.2	SIGNED:	PLLOT DATE: 26.05.15
CHECKED: DCN	DATE: 19.05.15	SIGNED:	SURVEY BY:
APPROVED: DCN	DATE: 19.05.15	SIGNED:	SURVEY DATE:

ISSUE STATUS:		RESOURCE CONSENT	
PROJECT No: 1520-132631-01	SCALES: 1:625 - A1 1:1250 - A3	STATUS:	A1
DRAWING No:		REV	4





THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 934 HEREBE AMALGAMATED WITH SECTION 2 SO 416677 AND ONE COMPUTER REGISTER BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 992 HEREBE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 434 AND 777 HEREBE AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council

APPROVED
Subdivision Consent

RC21332-08 **PLAN** 13 July 2015

HG HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 9023
W www.harrisongrison.com

REV	DESCRIPTION	DATE	BY
5	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
4	REVISED LOT AND ROAD WIDTHS IN STAGES 2Q, 2T & 3A - LOT NUMBERS	HEH	19.05.15
3	REVISED STAGE 3A, C, D, G & M LAYOUT & ALL LOT NUMBERS	RJM	25.02.14
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.10.12
1	ISSUED FOR RESOURCE CONSENT		

PROJECT: **THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M**


TITLE: **PROPOSED SUBDIVISION OF PT LOTS 9, 10 & 11 DP 364444, PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR: RJM	DATE: 10.1.12	SIGNED:	PLAT BY: RJM
DRAWN: RJM	DATE: 10.1.12	SIGNED:	PLAT DATE: 24.06.15
CHECKED: DCN	DATE: 24.06.15	SIGNED:	SURVEY BY:
APPROVED: DCN	DATE: 24.06.15	SIGNED:	SURVEY DATE:

RESOURCE CONSENT

PROJECT No: 1520-132631-01	SCALES: 1:625 - A1 1:1250 - A3	A1
DRAWING No:		REV

132631-23-RC104 5



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 969 HEREBE BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 164 AND 165 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 970 HEREBE BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 256 AND 257 HERON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council

APPROVED
 Subdivision Consent
 RC21332-08 **PLAN** 13 July 2015


 TAURANGA OFFICE
 LEVEL 1 HARRISON GRIERSON HOUSE
 141 CAMERON ROAD TAURANGA 3110
 T +64 4 378 9023
 W www.harrisongrierson.com

REV	REVISIONS	BY	DATE	
4	REVISED LOT AND ROAD LAYOUTS IN STAGES 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000			
3	REVISED STAGE 3A, B, C, D, G & H LAYOUT & ALL LOT NUMBERS	RJM	25.02.14	
2	NEW EASEMENT A PROPOSED OVER LOT 242	RJM	15.11.12	
1	ISSUED FOR RESOURCE CONSENT	RJM	15.10.12	


PROJECT: THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M


TITLE: PROPOSED SUBDIVISION OF
 PT LOTS 9, 10 & 11 DP 364444,
 PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR:	DATE:	SIGNED:	PLOT BY:	HEH
RJM	10.1.2			
RJM	10.1.2			
CHECKED:	DATE:	SIGNED:	SURVEY BY:	
DCN	19.05.15			
APPROVED:	DATE:	SIGNED:	SURVEY DATE:	
DCN	19.05.15			

RESOURCE CONSENT

PROJECT No:	SCALES:	A1
1520-132631-01	1:625 - A1 1:1250 - A3	
DRAWING No:		REV
132631-23-RC105		4





THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

1. **AMALGAMATION CONDITIONS**
THAT LOT 971 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 260 AND 261 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 972 HEREON BE HELD AS TO SIX UNDIVIDED ONE SIXTH SHARES BY THE OWNERS OF LOTS 220 TO 225 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 973 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 236 AND 237 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 974 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 215, 216 AND 217 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council

APPROVED
Subdivision Consent

RC12332-08 **PLAN** 13 July 2015

HG HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 9023
W www.harrisongrison.com

REV	REVISIONS	BY	DATE
1	ISSUED FOR RESOURCE CONSENT		
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES		
3	REVISED STAGE 2A, B, C, D, G & H LAYOUT & ALL LOT NUMBERS		
4	REVISED LOT AND ROAD WIDTHS IN STAGES 2C, D, E, H, I, J, L, O, M, N		
5	REVISED AMALGAMATION CONDITIONS		


PROJECT: THE LAKES 2012 LTD TAURANGA STAGES 2Q - 2T & 3A - 3M

TITLE: PROPOSED SUBDIVISION OF PT LOTS 9, 10 & 11 DP 364444, PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR:	DATE:	SIGNED:	PLOT BY:	RJM
DRAWN:	10.12			
CHECKED:	10.12			
APPROVED:	24.06.15			
ISSUE STATUS:				

RESOURCE CONSENT

PROJECT NO:	SCALES:	A1
1520-132631-01	1:625 - A1 1:1250 - A3	
DRAWING NO:		REV
132631-23-RC106		5



PT 2
DPS 30316

SEC 9
SO 344242



ASSOCIATION OF CONSULTING
ENGINEERS NEW ZEALAND

ISO 9001
QUALITY
ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
THAT LOT 976 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 382, 383 AND 384 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

THAT LOT 977 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 390, 391 AND 392 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council

APPROVED
Subdivision Consent

RC21332-08 **PLAN** 13 July 2015

HG HARRISON GRIERSON

TAURANGA OFFICE
LEVEL 1 HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 0023
W www.harrisongrierson.com


REV	REVISIONS	BY	DATE
5	REVISED LOT AND ROAD LAYOUTS IN STAGES 3C, D, E & M, & LOT NUMBERS	HEH	15/05/15
4	REVISED STAGE 3A, C, D, G & M LAYOUT & ALL LOT NUMBERS	RJM	25/02/14
3	LOT 942 REMOVED, LOT 469 REVISED FOR RESERVE	RJM	05/05/12
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23/11/12
1	ISSUED FOR RESOURCE CONSENT	RJM	15/02/12

THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M


TITLE:
PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694

ORIGINATOR:	DATE:	SIGNED:	PLOT BY:
RJM	10.1.12		HEH
DRAWN:	DATE:	SIGNED:	PLOT DATE:
RJM	10.1.12		26.05.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	15.05.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	15.05.15		

PROJECT NO:	SCALES:	REV
1520-132631-01	1:625 - A1 1:1250 - A3	A1
DRAWING NO:	REV	
132631-23-RC107	5	



REFER TO APPROVED MASTER DRAWINGS FOR ORIGINAL SIGNATURES File: TAURANGA N:\1520\132631_A\CAD\STAGE 2 AND 3\132631-23-RC100.DWG



NOTES:

1. AMALGAMATION CONDITIONS
THAT LOT 980 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 527, 528 AND 529 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.



7	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
6	REVISED LOT AND ROAD LAYOUTS IN STAGES 2Q, D, E, H & LOT NUMBERS	HEH	19.05.15
5	REVISED STAGE 2A, B, C, D, S & M LAYOUT & ALL LOT NUMBERS	RJM	25.02.14
4	LOT 940 REMOVED NEW PART OF LOT 790	RJM	14.12.12
3	AREA OF LOT 945 INCREASED	RJM	5.12.12
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
REF	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**


TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694**


ORIGINATOR:	RJM	DATE:	10.12	SIGNED:		PLotted BY:	RJM
DRAWN:	RJM	DATE:	10.12	SIGNED:		PLotted DATE:	24.06.15
CHECKED:	DCN	DATE:	24.06.15	SIGNED:		SURVEY BY:	
APPROVED:	DCN	DATE:	24.06.15	SIGNED:		SURVEY DATE:	

ISSUE STATUS:
RESOURCE CONSENT

PROJECT No:	1520-132631-01	SCALE:	1:625 - A1 1:1250 - A3	REV	A1
DRAWING No:				REV	7

132631-23-RC108





THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 978 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 505 AND 506 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 979 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 509 AND 510 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 981 HEREON BE HELD AS TO EIGHT UNDIVIDED ONE EIGHTH SHARES BY THE OWNERS OF LOTS 567 TO 574 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

PROPOSED MEMORANDUM OF EASEMENT IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	GRANTEE
PEDESTRIAN ACCESSWAY	B	LOT 790 HEREON	TAURANGA CITY COUNCIL
	LOT 981 HEREON	LOT 981 HEREON	

Tauranga City Council

APPROVED
Subdivision Consent

RC21332-08 **PLAN** 13 July 2015

HG HARRISON GRIERSON

TAURANGA OFFICE
LEVEL 1 HARRISON GRIERSON HOUSE
141 CAMERON ROAD TAURANGA 3110
T +64 7 578 9023
W www.harrisongrison.com

REF	REVISIONS	BY	DATE
7	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
6	REVISED LOT TWO ROAD JOISTS IN STAGES 2Q, 2T & 3A LOT NUMBERS	HEP	15.05.15
5	REVISED STAGE 2A, B, C, D & W LAYOUT & ALL LOT NUMBERS	RJM	25.04.14
4	PEDESTRIAN ACCESS OVER LOT 981 PROVIDED	RJM	18.12.12
3	LOT 946 REMOVED NOW PART OF LOT 790	RJM	14.12.12
2	REVISED WORDING FOR VESTING OF OPEN SPACE RESERVES	RJM	13.11.12

PROJECT:
**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR:	DATE:	SIGNED:	FLIGHT BY:	RJM
RJM	10.1.12			RJM
DRAWN: <th>DATE:</th> <th>SIGNED:</th> <th>FLIGHT DATE:</th> <td></td>	DATE:	SIGNED:	FLIGHT DATE:	
RJM	10.1.12			24.06.15
CHECKED: <th>DATE:</th> <th>SIGNED:</th> <th>SURVEY BY:</th> <td></td>	DATE:	SIGNED:	SURVEY BY:	
DCN	24.06.15			
APPROVED: <th>DATE:</th> <th>SIGNED:</th> <th>SURVEY DATE:</th> <td></td>	DATE:	SIGNED:	SURVEY DATE:	
DCN	24.06.15			

RESOURCE CONSENT

PROJECT NO:	SCALES:	A1
1520-132631-01	1:625 - A1 1:1250 - A3	A1

DRAWING No: **132631-23-RC109** 7



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALIENED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 982 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 593 TO 596 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 983 HEREON BE HELD AS TO TWELVE UNDIVIDED ONE TWELFTH SHARES BY THE OWNERS OF LOTS 624 TO 621 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 984 HEREON BE HELD AS TO SEVEN UNDIVIDED ONE SEVENTH SHARES BY THE OWNERS OF LOTS 624 TO 630 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.



HG HARRISON GRIERSON HOUSE
 141 CAMERON ROAD TAURANGA 3110
 T +64 719 9023
 W www.harrisongrison.com


6	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
5	REVISED LOT AND ROAD LAYOUTS & STAGES 2Q, 2T & 3A, AND LOT NUMBERS	HEH	15.06.15
4	REVISED STAGE 3A, B, C, D & W LAYOUT & ALL LOT NUMBERS	RJM	23.04.14
3	LOT 565 REMOVED, NOW PART OF LOT 951	RJM	14.03.12
2	AREA B ADDED AS GREEN BELT LAND COVENANT	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	15.10.12
REF	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**

TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 9, 10 & 11 DP 364444,
 PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR:	DATE:	SIGNED:	PLOT BY:	RJM
DRAWN:	DATE:	SIGNED:	PLOT DATE:	24.06.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:	
APPROVED:	DATE:	SIGNED:	SURVEY DATE:	
ISSUE:	DATE:	SIGNED:		

RESOURCE CONSENT	
PROJECT No:	SCALES: 1:625 - A1
DRAWING No:	1:1250 - A3
132631-23-RC110	A1
	6



THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 985 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 647, 648 AND 649 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

 THAT LOT 986 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 668 AND 669 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

Tauranga City Council
APPROVED
 Subdivision Consent
 RC21332-08 PLAN 13 July 2015

HG HARRISON GRIERSON
 TAURANGA OFFICE
 LEVEL 1 HARRISON GRIERSON HOUSE
 141 CAMERON ROAD TAURANGA 3110
 T +64 7 978 9023
 W www.harrisongrierson.com

5	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
4	REVISED OF ROAD RIGHTS IN STAGES 2Q, 2T & 3A & 3B	RJM	15.05.15
3	REVISED STAGE 3A, C, D & 3B LAYOUT & ALL LOT NUMBERS	RJM	25.04.14
2	REVISED WORKING FOR VESTING OF OPEN SPACE RESERVES	RJM	23.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	15.10.12
REF	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
 TAURANGA
 STAGES 2Q - 2T & 3A - 3M**


TITLE:
**PROPOSED SUBDIVISION OF
 PT LOTS 9, 10 & 11 DP 364444,
 PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR:	DATE:	SIGNED:	PLAT BY:
RJM	10.1.12		RJM
DRAWN:	DATE:	SIGNED:	PLAT DATE:
RJM	10.1.12		24.06.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	24.06.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	24.06.15		

RESOURCE CONSENT

PRODUCT NO:	SCALE:	A1
1520-132631-01	1:1250 - A3	
DRAWING NO:	REV	

132631-23-RC111 **5**



PYES PA RD (SH 36)
LEGAL ROAD

NOTES:

- AMALGAMATION CONDITIONS**
 THAT LOT 987 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 699 AND 701 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 988 HEREON BE HELD AS TO TWO UNDIVIDED ONE HALF SHARES BY THE OWNERS OF LOTS 703 AND 704 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 990 HEREON BE HELD AS TO THREE UNDIVIDED ONE THIRD SHARES BY THE OWNERS OF LOTS 721, 722 & 723 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.
 THAT LOT 991 HEREON BE HELD AS TO FOUR UNDIVIDED ONE QUARTER SHARES BY THE OWNERS OF LOTS 727 TO 730 HEREON AS TENANTS IN COMMON IN THE SAID SHARES AND THAT INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.



5	REVISED AMALGAMATION CONDITIONS	RJM	24.06.15
4	REVISED LOT AND ROAD LAYOUTS IN STAGES 2Q, 2R, 3A & 3B AND LOT NUMBERS	RJM	19.05.15
3	REVISED STAGE 3A, 3B, 3C, 3D, 3E & 3F LAYOUT AND ALL LOT NUMBERS	RJM	25.02.14
2	REVISED LOT LAYOUT	RJM	19.11.12
1	ISSUED FOR RESOURCE CONSENT	RJM	19.10.12
REF	REVISIONS	BY	DATE

PROJECT:
**THE LAKES 2012 LTD
TAURANGA
STAGES 2Q - 2T & 3A - 3M**


TITLE:
**PROPOSED SUBDIVISION OF
PT LOTS 9, 10 & 11 DP 364444,
PT LOT 103 DP 408042 & LOT 6 DP 348694**

ORIGINATOR:	DATE:	SIGNED:	PLAT BY:
RJM	10.1.2		RJM
DRAWN:	DATE:	SIGNED:	PLAT DATE:
RJM	10.1.2		24.06.15
CHECKED:	DATE:	SIGNED:	SURVEY BY:
DCN	24.06.15		
APPROVED:	DATE:	SIGNED:	SURVEY DATE:
DCN	24.06.15		

ISSUE STATUS:		RESOURCE CONSENT	
PROJECT No:	1520-132631-01	SCALES:	1:625 - A1 1:1250 - A3
DRAWING No:			A1
132631-23-RC112			5

NOTES:

- EXISTING TITLES**
 PT LOTS 9-11 DP 364444
 CT 261821
 THE LAKES 2012 LTD 84.8420ha
 LOT 6 DP 348694
 CT 209384
 THE LAKES 2012 LTD 0.8700ha
 PT LOT 103 DP 408042
 CT 428562
 THE LAKES 2012 LTD 19.0621ha
TOTAL 104.7741ha
- PROPOSED TITLES**
 LOTS 801-890 & 1-777
 (867 RESIDENTIAL LOTS) 51.8307ha
 LOTS 900-920
 (21 ROADS TO VEST) 18.9857ha
 LOTS 930-952 & PT LOT 9
 (21 RESERVES TO VEST) 29.6506ha
 LOTS 960-992
 (30 PRIVATE ACCESS LOTS) 1.0023ha
 LOT 790
 (LARGE LOT) 3.1678ha
 STAGE 2M LOTS FROM PARENT
 TITLE (1061 & 1065) 0.1331ha
TOTAL 104.7703ha
- AREAS & DIMENSIONS ARE APPROXIMATE ONLY & ARE SUBJECT TO RESOURCE CONSENT AND LAND TRANSFER SURVEY.
- REFER SHEETS RC101-RC112 FOR AMALGAMATION CONDITIONS AND MEMORANDUM OF EASEMENTS.
- STAGING LAYOUT SHOWN IS INDICATIVE ONLY. FINAL NUMBER, SIZE AND SEQUENCE OF STAGES MAY VARY.



HG

TAURANGA OFFICE
 LEVEL 1 HARRISON GREENBERG HOUSE
 141 CARMON ROAD TAURANGA 3100
 T +64 7 878 8023
 W www.harrisongreenberg.com

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
 ACENZ

ISO 9001
 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GREENBERG CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.

1 ISSUED FOR RESOURCE CONSENT	RJM	20.05.15
REF REVISIONS	BY	DATE
PROJECT:		
THE LAKES 2012 LTD TAURANGA STAGES 3CDEFGM		
TITLE:		
RC21332 SUMMARY OF REVISIONS FOR VARIATION SUBMITTED MAY 2015		
DRAWN BY: RJM	DATE: 05.05.15	SIGNED: [Signature]
CHECKED BY: MEH	DATE: 20.05.15	SIGNED: [Signature]
APPROVED BY: DCN	DATE: 20.05.15	SIGNED: [Signature]
ISSUE STATUS:		
RESOURCE CONSENT		
PROJECT No: 1520-132631-01	SCALES: 1:2500 - A1 1:5000 - A3	A1
DRAWING No:	132631-23-RC502	
APPROVED		13 July 2015
Subdivision Consent		
PLAN		

Tauranga City Council

APPROVED

Subdivision Consent

PLAN

13 July 2015



Lakes Homes Ltd
C/- S & L Consultants Ltd
PO Box 231
Tauranga 3140

DECISION ON RESOURCE CONSENT APPLICATION – RC25903

Under the Resource Management Act 1991

Tauranga City Council resolves:

That pursuant to Sections 104 and 104B of the Resource Management Act 1991, the application for resource consent made by Lakes Homes Ltd to undertake a two-lot residential subdivision (and associated development complying with Suburban Residential Zone standards) within the Greenbelt Zone at 16 Okataina Street, Pyes Pa legally described as Lot 237 DP 507200 (CFR 769811) is granted.

Reasons for Decision:

It has been determined that allowing this activity, subject to the conditions set out below, will avoid any unacceptable actual and potential effects on the environment. These conditions include those considered necessary for addressing the matters set out under section 106 of the Act.

The activity is considered to be consistent with the relevant provisions of the National Policy Statement on Urban Development Capacity particularly as it relates to the direction set out under policies PA1, PA2 and PA4. The proposal is also consistent with the provisions of the NESCS. Further the proposal is also consistent with the Tauranga City Plan and the Bay of Plenty Regional Policy Statement. For these reasons, it has been determined that granting this application will be consistent with the purpose and principles of the Act as set out under Part 2.

The granting of this resource consent is subject to the following conditions pursuant to Sections 108 and 220 of the RMA 1991:

General

1. *The proposal shall proceed in accordance with the application prepared by S&L Consultants Ltd, ref.21809-RCA, dated June 2017, including:*
 - *S & L Consultants Ltd e-mail, dated 21 July 2017 relating to earthworks*
 - *S & L Consultants Ltd Subdivision Plan Dwg.No.21809-RC1, Rev.2, dated June 2017.*

Subject to any changes required through compliance with the following conditions [see Advice Note 1].

2. *All costs associated with the conditions of this consent, including undertaking works in accordance with the Infrastructure Development Code, shall be met by the consent holder.*

Access and Easements:

3. *That the following amalgamation conditions shall be recorded on the survey plan prior to certification pursuant to Section 223 of the Resource Management Act (LINZ Request: 1459067):*
 - *“That Lot 3 hereon (legal access) be held as to two undivided one half shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.”*
 - *“That Lot 973 DP507200 (legal access) be held as two undivided one quarter shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.”*
4. *All easements required for underground services (including easements in gross) and rights of way serving lots within the subdivision shall be duly granted or reserved.*

Servicing / Engineering Certification:

5. *All matters and works relating to the servicing of the subdivision shall be designed, supervised, constructed and certified in accordance with requirements of the Council's Infrastructure Development Code [see Advice Notes 3 & 4].*
6. *Prior to any works commencing on the site, the consent holder shall submit, to the Council (Team Leader: Land Development Engineering), plans of the proposed activity to and obtain plan approval. The detail to be submitted in accordance with this condition shall include the information and plans required by the Infrastructure Development Code including the location of existing services and connections (including the depth of existing connections; details of all proposed pipework with invert levels and details of access points or rodding eyes; and details of the formation of the proposed shared accessway.*
7. *The consent holder shall construct the shared accessway shown as Area A on the scheme plan in accordance with the Infrastructure Development Code and detail approved in accordance with condition 6 of this consent.*
8. *All residential lots shall be provided with a separate underground connection to the sanitary sewer, water, stormwater and electricity reticulation system in accordance with the Council's Infrastructure Development Code and condition 6 of this consent [see Advice Notes 3 & 4].*
9. *The consent holder shall supply to the Council a set of 'as built' plans of all engineering works in accordance with the Council's Infrastructure Development Code.*

Recommended and Assessed by:



James Danby
Consultant Planner

Delegated Authorisation by:



Brad Bellamy
Team Leader: Environmental Planning

Date: 25 July 2017

Advice Notes:

1. *This consent has been granted on the basis of the proposal being for residential subdivision (and associated residential dwellings) in accordance with the Suburban Residential Zone. Until the City Plan is amended to realign the boundary of Greenbelt Zone (in accordance with the underlying resource consent) it is expected that future development of the subject site will be subject to the relevant standards of the Suburban Residential Zone.*
2. *Under sections 357A and 357B of the Resource Management Act 1991, you have a right of objection to the consent authority in respect of the above decision or any additional fees and charges required in respect of this decision. In accordance with section 357C notice of any such objection must be in writing to the Council within 15 working days of receiving this decision and/or the date on which the invoice is received. Any notice given under section 357C should describe the reasons for the objection.*
3. *For new connections to Council infrastructure (sanitary sewer and water) pipework shall be inspected and approved by Council prior to backfilling*
4. *For all new connections to council's infrastructure, a services connection approval is required. Applications can be made to sca@tauranga.govt.nz*
5. *Development contributions under LGA 2002 –*

Requirement for development contribution: Pursuant to section 198(1)(a) of the Local Government Act 2002, Council requires that a development contribution provided for and in accordance with Council's Development Contributions Policy (which is subject to change), be made (paid) by the consent holder to Council.
6. *Where any building or drainage works are required to satisfy conditions of this consent, all consents required under the Building Act 2004 must be obtained prior to the works being carried out.*
7. *Should the actual processing cost exceed the deposit fee paid at lodgement, if not already accompanying this decision, an invoice may be sent at a later date.*

Areas and dimensions are approximate only and subject to survey.

This plan has been prepared for the purposes of Section 88 of the Resource Management Act 1991 and should not be relied on for any other purpose.

CKD BY	2	Issued for Consent	06/17
REV NO	1	Issued to Client	03/17
		DESCRIPTION	DATE
Surveyed	AJW	03/17	
Designed	CJH	03/17	
Drawn	NDP	03/17	
Checked	CJH	03/17	
Approved			


References
 Heights are in terms with Moturiki Datum.
 Origin : TCC BM 1341 RL 56.47



S & L CONSULTANTS LTD
 SURVEYORS - ENGINEERS - PLANNERS
 102 Hamilton Street, Tauranga, New Zealand
 P.O. Box 231 Ph: (07) 577-6069
 Fax: (07) 577-6065
 Email: slconsultants@slga.co.nz
 Web Site: www.slga.co.nz

Title
Proposed Subdn of Lot 237 DP 507200
 16 Okataina Street

Comprised in CT 769811
 Lakes Homes Ltd
 Copyright on this drawing is reserved
 Original Scales @ A3 Date
1:200 06/17
 Do Not Scale Dimensions
 Drawing No
21809 - RC1 Revision
2



Proposed Easements			
Purpose	Shown	Serv. Ten.	Dom. Ten.
ROW, Right to Convey Water, Electricity, Gas & Telecom	A	Lot 3 hereon	Lots 1 & 2 hereon
Right to Drain Sewage & Water	A	Lot 3 hereon	Lot 1 hereon
Right to Drain Sewage & Water	B	Lot 2 hereon	Lot 1 hereon

Areas C and D are subject to an existing consent notice.

Amalgamation Conditions

That Lot 3 hereon (Legal access) be held as to two undivided one half shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.

That Lot 973 DP 507200 (Legal access) be held as to two undivided one quarter shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.



APPROVED
 Resource Consent
PLAN
 RC25903 25-Jul-2017

150Ø RCRRJ @ 1.2% minimum
 (replace if 100Ø)

H:\21000 - 21809\21800 - 21809\21809 - Bellis Vista Homes - Okataina Street - The Lakes\Drawings\Scheme\21809 - RC1 - Scheme Plan - Rev 2.dwg - Plotred: 26/06/2017

Land Development



General Description of Landform within Tauranga District

The landform and geology within Tauranga District have some features which demand particular attention.

(a) Minimum Building Platform Levels

Significant areas of Tauranga District are at risk of flooding through sea level rise, tidal surges within the harbour, storm-wave runup on the ocean coastline and the flooding of streams, sewer drains, ponding areas and overland flow paths in extreme climatic conditions. Council has some “broadbrush” information on many possibly flood prone areas. More detailed investigations by appropriately qualified people may be required to be submitted in support of Resource and Building consents. Building Platforms should be constructed with adequate freeboard above flood levels. Council has adopted a minimum floor level policy. This level is available from Council on request from Council’s Development Engineer. However due to the dynamic nature of the environment and the ongoing investigative work these levels may be reviewed at any time. For the purposes of this clause, a “building platform” is defined as the area of ground within a line 1.0m outside the perimeter of the building proper.

(b) Low-lying Land

There are many areas of low-lying land (often adjacent to the harbour) which comprise soft or very soft foundation conditions. These conditions are characterised by normally consolidated fine grained alluvial sediments (silts and clays) which have been deposited in marine or estuarine environments. In many areas they have been subject to random and non-engineered fillings. The materials are prone to settlement caused by consolidation under even minor loadings. These areas require particular care and appropriate geotechnical investigation and advice prior to development concepts being prepared. Whilst most of the Mount Maunganui/Papamoa area has an underlying sand formation, pockets of peat and “black sand” occur which exhibit poor foundation support qualities. These should be removed from building platforms and roading subgrades.

(c) Sloping Ground

The foundation conditions of the low-lying areas in the District have been described in (b) above. The near surface geology of the higher ground within the District comprises a series of weathered fine grained rhyothic ashes known locally as the Older Ashes. The Older Ashes consist of the Pahoia Tuffs overlain by the Hamilton Ash (the top of which is known locally as the “chocolate” layer).

Overlying the Older Ashes is a series of coarse friable silts, sands and pumice lapilli which tends to mantle the topography formed within the Older Ashes and are known locally as the Younger Ashes.

On some sloping ground, particularly the present and relic slips adjacent to the harbour, the ashes often have marginal stability and there are numerous examples of past and recent instability. Deep seated failures are generally confined to the steep banks which are or have in their history been subjected to active toe erosion. Development must be set back from the top of such steep banks, with the setback distance being determined by appropriate geotechnical investigations carried out by a Person who has pre-qualified with Council as a Specialist Geotechnical Advisor.


The majority of other failures on modest to steeply sloping ground are shallow failures (involving the top 1m to 3m of soil), but are nonetheless of serious consequence to any building development. Such failures are usually initiated by extreme climatic conditions. Any sloping ground greater than 15-degree gradient should be subject to appropriate geotechnical investigations to determine whether the ground is adequately stable for development.

The Lakes (2012) Ltd

The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D)

Geotechnical Completion Report

17 February 2017



Experience
comes to life
when it is
powered by
expertise

This page has been left intentionally blank

The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D)

Prepared for
The Lakes (2012) Ltd
C/- Harrison Grierson Consultants Ltd
PO Box 13 025
Tauranga 3141
Tauranga

Prepared by
Coffey Services (NZ) Ltd
96 Cameron Road, Tauranga
Tauranga Central 3110 New Zealand
t: +64 7 577 42866081

17 February 2017

Document authorisation

Our ref: GENZTAUC13086AP-AK

For and on behalf of Coffey



David Cullen
Engineering Geologist

Quality information

Revision history

Revision	Description	Date	Author	Reviewer	Signatory
Draft	Draft for review	23 Jan 2017	D Cullen	D Sullivan	D Cullen
Final	Final for issue	17 Feb 2017	D Cullen	D Sullivan	D Cullen

Distribution

Report Status	No. of copies	Format	Distributed to	Date
Final	1	PDF	The Lakes (2012) Ltd	17 Feb 2017
Final	1	PDF	Harrison Grierson Consultants Ltd	17 Feb 2017
Final	2	Hardcopy	Tauranga City Council	17 Feb 2017

Table of contents

1.	INTRODUCTION AND SCOPE.....	1
2.	DESCRIPTION OF SUBDIVISION.....	1
3.	RELATED REPORTS.....	2
3.1.	Geotechnical Assessments.....	2
3.2.	Earthworks Completion Report	2
4.	INVESTIGATIONS COMPLETED.....	3
5.	OVERVIEW OF GEOLOGICAL CONDITIONS.....	3
6.	EARTHWORKS OPERATIONS	4
6.1.	Plant	4
6.2.	Construction Programme	4
6.2.1.	2007 – 2012	4
6.2.2.	2013 – 2014 & 2014 – 2015 Earthworks Seasons.....	4
7.	QUALITY CONTROL.....	5
7.1.	Site Preparation Observations	5
7.2.	Fill Control	5
7.2.1.	Compaction Control Criteria	5
7.2.2.	Test Results	5
8.	ENGINEERING EVALUATION AND RECOMMENDATIONS	6
8.1.	Fill Quality.....	6
8.2.	Static Settlement	6
8.2.1.	Stage 3H.....	6
8.2.2.	Lots 236-239 (Stage D).....	6
8.2.3.	Fill Development Restrictions.....	7
8.3.	Slope Stability.....	7
8.3.1.	Lots 413, 458, 460 and 493-503	7
8.3.2.	Lots 236-239 (Stage 3D).....	7
8.3.3.	Slope Development Restrictions	7
8.4.	Stage 3G Retaining Wall.....	8
8.4.1.	Retaining Wall BRL	8
8.4.2.	Retaining Wall Development Restrictions	8
8.5.	Stage 3H Stormwater Pipe Line.....	8
8.6.	Foundation Design & Bearing Capacity	9
8.7.	Stormwater Management.....	9
9.	CONCLUSION.....	9
10.	LIMITATIONS	9

Important information about your Coffey Report

Appendices

Appendix A - Figures

Appendix B - Geotechnical Suitability Statement & Geotechnical Data Summary Table

Appendix C - Pre Development Investigation Data

Appendix D - Post Development Investigation Data

Appendix E – Fill Test Summary Tables

Appendix F – Static Settlement Results

Appendix G – Stage 3G Retaining Wall Certification

Appendix H – Stage 3H Stormwater Pipeline Drawings

1. INTRODUCTION AND SCOPE

This Geotechnical Completion Report (GCR) has been prepared by Coffey Services (NZ) Ltd (Coffey) for the Lakes (2012) Limited following completion of earthworks for Stage 3G, Stage 3H (collectively known as 3GH) and Lots 236 to 239 within Stage D of the Lakes Subdivision and in general accordance with the conditions of Council resource consent number RC21332.

This GCR contains the results of site investigations together with as-built plans derived from Harrison Grierson Consultants Ltd (HGCL) topographical data. It describes bulk earthworks completed during the 2007-2008, 2013-2014 and 2014-2015 earthworks seasons.

The extent of earthworks observed by Coffey is shown on the appended plans (Figures 1 to 6, Appendix A). A Statement of Professional Opinion (Form G2) and Summary of Technical Data (Form G3) for the works described herein are also appended.

2. DESCRIPTION OF SUBDIVISION

Stages 3GH and Lots 236 to 239 within Stage D of the Lakes subdivision are located near the intersection of Pyes Pa Road and Takitimu Drive (State Highway SH26) in Pyes Pa, Tauranga. The site location and original ground contours are shown on Figures 1 (Stage 3GH) and 4 (Lots 236 to 239) in Appendix A. Stage 3G, Stage 3H and Lots 236 to 239 consists a total of 80, 11 and 4 lots respectively.

Before earthworks began, the majority of Stage 3G consisted of a flat or gently rolling north-south oriented plateau at approximately RL 55-65m (Moturiki Datum, 1953). During the 2013-2014 earthworks season, filling was placed over the northern portion of Stage 3G. The following 2014-2015 earthworks season, excavation of the elevated plateau was undertaken in the southeast of Stage 3G and additional filling was placed in the north and eastern extent. Combined cut/fill contours of the works completed are shown on Figure 2.

Stage H comprised a sloping terrace on the edge of the plateau before earthworks proceeded, dipping from approximately RL 59m in the western extents to approximately RL 49m in the east. During the 2014 to 2015 earthworks season, filling commenced over much of Stage 3H, with the exception of minor cut in the north-western and south-western extents.

Lots 236 to 239 within Stage 3D originally comprised of steeply sloping ground over much of the lots, dipping in a southeast and western direction where a deeply incised gully extended into the lots. Earthworks commenced in this area with the placement of fill over Lots 237 to 239 during the 2007 to 2008 earthworks season, followed by unsupervised filling thereafter, likely between 2010 and 2012 and discussed later in this report. Cut/fill contours are shown on Figure 4. The 2012 ground surface is shown on Figure 5. Further earthworks were completed during the 2014-2015 work season, with cut/fill contours for the 2014-2015 earthworks also shown on Figure 5.

Construction of a cantilever timber pole retaining wall was completed in 2017 adjacent to the northern perimeter of Stage 3G. Additionally in 2016, a stormwater pipe was thrust beneath the slope to the east of Stage 3H to an outlet structure above the stream in the valley below. The location of the stormwater pipe and indicative location of the retaining wall is shown on Figure 3.

Civil infrastructure for these stages and lots of the subdivision was installed in 2015 and 2016. The finished ground surface is shown on Figures 3 and 6.

3. RELATED REPORTS

The following documents were prepared prior to or during the design and development of Stages 3G, 3H & Lots 236-239 (Stage D):

1. *'Pyes Pa West Urbanisation Development, Tauranga – Geotechnical Assessment Report'*, report prepared by S&L Consultants Ltd (Ref: 16944, dated October 2003).
2. *'Geotechnical Investigation Report for the Lakes Subdivision – Stage 3 (Phase 1) at Pyes Pa, Tauranga'*, report prepared by Coffey (Ref: GENZTAUC13086AF-AA, dated 29 April 2013).
3. *'Geotechnical Investigation Report for the Lakes Subdivision – Stage 3 Zone 2 at Pyes Pa, Tauranga'*, report prepared by Coffey (Ref: GENZTAUC13086AK-AC, dated 7 April 2014).
4. *'The Lakes Subdivision Stage 3 Zone 1 Earthworks Completion Report'*, report prepared by Coffey (Ref: GENZTAUC13086AF-AE, dated 15 August 2014).
5. *'The Lakes Stage 3 - Zone 3, Geotechnical Investigation Report (Addendum 1)'*, report prepared by Coffey (Ref: GENZTAUC13086AQ-AB, dated 10 July 2015).
6. *'Building Restriction Lines above Western Slope and Collector Road, The Lakes Subdivision Stage 3 – Zone 2'*, memo prepared by Coffey (Ref: GENZTAUC13086AQ-AC, dated 25 August 2015).
7. *'Retaining Wall Design Report for Stage 3G The Lakes, The Lakes Subdivision, Tauriko'*, report prepared by Coffey (Ref: GENZTAUC13086AB-AB, dated 16 June 2016).

Key conclusions of the main documents are summarised below.

3.1. Geotechnical Assessments

The original geotechnical assessment for the Lakes subdivision was completed by S&L Consultants Ltd and contained an overview of geotechnical conditions for the entire Lakes project. The report concluded that the site was generally adequate for subdivision and residential development, subject to appropriate design and construction.

Subsequent geotechnical investigation reports by Coffey in April 2013 and April 2014 summarised additional investigations that were completed to specifically assess the Stage 3 area. These investigations generally confirmed the S&L conclusion that the site was adequate for subdivision.

3.2. Earthworks Completion Report

The August 2014 Earthworks Completion Report (ECR) concluded that the bulk earthworks undertaken in 2007-2008 and 2013-2014 were generally completed in accordance with the relevant standards and guidelines including NZS 4431 (Code of Practice for Earth Fill for Residential Development) and the Tauranga City Council Infrastructure Development Code (TCC IDC). The report did however identify several areas that needed to be re-visited in this GCR. These were:

1. Some of the fill materials placed towards the end of the 2013-2014 season did not pass the required Nuclear Density Meter (NDM) tests. The failed tests were attributed to the highly variable source materials being used (silts, sands and clays) which resulted in fills that could not be easily assessed with a NDM. It was therefore decided that the affected fill would be re-tested using hand-auger boreholes with undrained shear strength measurements and/or Dynamic Cone Penetrometer (DCP) testing as appropriate for the individual soils.
2. The ECR also commented on the presence of undocumented filling that was encountered during excavations in 2013 within lots 238 & 239 and elsewhere within the Lakes development. This filling is understood to have been placed between 2010 and 2012, when

works on site were not closely managed by either Grasshopper Farms Ltd or The Lakes (2012) Ltd.

3. Finally, the ECR recommended that the stability of the eastern slope should be reassessed in the GCR and an appropriate Building Restriction Line (BRL) be defined for lots along the crest of this slope.

These issues are addressed in the following sections of this report.

The ECR also referred to the presence of subsurface erosion features ('tomos') found in other stages of the Lakes Subdivision, indicating soils below the plateau may be subject to erosion and scouring. While 'tomos' have not been observed within these subject Stages and Lots, it is possible erosional features may be encountered during construction on these lots.

4. INVESTIGATIONS COMPLETED

Geotechnical investigations have been undertaken on this and adjacent sites during each stage of the Lakes subdivision's design and construction. The investigations used for this report are listed below. Logs of each investigation are included in Appendix C.

- Three test pits excavated in 2012 within or near Stage 3G to maximum depths of up to 5m to assess shallow ground conditions before the 2013-2014 work season (Coffey, TP07–TP09 on Figure 1);
- One Cone Penetrometer Test (CPT) to a depth of approximately 13 meters below the existing ground level using a truck mounted rig supplied by Geotech Drilling Limited (Coffey, CPT314 on Figure 1);
- One machine borehole drilled to a depth of approximately 20.0m. Standard Penetration Tests (SPT) were carried out at 1.5m intervals (Coffey, MH301 on Figure 1);
- Two flight-auger machine boreholes drilled to a maximum depth of 20.0m within Stage 3H. SPT tests were conducted at specific depths within these boreholes to provide strength estimates and relatively undisturbed samples of key lithologies encountered (Coffey, CFA04 & CFA05 on Figure 1).

On completion of the bulk earthworks in 2016, Coffey drilled a total of 50 hand-auger boreholes to target depths of 2m or 2.5m (and in some cases, up to 5m depth) on approximately every second lot to confirm finished subgrade conditions. The location of each borehole is shown on Figures 3 & 6. Although labels are not shown on the plan, the boreholes are numbered according to the relevant lot number. For example, the hand auger borehole on Lot 413 in Stage 3G is referred to as HAL413. Logs of these boreholes are included in Appendix D.

5. OVERVIEW OF GEOLOGICAL CONDITIONS

The subject areas of Stage 3G and Lots 236 to 239 within Stage 3D are located on an elevated, gently sloping plateau. Below the topsoil layer, the pre-development soil profile across this plateau comprised of volcanic ashes including the Hamilton Ash and Rotoehu Ash. This ash sequence is common throughout the Tauranga area. At this location the volcanic ashes overlie ancient alluvial deposits of the Matua Sub-Group and weakly cemented pumice sands of the Te Ranga Ignimbrite.

Stage 3H is located on a gently to moderately sloping terrace formed from ancient alluvial deposits of the Matua Subgroup.

Excavations during the 2013-2015 period reduced the thickness of the volcanic ashes across the southeast of the Stage 3G plateau by up to 7m. The subsoils below many of the finished lots therefore

comprise volcanic ash silts but in some areas excavations have penetrated through the ash layers and the finished lots are underlain by variable Matua Sub-Group soils. These include silts, sands and clays which can be highly sensitive to reworking. Areas underlain by fill are discussed in Section 6.2.

6. EARTHWORKS OPERATIONS

6.1. Plant

Earthworks during the 2007-2008 season were completed by Bob Hicks Earthmovers Ltd. The contractor for the 2013-2014 and 2014-2015 seasons was JMC Civil Construction Ltd.

The main items of plant used during each of the bulk earthworks phase comprised Terex motor-scrappers and bulldozer or tractor towed 'scoops', hydraulic excavators, bulldozers, articulated all-terrain dump trucks (ADT's) and sheep's-foot rollers.

6.2. Construction Programme

6.2.1. 2007 – 2012

Under ownership of Grasshopper Farms Ltd, earthworks during this period included excavations of up to 1m depth over Lot 237 (Stage D) as shown on Figure 4. Filling took place over Lots 237 to 239 (Stage D), however as cut & fill contours for this period are not available, fill contours were calculated by HGCL (Harrison Grierson Consultants Ltd) by subtracting the original ground surface (surveyed in 2007) from a survey completed by HGCL in 2012. This resulted in indicated fill depths of up to 11m across the lots.

Excavations in the filling in Lots 237 to 239 encountered soils that consisted of highly sensitive silts and clays with a relatively high moisture content and low undrained shear strength. Based on a series of unlogged test pits within the fill, it was considered that the non-engineered filling could remain in place provided that later fill in these areas was placed appropriately and that static settlements were monitored and reviewed prior to issue of the GCR. This later filling is discussed in more detail below.

No cut or fill took place over Stages 3GH during 2007 to 2012.

6.2.2. 2013 – 2014 & 2014 – 2015 Earthworks Seasons

In 2012 ownership of the Lakes subdivision passed from Grasshopper Farms Ltd to The Lakes (2012) Ltd. During this period the remaining earthworks were completed to form the current ground surface. Earthworks during the 2013-14 and 2014-15 summers included excavations of up to 7m depth on the main plateau of Stage 3G and 1m cuts in the north and south of Stage 3H, as shown on Figure 2.

Excavated material was used for filling up to approximately 2m deep in the northern portion of Stage 3G during both summer periods, and up to 4m deep along the eastern boundary of Stage 3G and over much of Stage 3H during the 2014-15 season.

Further cut and fill was undertaken over Lots 236 to 239 of Stage D. Lot 236 and 237 underwent cut of up to 1m and all of the lots had fill placed to varying depths, with filling of up to 8m deep in places as shown on Figure 5.

7. QUALITY CONTROL

7.1. Site Preparation Observations

During 2013-2014 and 2014-2015, Coffey undertook regular observations of fill areas to ensure topsoil, vegetation or unsuitable materials had been removed before filling.

7.2. Fill Control

As mentioned previously, filling placed over Lots 237 to 239 of Stage 3D during 2007-2012 was not tested or certified by Coffey and no other records or test results have been located.

For Stages 3GH and Lots 236 to 239 of Stage 3D in the 2013-2014 and 2014-2015 seasons, Nuclear Density Meter (NDM), laboratory moisture content and undrained shear strength tests were carried out by Geotechnics & Fulton Hogan on behalf of JMC Limited. The locations of the tests completed are shown on Figure 2 and 5.

In cases where of the above tests recorded low undrained shear strengths, retests were undertaken to assess the ground conditions and fill strength, either as additional NDM tests or subsequent hand-auger boreholes in close proximity to the original test.

7.2.1. Compaction Control Criteria

The compaction control criteria for this project were specified using the 'minimum allowable shear strength and maximum allowable air voids' method as defined below:

- Air voids percentage (defined in NZS 4402:1986 and as measured by NDM) targeting an average value less than 10% over any 10 consecutive tests and maximum single value no greater than 12%.
- Undrained shear strength measured by hand held shear vane calibrated using the NZGS 2001 method. A single undrained shear strength 'test' was defined as the average of four individual shear vane readings at each NDM location. The target test values were an average value greater than 150kPa and minimum single value no less than 140kPa.

The hand-auger boreholes drilled to re-test filling used field shear vane measurements with the same target result as above.

7.2.2. Test Results

Summary tables showing the results of the laboratory fill tests for bulk earthworks at Stages 3G, 3H & Lots 236-239 (Stage D) are included in Appendix E and the locations of the tests are shown on Figures 2 and 5. The majority of tests met or exceeded the compaction control criteria given above. Failed tests are shown in red on the relevant figures.

Three tests during the 2013-2014 season did not meet the required values, with test numbers A-05, A-12, and A-41 being deemed to have failed due to low undrained shear strength readings. The fill surrounding these tests were either reworked or retested with hand-auger boreholes at a later date (passing thereafter), indicating the failed result was either due to an incorrect test value or an isolated pocket of filling.

During the 2014-2005 season, three tests being B-01, B-05 and B-13 initially failed due to low undrained shear strength readings but were retested and subsequently passed. As these tests were superseded by later testing, the tests are not showing as failed results on the site plan.

Two further tests, B-08 and B-09, failed due to low undrained shear strength readings and were retested with hand-auger boreholes at a later date, again with passing results indicating the failed tests were either due to an incorrect test value or an isolated pocket of filling.

8. ENGINEERING EVALUATION AND RECOMMENDATIONS

8.1. Fill Quality

Based on the appended earth fill quality control test data and reliance on the diligence of the bulk earthworks contractor at times when engineering staff were not present on site, results indicate that the compaction control criteria were generally met during the bulk earthworks periods in 2013-2014 and 2014-2015.

8.2. Static Settlement

The majority of the area, specifically Stage 3G, was either located in zones of cut or received evenly distributed filling over volcanic ashes with soils not expected to be subject to significant settlement. Static settlements were therefore not monitored in Stage 3G.

However, Stage 3H and Lots 236-239 (Stage D) received up to 4m and 8m of fill material respectively during the 2013-14 season. Settlement monitoring points were therefore installed in these areas. The monitoring pins consisted of steel rods attached to plates installed at the base of the filling. The data from these pins are presented graphically in Appendix F and settlement marker locations shown on Figures 2 and 6 for Stage 3H and Lots 236-239 (Stage D) respectively.

8.2.1. Stage 3H

Static settlements below the 2014 filling were monitored at two locations shown as SM26 and SM27 on Figure 2. Measured settlements were 205mm and 390mm for SM26 and SM27.

The data show the majority of consolidation settlement below the filling occurred within 2 to 3 months of earthworks being completed. Thereafter, settlement entered a long term 'creep' phase. Extrapolating the data out for a period of 50 years indicated that lots in this area may be affected by up to 100mm of future creep settlement over the assumed life of the proposed dwellings. However, differential settlements within the affected lots would be expected to be within the allowable range recommended by MBIE (i.e. 25mm/6m length), provided additional fill does not exceed 0.6m.

8.2.2. Lots 236-239 (Stage D)

Static settlements were monitored over Lots 236-239 during and after the 2013-2014 and 2014-2015 work seasons.

Three settlement markers were installed, SM15, SM28, and SM28A as shown on Figure 6, however only SM28 remained functional during the whole monitoring period as the other two markers were either damaged or moved during fill placement.

In regards to SM28, monitoring from April 2015 to August 2016 indicated the filling had induced static settlements of 68mm and that settlement was ongoing. Extrapolating the data out for 50 years indicated long-term settlement may exceed 60mm, with a high likelihood of excessive differential settlement beneath the building platforms.

The area was therefore pre-loaded with 2m of topsoil in April 2016 as shown in Figure 6. Continuing monitoring indicated this pre-load induced an additional settlement of up to 47mm. Following the completion of monitoring in August 2016, the pre-load was removed.

Following preloading we consider that the potential for future static settlements beneath these lots has been reduced, and long term differential settlements would be expected to be within accepted limits, provided additional fill does not exceed 1.0m.

8.2.3. Fill Development Restrictions

To reduce possible future settlements, any additional filling the lots listed below should not exceed the following depths without the approval of the TCC Category 1 or 2 Geo-Professional:

- 1.0m for lots 236-239
- 0.6m for lots 495-502

8.3. Slope Stability

While the majority of proposed lots within Stage 3G are located on gently sloping ground, the lots within this stage adjacent to the eastern perimeter and all lots within Stage 3H are located above a steeper slope. Lots 236-239 are also positioned above steeper slopes to the east and south of the lot boundaries.

8.3.1. Lots 413, 458, 460 and 493-503

The adjacent slope below the plateau exhibited a few areas of instability. Colluvial soils were encountered in hand auger boreholes and test pits in this area and topographic evidence also suggested that this slope has been affected by larger scale ancient instability.

Stability analyses of this slope noted that values were generally less than required by the IDC for residential development and indicated that further instability may occur on this slope in the future during extreme rainfall events or under seismic loads.

As the slope is insufficiently stable for residential development, the lots are subject to a building restriction line (BRL) as shown on Figure 3. The BRL has been defined by either projecting a 1V:2.5H line from the toe of the steepest adjacent slope, or by measuring 15m back from the slope crest, whichever is smaller. The proposed setback distance is considered adequate for the residential development in this area.

8.3.2. Lots 236-239 (Stage 3D)

Slopes adjacent to Lots 236-237 have been engineered with a gradient of 1V:2.5H for which this gradient is considered to be an adequately stable slope angle for Tauranga soils. However, this does not allow for surcharge from residential buildings or fill and therefore a BRL has been placed on these lots, setback 3-5m from the slope crest as shown on Figure 6.

The slope south of lots 237-239 have been engineered with a gradient of 1V:3H and therefore are adequate for residential development without a BRL.

8.3.3. Slope Development Restrictions

For lots 236-237, 413, 458, 460 and 493-503, it should be understood that the inclusion of a BRL on a lot does not specifically preclude development beyond the restriction line. However, any development between the BRL and slope will require specific geotechnical input and may need additional slope protection works such as retaining walls, deepened foundations, etc. The following restrictions are recommended for these lots:

- Any part of a dwelling or structure which extends beyond the BRL must be reviewed and approved by a TCC Category 1 Geo-Professional prior to the building consent application. A geotechnical report must be provided including the specific design of any mitigation works proposed.

- Any filling between the BRL and slope must be reviewed and approved by a TCC Category 1 Geo-Professional with a report to be provided to Council before work begins.
- Stormwater from any paved or impermeable surfaces including roofs and driveways on these lots must be collected and piped to the site's stormwater system. Stormwater must not be disposed via ground soakage on these lots and any concentration of runoff over the slope must be avoided.

8.4. Stage 3G Retaining Wall

The construction of the timber pole retaining wall along the northern boundary of Stage 3G was observed by Coffey. This included regular site visits to confirm borehole and post dimensions and ground conditions along the wall alignment as specified in the retaining wall design report.

Based on our observations we consider the wall has been built in accordance with the design. A separate certification letter has been provided for the wall, a copy of which is included in Appendix G.

8.4.1. Retaining Wall BRL

As the wall has not been designed for additional surcharge loads, a BRL has been defined with a setback distance equal to the height of the wall. The BRL has been assigned to lots 441, 442, 444 to 455, 457 and 458 within Stage 3G as shown on Figure 3.

8.4.2. Retaining Wall Development Restrictions

Specifically for lots 441, 442, 444 to 455, 457 and 458, in regards to the BRL adjacent to the Stage 3G retaining wall, the following restrictions are recommended:

- Any part of a dwelling or structure which extends beyond the BRL must be reviewed and approved by a TCC Category 1 or 2 Geo-Professional prior to the building consent application. A geotechnical report must be provided including the specific design of any mitigation works proposed. Specific design may include, deepened foundations past the 45° zone of influence from the toe of the retaining wall.
- No filling is to take place between the BRL and crest of wall without review and approval by a TCC Category 1 or 2 Geo-Professional. Due to the height of the existing retaining wall, any additional filling or retaining structures above the wall and within the BRL may require a Resource Consent.
- Stormwater from any paved or impermeable surfaces including roofs and driveways on these lots must be collected and piped to the site's stormwater system and not allowed to flow over the the retaining wall.

8.5. Stage 3H Stormwater Pipe Line

As mentioned in Section 2, a stormwater pipeline was horizontally drilled or 'thrust' beneath the slope to the east of Stage 3H as part of the civil infrastructure installation in 2016. The pipeline was designed by Harrison Grierson Consultants Ltd. Coffey provided advice regarding the pipeline alignment and recommended the pipe was installed at least 3.0m below existing ground level to reduce the risk of damage in the event of slope failure

A copy of Harrison Grierson's design drawings for the pipeline is included in Appendix G. Based on our observations during drilling and as-built survey information from Harrison Grierson, we consider the pipeline has been installed along an appropriate alignment. The survey data indicate the pipe is at least 3.0m deep below the existing ground surface as recommended.

8.6. Foundation Design & Bearing Capacity

The lots within Stage 3G and Lots 236-239 (Stage D) are underlain by either engineered fill or natural soils that meet or exceed the conditions for 'good ground' as defined by NZS 3604. Dwellings on these sites may therefore be supported on standard shallow foundations designed for a geotechnical ultimate bearing capacity of 300kPa.

Lots 493 to 503 within Stage 3H also meet or exceed the conditions for 'good ground' as defined by NZS 3604. However, as the lots are moderately steeply sloping, development on these lots may require deep excavation to form a level building platform. We recommend that whenever the proposed depth of excavation exceeds 1.5m, additional investigation should be undertaken by a TCC Category 1 or 2 Geo-Professional at the design/building consent stage to confirm soil conditions below the proposed foundations. A consent notice to this effect should be added to the affected lots (see Form G3, Appendix B).

It should be understood that due to the volcanic nature of the natural soils on this site, it is possible that local soil conditions may vary from those discussed above. Some soils observed onsite are also potentially prone to sub-surface erosion (e.g. 'tomos'). It is therefore important that any potentially soft or unsuitable soils encountered in the foundation excavations are brought to the attention of a geotechnical professional.

8.7. Stormwater Management

To further reduce the potential for surface and sub-surface erosion, all stormwater from impervious areas within the development will need to be carefully collected and piped to a safe disposal point or to the reticulated network. Particular care should be taken to avoid areas of ponded stormwater or concentrated flows around and under buildings or structures.

9. CONCLUSION

Based on the observations and investigations presented in this report and with reliance on the diligence of the earthworks contractors, it is concluded that the earthworks and subdivision of Stages 3GH and Lots 236-239 of Stage 3D have been completed in general accordance with previous recommendations and current Tauranga City Council Infrastructure Development Code.

This report presents site-specific recommendations including Building Restriction Lines (BRLs) on some lots located above steeper slopes or adjacent to retaining walls. Provided these recommendations are followed and prudent development practices are adopted, it is considered that the finished lots are at low risk of erosion, falling debris, subsidence, inundation or liquefaction and these sites are therefore adequate for residential development without the need for Section 72 restrictions under the New Zealand Building Act.

Development outside the BRL (i.e. between the restriction line and the slope/retaining wall) is subject to further geotechnical input per Sections 8.3.3 and 8.4.2 of this report. The placement of additional filling is also restricted on some lots as per Section 8.2.3. The need for a Section 72 restriction on affected lots may therefore need to be re-assessed at the building consent stage.

10. LIMITATIONS

This report has been prepared solely for the use of the client, The Lakes (2012) Limited, their professional advisers and the relevant Territorial Authorities in relation to the specific project described herein. No liability is accepted in respect of its use for any other purpose or by any other person or entity. All future owners of this property should seek professional geotechnical advice to satisfy themselves as to its ongoing suitability for their intended use.

The opinions, recommendations and comments given in this report result from the application of normal methods of site investigation. As the post construction factual evidence has been obtained solely from boreholes and test pits, which by their nature only provide information about a relatively small volume of subsoils, there may be special conditions pertaining to this site which have not been disclosed by the investigation and which have not been taken into account in the report.

For and on behalf of Coffey

Report Prepared By:



D B CULLEN
Engineering Geologist

Report Reviewed By:



D SULLIVAN
Principal Geotechnical Engineer
BSc, MBA, CE (Calif.), MIPENZ, CPEng, TCC Category 1 Geotechnical Engineer
CPEng No. 1025183

Geotechnical Suitability Statement Signed By:



R TELFORD
TCC Category 2 Geotechnical Engineer

Important information about your **Coffey Report**

As a client of Coffey you should know that site subsurface conditions cause more construction problems than any other factor. These notes have been prepared by Coffey to help you interpret and understand the limitations of your report.

Your report is based on project specific criteria

Your report has been developed on the basis of your unique project specific requirements as understood by Coffey and applies only to the site investigated. Project criteria typically include the general nature of the project; its size and configuration; the location of any structures on the site; other site improvements; the presence of underground utilities; and the additional risk imposed by scope-of-service limitations imposed by the client. Your report should not be used if there are any changes to the project without first asking Coffey to assess how factors that changed subsequent to the date of the report affect the report's recommendations. Coffey cannot accept responsibility for problems that may occur due to changed factors if they are not consulted.

Subsurface conditions can change

Subsurface conditions are created by natural processes and the activity of man. For example, water levels can vary with time, fill may be placed on a site and pollutants may migrate with time. Because a report is based on conditions which existed at the time of subsurface exploration, decisions should not be based on a report whose adequacy may have been affected by time. Consult Coffey to be advised how time may have impacted on the project.

Interpretation of factual data

Site assessment identifies actual subsurface conditions only at those points where samples are taken and when they are taken. Data derived from literature and external data source review, sampling and subsequent laboratory testing are interpreted by geologists, engineers or scientists to provide an opinion about overall site conditions, their likely impact on the proposed development and recommended actions. Actual conditions may differ from those inferred to exist, because no professional, no matter how qualified, can reveal what is hidden by

earth, rock and time. The actual interface between materials may be far more gradual or abrupt than assumed based on the facts obtained. Nothing can be done to change the actual site conditions which exist, but steps can be taken to reduce the impact of unexpected conditions. For this reason, owners should retain the services of Coffey through the development stage, to identify variances, conduct additional tests if required, and recommend solutions to problems encountered on site.

Your report will only give preliminary recommendations

Your report is based on the assumption that the site conditions as revealed through selective point sampling are indicative of actual conditions throughout an area. This assumption cannot be substantiated until project implementation has commenced and therefore your report recommendations can only be regarded as preliminary. Only Coffey, who prepared the report, is fully familiar with the background information needed to assess whether or not the report's recommendations are valid and whether or not changes should be considered as the project develops. If another party undertakes the implementation of the recommendations of this report there is a risk that the report will be misinterpreted and Coffey cannot be held responsible for such misinterpretation.

Your report is prepared for specific purposes and persons

To avoid misuse of the information contained in your report it is recommended that you confer with Coffey before passing your report on to another party who may not be familiar with the background and the purpose of the report. Your report should not be applied to any project other than that originally specified at the time the report was issued.

Important information about your **Coffey** Report

Interpretation by other design professionals

Costly problems can occur when other design professionals develop their plans based on misinterpretations of a report. To help avoid misinterpretations, retain Coffey to work with other project design professionals who are affected by the report. Have Coffey explain the report implications to design professionals affected by them and then review plans and specifications produced to see how they incorporate the report findings.

Data should not be separated from the report*

The report as a whole presents the findings of the site assessment and the report should not be copied in part or altered in any way.

Logs, figures, drawings, etc. are customarily included in our reports and are developed by scientists, engineers or geologists based on their interpretation of field logs (assembled by field personnel) and laboratory evaluation of field samples. These logs etc. should not under any circumstances be redrawn for inclusion in other documents or separated from the report in any way.

Geoenvironmental concerns are not at issue

Your report is not likely to relate any findings, conclusions, or recommendations about the potential for hazardous materials existing at the site unless specifically required to do so by the client. Specialist equipment, techniques, and personnel are used to perform a geoenvironmental assessment.

Contamination can create major health, safety and environmental risks. If you have no information about the potential for your site to be contaminated or create an environmental hazard, you are advised to contact Coffey for information relating to geoenvironmental issues.

Rely on Coffey for additional assistance


Coffey is familiar with a variety of techniques and approaches that can be used to help reduce risks for all parties to a project, from design to construction. It is common that not all approaches will be necessarily dealt with in your site assessment report due to concepts proposed at that time. As the project progresses through design towards construction, speak with Coffey to develop alternative approaches to problems that may be of genuine benefit both in time and cost.

Responsibility

Reporting relies on interpretation of factual information based on judgement and opinion and has a level of uncertainty attached to it, which is far less exact than the design disciplines. This has often resulted in claims being lodged against consultants, which are unfounded. To help prevent this problem, a number of clauses have been developed for use in contracts, reports and other documents. Responsibility clauses do not transfer appropriate liabilities from Coffey to other parties but are included to identify where Coffey's responsibilities begin and end. Their use is intended to help all parties involved to recognise their individual responsibilities. Read all documents from Coffey closely and do not hesitate to ask any questions you may have.

* For further information on this aspect reference should be made to "Guidelines for the Provision of Geotechnical information in Construction Contracts" published by the Institution of Engineers Australia, National headquarters, Canberra, 1987.

Appendix A - Figures



LEGEND

EXTENT OF STAGES IN THIS GCR

TEST PIT (COFFEY 2012)

CONE PENETRATION TEST (COFFEY 2014)

MACHINE BOREHOLE (COFFEY 2014)

NOTES:

1. Contour data of 2012 landform from Harrison Grierson Consultants Ltd.
2. Contours shown at 1.0m intervals to Moturiki Datum.
3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.


revision		date	approved	drawn	description

drawn	ODS / DBC
approved	RBT
date	17-2-2017
scale	1:2000
original size	A3

Horizontal Scale (metres)	0 30.0 60.0 90.0 120.0
Vertical Scale (metres)	0 30.0 60.0 90.0 120.0

client:	The Lakes (2012) Ltd
project:	The Lakes Stage 3G & 3H Geotechnical Completion Report
title:	Original Contour Plan
project no.:	13086AP-AK
figure no.:	1
rev.:	-





LEGEND	
	EXTENT OF STAGES IN THIS GCR
	CUT CONTOURS
	FILL CONTOURS
	SETTLEMENT MONITORING POINTS
	2013-2014 NDM TEST LOCATION (PASSED)
	2013-2014 NDM TEST LOCATION (FAILED)
	2014-2015 NDM TEST LOCATION (PASSED)
	2014-2015 NDM TEST LOCATION (FAILED)

NOTES:
 1. Cut/Fill contours show difference between 2012 and March 2016 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

revision		description	drawn	approved	date

drawn	ODS / DBC
approved	RBT
date	17-2-2017
scale	1:2000
original size	A3


client:	The Lakes (2012) Ltd
project:	The Lakes Stage 3G & 3H
title:	2013-2015 Earthworks Contour & Settlement Monitoring Plan
project no.:	13086AP-AK
figure no.:	2
rev.:	-





LEGEND

- EXTENT OF STAGES IN THIS GCR
- BUILDING RESTRICTION LINE (BRL)
- - - RETAINING WALL
- STORMWATER PIPE
- HAND AUGER BOREHOLE LOCATIONS



Horizontally drilled stormwater pipe connects to stormwater system as per Harrison Grierson Consultants Ltd drawings 138804-403, 138804-435 and 138804-483.

Outlets to Nanako stream as per Harrison Grierson Consultants Ltd drawings 138804-403, 138804-435 and 138804-483.

NOTES:

1. Contour data of 2017 landform from Harrison Grierson Consultants Ltd.
2. Contours shown at 0.2m intervals to Metuiki Datum.
3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.
4. Hand auger boreholes are numbered according to the relevant lot number. Where two boreholes occur on the same lot, they are appended with the letter A and B.

revision		description	drawn	approved	date


drawn	approved	date	scale	original size

ODS / DBC	RBT

date	scale	original size
17-2-2017	1:2000	A3


Horizontal Scale (metres)	Vertical Scale (metres)
0 30.0 60.0 90.0 120.0	0 30.0 60.0 90.0 120.0

client:	The Lakes (2012) Ltd
project:	The Lakes Stage 3G & 3H Geotechnical Completion Report
title:	2017 Contour Plan
project no.:	130886AP-AK
figure no.:	3
rev.:	-



ORIGINAL SITE CONTOUR PLAN

NOTES:
 1. Contour data of original pre-earthworks landform from Harrison Grierson Consultants Ltd, May 2007.
 2. Contours shown at 10m intervals to Metriki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.




2007-2012 EARTHWORKS CONTOUR PLAN

NOTES:
 1. Cut/Fill contours show difference between 2007 and March 2012 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

LEGEND

- EXTENT OF STAGES IN THIS GCR
- CUT CONTOURS
- FILL CONTOURS




rev	description	drawn	approved	date

drawn	DBC
approved	RBT
date	17-2-2017
scale	1:750
original size	A3




client:	The Lakes (2012) Ltd
project:	The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report
title:	Original Contour & 2007-2012 Earthworks Plan
project no.:	13086AP-AK
figure no.:	4
rev.:	-



2012 CONTOUR PLAN

NOTES:
 1. Contour data of 2012 landform from Harrison Grierson Consultants Ltd.
 2. Contours shown at 1.0m intervals to Metukiki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.




2013-2015 EARTHWORKS CONTOUR PLAN

NOTES:
 1. Cut/Fill contours show difference between 2012 and March 2016 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

LEGEND


- EXTENT OF STAGES IN THIS GCR
- CUT CONTOURS
- FILL CONTOURS
- B-01 2014-2015 NDM TEST LOCATION (PASSED)
- B-01 2014-2015 NDM TEST LOCATION (FAILED)

rev	description	drawn	approved	date




drawn	DBC
approved	RBT
date	17-2-2017
scale	1:750
original size	A3

client:	The Lakes (2012) Ltd
project:	The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report
title:	2012 Contour & 2013-2015 Earthworks Plan
project no.:	13086AP-AK
figure no.:	5
rev.:	-



2017 CONTOUR PLAN

- NOTES:**
1. Contour data of February 2017 landform from Harrison Grierson Consultants Ltd.
 2. Contours shown at 1.0m intervals to Moturiki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.
 4. Hand auger boreholes are numbered according to the relevant lot number.



2013-2015 SETTLEMENT MONITORING PLAN

- NOTES:**
1. Cut/Fill contours show difference between 2012 and March 2016 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.
 3. Settlement Monitoring Point locations provided by Harrison Grierson Consultants Ltd.

LEGEND

- EXTENT OF STAGES IN THIS GCR
- EXTENT OF 2m TOPSOIL PRELOAD
- CUT CONTOURS
- FILL CONTOURS
- SETTLEMENT MONITORING POINTS
- BUILDING RESTRICTION LINE (BRL)
- HAND AUGER BOREHOLE LOCATIONS


revision	description	drawn	approved	date

drawn	approved	date	scale	original size

DBC	RBT

date	17-2-2017
scale	1:750
original size	A3

client:	The Lakes (2012) Ltd
Project:	The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report
title:	Settlement Monitoring & 2016 Contour Plan
Project no.:	13086AP-AK
figure no.:	6
rev.:	-



**Appendix B - Geotechnical Suitability Statement &
Geotechnical Data Summary Table**

**STATEMENT OF PROFESSIONAL OPINION AS TO THE
GEOTECHNICAL SUITABILITY OF LAND FOR BUILDING**

NAME OF SUBDIVISION	The Lakes Subdivision – Stages 3G, 3H & Lots 236-239 (Stage D)
COUNCIL FILE NUMBER RC No:	RC21332
ENGINEER RESPONSIBLE FOR DEVELOPMENT	Robert Telford
QUALIFICATIONS:	TCC Category 2 Geotechnical Engineer

I, Robert Telford of Coffey Services (NZ) Ltd, 96 Cameron Road, Tauranga, hereby confirm that:

- 1) I am a professional person, appropriately qualified with experience in geomechanics to ascertain the suitability of the land for building development and was retained as the Soils Engineer to the above development.
- 2) An appropriate level of site investigation and construction supervision has been carried out under my direction and is described in our development evaluation reports dated 29 April 2013, 7 April 2014 and 10 July 2015.
- 3) In my professional opinion, not to be construed as a guarantee, I consider that;
 - a) The areas shown in my report dated 17 February 2017 of each new allotment are suitable for the erection thereon of the building types appropriate to the zoning of the land, provided that reference is made to my Geotechnical Completion Report Ref. GENZTAUC13086AP-AK, dated 17 February 2017.
 - b) The earth fills shown on the attached Plans ref Figure 2, Figure 5 and Figure 6 have been placed in general accordance with the requirements of the Infrastructure Development Code.
 - c) The completed works give due regard to all land slope and foundation stability considerations.
 - d) The filled ground is suitable for the erection thereon of residential buildings not requiring specific design subject to the recommendations presented in my Geotechnical Completion Report Ref. GENZTAUC13086AP-AK, dated 17 February 2017.
 - e) The original ground not affected by filling is suitable for the erection thereon of residential buildings not requiring specific design subject to the recommendations presented in my Geotechnical Completion Report Ref. GENZTAUC13086AP-AK, dated 17 February 2017.
- 4) This professional opinion is furnished to the Council and the owner for their purposes alone, on the express condition that it will not be relied upon by any other person and does not remove the necessity for the normal inspection of foundation conditions at the time of erection for any dwelling.

Signed

Date: 17 February 2017



**PRODUCER STATEMENT
SUITABILITY OF LAND FOR BUILDING DEVELOPMENT**

INFRASTRUCTURE DEVELOPMENT CODE

G2

VERSION 1
July 2011

1

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332													
Lot No:	Subsurface data		Foundations	Consent Notice	Comments													
	Area (m ²)	Shear Strength (kPa) at 0.5m depth		Subdivision Filling		Natural Topography Unworked	Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	
	Y/N	Depth (m)	Y/N	Y/N		Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	
236	765	147	Y	5		N	Y	1	Y	N	Y	N	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
237	894	DCP	Y	14		N	Y	1	Y	N	Y	N	N	N	N	Y	Development subject to fill depth restrictions per Section 8.2.3 of Coffey GCR ref:GENZTAUC13086AP-AK.	
238	599	>240	Y	19		N	N	-	N	N	N	N	N	N	N	Y	Development subject to Slope BRL restrictions per Section 8.3.3 of Coffey GCR ref:GENZTAUC13086AP-AK.	
239	540	>183	Y	16		N	Y	2	Y	N	Y	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.	
413	605	190	N	-		N	Y	3	Y	N	Y	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.	
414	487	N/T	N	-		N	Y	5	Y	N	Y	N	N	N	N	N	Development subject to Slope BRL restrictions per Section 8.3.3 of Coffey GCR ref:GENZTAUC13086AP-AK.	
415	455	>202	N	-		N	Y	5	Y	N	Y	N	N	N	N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.	



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">Consent Notice</td> <td style="width:15%;">On-Site Effluent Disposal</td> <td style="width:15%;">Compressible Soils</td> <td style="width:15%;">Minimum Building Platform</td> <td style="width:15%;">Designated Building Platform</td> <td style="width:15%;">S/W Reticulate</td> <td style="width:15%;">S/W Soakage</td> <td style="width:15%;">S/W Specific Design</td> <td style="width:15%;">Building Restriction Line</td> </tr> <tr> <td colspan="2">Subsurface data</td> <td colspan="2">Foundations</td> <td colspan="4"></td> <td colspan="2"></td> </tr> <tr> <td rowspan="2">Shear Strength (kPa)</td> <td rowspan="2">Subdivision Filling</td> <td rowspan="2">Natural Topography Unworked</td> <td rowspan="2">Natural Topography Earthworked</td> <td rowspan="2">Conventional Shallow Foundation to NZS 3604:2011</td> <td rowspan="2">Specific Design</td> <td colspan="2">Depth (m)</td> <td rowspan="2">Y/N/NA</td> </tr> <tr> <td>Y/N</td> <td>Y/N/NA</td> </tr> <tr> <td>at 0.5m depth</td> <td>Y/N</td> <td>Y/N</td> <td>Y/N</td> <td>Y/N/NA</td> <td>Y/N/NA</td> <td colspan="2"></td> <td></td> </tr> </table>						Consent Notice	On-Site Effluent Disposal	Compressible Soils	Minimum Building Platform	Designated Building Platform	S/W Reticulate	S/W Soakage	S/W Specific Design	Building Restriction Line	Subsurface data		Foundations								Shear Strength (kPa)	Subdivision Filling	Natural Topography Unworked	Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Depth (m)		Y/N/NA	Y/N	Y/N/NA	at 0.5m depth	Y/N	Y/N	Y/N	Y/N/NA	Y/N/NA			
Consent Notice	On-Site Effluent Disposal	Compressible Soils	Minimum Building Platform	Designated Building Platform	S/W Reticulate	S/W Soakage	S/W Specific Design	Building Restriction Line																																				
Subsurface data		Foundations																																										
Shear Strength (kPa)	Subdivision Filling	Natural Topography Unworked	Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Depth (m)		Y/N/NA																																				
						Y/N	Y/N/NA																																					
at 0.5m depth	Y/N	Y/N	Y/N	Y/N/NA	Y/N/NA																																							
Area (m ²)																																												
Lot No:																																												
<p>Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.</p>																																												
427	481	N/T	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
428	432	>202	Y	<1	N	N	-	N	Y	N	N	N	N	N	N	N	N	N	N																									
429	407	N/T	Y	<1	N	N	-	N	Y	N	N	N	N	N	N	N	N	N	N																									
430	407	>182	Y	<1	N	N	-	N	Y	N	N	N	N	N	N	N	N	N	N																									
431	431	N/T	Y	<1	N	N	-	N	Y	N	N	N	N	N	N	N	N	N	N																									
432	473	156	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
433	573	N/T	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
434	569	>202	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
435	473	N/T	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
436	473	>202	Y	<1	N	Y	<1	N	Y	N	N	N	N	N	N	N	N	N	N																									
437	358	N/T	Y	<1	N	N	-	N	Y	N	N	N	N	N	N	N	N	N	N																									



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332													
Lot No:	Subsurface data		Foundations		Comments													
	Area (m ²)	Shear Strength (kPa) at 0.5m depth	Subdivision Filling	Natural Topography Unworked		Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	Consent Notice	
	Y/N	Depth (m)	Y/N	Y/N	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	
438	372	>202	Y	<1	N	N	Y	Y	N	N	N	N	N	N	N	N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
439	529	N/T	Y	1	N	Y	Y	<1	N	Y	Y	Y	Y	N	N	N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
440	430	N/T	Y	<1	N	Y	Y	<1	N	Y	Y	Y	Y	N	N	N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
441	610	>182	Y	1	N	N	Y	1	N	Y	Y	Y	Y	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
442	482	>202	Y	1	N	N	Y	1	N	Y	Y	Y	Y	N	N	N	Y	Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref: GENZTAUC13086AP-AK.
443	450	N/T	Y	1	N	N	Y	1	N	Y	Y	Y	Y	N	N	N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
444	582	N/T	Y	1	N	N	Y	1	N	Y	Y	Y	Y	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
445	512	>182	Y	2	N	N	Y	2	N	Y	Y	Y	Y	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
446	512	N/T	Y	2	N	N	Y	2	N	Y	Y	Y	Y	N	N	N	Y	Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref: GENZTAUC13086AP-AK.
447	530	166	Y	2	N	N	Y	2	N	Y	Y	Y	Y	N	N	N	Y	Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref: GENZTAUC13086AP-AK.



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332													
Lot No:	Subsurface data		Foundations		Comments													
	Area (m ²)	Shear Strength (kPa) at 0.5m depth	Subdivision Filling	Natural Topography Unworked		Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	Consent Notice	
	Y/N	Depth (m)	Y/N	Y/N	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	
448	576	N/T	Y	2	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	<p>Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.</p> <p>Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref:GENZTAUC13086AP-AK.</p> <p>Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.</p>
449	576	UTP	Y	2	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
450	576	N/T	Y	2	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
451	576	N/T	Y	2	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
452	576	>202	Y	2	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
453	576	>202	Y	1	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
454	587	N/T	Y	1	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
455	732	>202	Y	1	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	
456	353	N/T	Y	1	N	N	N	Y	N	Y	Y	N	N	N	N	N	Y	



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332													
Lot No:	Subsurface data		Foundations	Consent Notice	Comments													
	Area (m ²)	Shear Strength (kPa) at 0.5m depth		Subdivision Filling		Natural Topography Unworked	Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	
	Y/N	Depth (m)	Y/N	Y/N		Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	
457	437	>202	Y	1		N	N	-	Y	N	Y	N	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK. Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref:GENZTAUC13086AP-AK.
458	586	N/T	Y	1		N	Y	<1	Y	N	Y	N	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK. Development subject to Slope BRL restrictions per Section 8.3.3 of Coffey GCR ref:GENZTAUC13086AP-AK.
459	353	>202	Y	1		N	N	-	Y	N	Y	N	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK. Development subject to Retaining Wall BRL restrictions per Section 8.4.2 of Coffey GCR ref:GENZTAUC13086AP-AK.
460	913	177	Y	<1		N	Y	<1	Y	N	Y	N	N	N	N	N	Y	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK. Development subject to Slope BRL restrictions per Section 8.3.3 of Coffey GCR ref:GENZTAUC13086AP-AK.



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332											
Lot No: Area (m ²)	Subsurface data		Foundations	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	Consent Notice	Comments			
	Shear Strength (kPa) at 0.5m depth	Subdivision Filling			Natural Topography Unworked	Natural Topography Earthworked	Depth (m)	Y/N	Y/N	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Y/N/NA		Y/N/NA	Y/N/NA	
			Y/N	Y/N												Y/N/NA
	472	450	>202	Y	1	N	N	-	Y	N	N	N		N	N	Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.
	473	450	N/T	Y	1	N	N	-	Y	N	N	N		N	N	
	474	407	N/T	Y	<1	Y	N	<1	Y	N	N	N		N	N	
	475	447	N/T	Y	1	Y	N	<1	Y	N	N	N		N	N	
	476	508	>182	Y	1	N	N	-	Y	N	N	N		N	N	
	477	450	N/T	Y	1	N	N	-	Y	N	N	N		N	N	
	478	450	>202	Y	1	N	N	-	Y	N	N	N		N	N	
	479	450	N/T	Y	1	N	N	-	Y	N	N	N		N	N	
	480	450	>202	Y	<1	N	N	-	Y	N	N	N		N	N	
481	450	N/T	Y	1	N	N	-	Y	N	N	N	N	N			
482	450	>202	Y	1	N	N	-	Y	N	N	N	N	N			



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS

INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

DP No:	Lot 1001 DP486181	Property Address	310 Lakes Boulevard, Pyes Pa	RC No:	21332												
Lot No:	Subsurface data		Foundations		Comments												
	Area (m ²)	Shear Strength (kPa) at 0.5m depth	Subdivision Filling	Natural Topography Unworked		Natural Topography Earthworked	Conventional Shallow Foundation to NZS 3604:2011	Specific Design	Building Restriction Line	S/W Specific Design	S/W Soakage	S/W Reticulate	Designated Building Platform	Minimum Building Platform	Compressible Soils	On-Site Effluent Disposal	Consent Notice
	Y/N	Depth (m)	Y/N	Y/N	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA	Y/N/NA
483	554	N/T	Y	1	N	N	N	-	Y	N	N	N	N	N	N	N	N
484	480	>202	Y	1	N	N	N	-	Y	N	N	N	N	N	N	N	N
485	489	N/T	Y	<1	N	N	N	-	Y	N	N	N	N	N	N	N	N
486	553	>202	Y	<1	N	N	N	-	Y	N	N	N	N	N	N	N	N
487	567	N/T	Y	<1	N	N	N	<1	Y	N	N	N	N	N	N	N	N
488	596	190	N	-	N	N	N	1	Y	N	N	N	N	N	N	N	N
489	601	N/T	N	-	N	N	N	2	Y	N	N	N	N	N	N	N	N
490	638	173	Y	<1	N	N	N	3	Y	N	N	N	N	N	N	N	N
491	383	N/T	Y	<1	N	N	N	2	Y	N	N	N	N	N	N	N	N
492	350	N/T	N	-	N	N	N	3	Y	N	N	N	N	N	N	N	N

Suitable for standard foundations designed in accordance with NZS 3604, as per Section 8.6 of Coffey GCR ref: GENZTAUC13086AP-AK.



SUMMARY OF GOTECHNICAL DATA FOR INDIVIDUAL LOTS
INFRASTRUCTURE DEVELOPMENT CODE

G3	
VERSION 1	1
July 2011	

Appendix C - Pre Development Investigation Data

Engineering Log - Trial Pit

Trial Pit No. **TP06**
 Sheet 1 of 1
 Project No: **GENZTAUC13086AF**
 Date started: **14.3.2013**
 Date completed: **14.3.2013**
 Logged by: **KB**
 Checked by: **RBT**

Client: **THE LAKES 2012 LTD**
 Principal:
 Project: **THE LAKES STAGE 3 CONSTRUCTION**
 Trial pit location: **Refer to site plan**

Equipment type: Pit Orientation: Easting: 368704.4 m R.L. Surface:
 Excavation dimensions: m long m wide Vane No: DR2244 Northing: 799943.7 m Datum:

excavation information				material substance							
stratigraphy	water	notes samples, tests, etc	RL	depth metres	graphic log	classification symbol	material	moisture condition	consistency/density index	vane shear (remoulded) (kPa)	structure and additional observations
Younger Ash	Groundwater not encountered	Sample 17		0		OL	TOPSOIL	D			
		Sample 18		1		ML	SILT; light brown. Friable and dry.			●	
		Sample 19		2		ML	- becoming orange brown and moist below 1.0m.	M			×
		Sample 20		3		ML	SILT with trace fine sand and clay; orange brown. Greasy when reworked.				
		Sample 21		4		ML	SILT with minor sand and trace clay; bright orange. Low plasticity.				
RA			5		SP	Fine to coarse SAND with trace silt; orange brown. Occasional silty lenses. Sand is well graded.					
Hamilton Ash			6		ML	- becoming white/light brown below 3.2m.					
				7		ML	Clayey SILT; brown. Medium plasticity, very stiff, greasy when reworked.				UTP
				8			(Target depth) RA = Rotoehu Ash Test pit TP06 terminated at 5 metres.				

Sketch

classification symbols and soil description based on New Zealand Geotechnical Society Inc 2005	vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate water 10/1/98 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated	consistency/ density index VS very soft VL very loose S soft L loose F firm MD medium dense St stiff D dense VSt very stiff VD very dense H hard
notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample Bs bulk sample E environmental sample R refusal			

TRIAL PIT TEST PITS 150313.GPJ COFFEY.GDT 29.4.13

Engineering Log - Trial Pit

Trial Pit No. **TP07**
 Sheet 1 of 1
 Project No: **GENZTAUC13086AF**
 Date started: **14.3.2013**
 Date completed: **14.3.2013**
 Logged by: **KB**
 Checked by: **RBT**

Client: **THE LAKES 2012 LTD**
 Principal:
 Project: **THE LAKES STAGE 3 CONSTRUCTION**
 Trial pit location: **Refer to site plan**

Equipment type: Pit Orientation: Easting: 368767.5 m R.L. Surface:
 Excavation dimensions: m long m wide Vane No: DR2244 Northing: 799923.9 m Datum:

excavation information				material substance								
stratigraphy	water	notes samples, tests, etc	RL	depth metres	graphic log	classification symbol	material	moisture condition	consistency/density index	vane shear (remoulded) (kPa)	structure and additional observations	
Younger Ash	Groundwater not encountered			1		OL	TOPSOIL	D				
						ML	SILT; light brown. Friable and dry.					
						ML	- becoming orange brown with trace sand and moist below 1.0m.	M				
						ML	SILT with trace sand and clay; orange brown. Greasy when reworked.					
ML	SILT with minor sand; bright orange.											
RA	Groundwater not encountered			2		SP	Fine to coarse SAND with trace silt; orange brown. Pumiceous, well graded.					
						- becoming light brown/white below 3.1m.						
HA	Groundwater not encountered			3		ML	Clayey SILT; brown. Medium plasticity and greasy when reworked.					
							- becoming orange brown below 4.0m.					
				4								
				5								
				6			(Target depth) RA = Rotoehu Ash HA = Hamilton Ash Test pit TP07 terminated at 5 metres.					

Sketch

classification symbols and soil description based on New Zealand Geotechnical Society Inc 2005	vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate water 10/1/98 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated	consistency/ density index VS very soft VL very loose S soft L loose F firm MD medium dense St stiff D dense VSt very stiff VD very dense H hard
notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample Bs bulk sample E environmental sample R refusal			

TRIAL PIT TEST PITS 150313.GPJ COFFEY.GDT 29.4.13

Trial Pit No. **TP08**
 Sheet 1 of 1
 Project No: **GENZTAUC13086AF**
 Date started: **15.3.2013**
 Date completed: **15.3.2013**
 Logged by: **RBT**
 Checked by: **RBT**

Engineering Log - Trial Pit

Client: **THE LAKES 2012 LTD**
 Principal:
 Project: **THE LAKES STAGE 3 CONSTRUCTION**
 Trial pit location: **Refer to site plan**

Equipment type: Pit Orientation: Easting: 368724 m R.L. Surface:
 Excavation dimensions: m long m wide Vane No: DR2244 Northing: 799993 m Datum:

excavation information				material substance							
stratigraphy	water	notes samples, tests, etc	RL	depth metres	graphic log	classification symbol	material	moisture condition	consistency/density index	vane shear (remoulded) (kPa)	structure and additional observations
Younger Ash	Groundwater not encountered	Sample 27		1		OL	Organic SILT with numerous fine rootlets; greyish brown.	D			
		Sample 28		1.5		ML	SILT with trace to minor clay, some fine rootlets; yellowish brown. Stiff, dry, friable.				
		Sample 29		2			- becoming moist, minor clay, occasional rootlets below 1.0m. - becoming mottled yellow/orange brown below 1.3m.	M			
		Sample 30		3		SP	Fine to coarse SAND with trace silt; yellow/brown with black flecks.				
		Sample 31		4		CL	Silty CLAY; chocolate brown with white flecks. Stiff to very stiff in-situ, soft and with medium to high plasticity when reworked.	M-W			
		Sample 32		5		ML	SILT with trace clay and trace fine sand; yellowish brown. Very stiff to hard, non plastic and moist.				
				6			(Target depth) RA = Rotoehu Ash HA = Hamilton Ash Test pit TP08 terminated at 5.2 metres.				

Sketch

classification symbols and soil description based on New Zealand Geotechnical Society Inc 2005	vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate water 10/1/98 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated	consistency/ density index VS very soft VL very loose S soft L loose F firm MD medium dense St stiff D dense VSt very stiff VD very dense H hard
--	---	---	---

Engineering Log - Machine Borehole

Client: **THE LAKES LTD (2012)**

Date started: **7.3.2014**

Principal:

Date completed: **7.3.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **SLC**





Machine Borehole

Location: **Crest of western slope**

Checked by: **RBT**

Drill model & mounting: Flight auger JD2 Easting: 368826.5 m Slope: -90° R.L. Surface: 56 m Vane No:
Hole diameter: 100 mm Drilling fluid: Northing: 799891.63 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects							
stratigraphy	method	support	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification	symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength	vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description		
	AD	N								SILT, low plasticity, brown; trace fine sand.	D										
VOLCANIC ASHES					55	1															
					54	2						-2.0m, becoming pale brown.									
HAMILTON ASH					53	3				Sandy SILT, low plasticity, pale brown, sand is fine to medium.											
					52	4						Clayey SILT, low plasticity, dark brown with some manganese inclusions.	D-M								
					51	5				-4.5m, becoming brown.	M										
					50	6															

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water  10/1/98 water level on date shown  water inflow  partial drill fluid loss  complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

Engineering Log - Machine Borehole

 Client: **THE LAKES LTD (2012)**

 Date started: **7.3.2014**

Principal:

 Date completed: **7.3.2014**

 Project: **STAGE 3 - ZONE 2**

 Logged by: **SLC**

Machine Borehole

 Location: **Crest of western slope**

 Checked by: **RBT**

 Drill model & mounting: Flight auger JD2 Easting: 368826.5 m Slope: -90° R.L. Surface: 56 m Vane No:
 Hole diameter: 100 mm Drilling fluid: Northing: 799891.63 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects										
stratigraphy	method	support	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description		moisture condition	consistency/density index	weathering alteration	estimated strength			vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description			
									Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.													number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)	particular	general
	AD	N	SPT 1,2,2 N*=4		49				Clayey SILT, low plasticity, dark brown with some manganese inclusions. (continued) Clayey SILT, medium plasticity, pale brown with black flecks. Clayey SILT, medium plasticity, pale brown with black flecks. (continued) -6.5m, becoming sticky.	M								40						
			SPT 1,2,2 N*=4		48				Sandy SILT, low plasticity, orange brown with black and pale grey flecks; some clay.	M-W								40						
					47				-8.5m, becoming cream brown, sticky, moist to wet, sand is fine to coarse.															
			SPT 0,0,0 N*=0		46				Sandy SILT, low plasticity, pale brown grey with dark brown manganese inclusions, some clay.									40						
			SPT 0,0,1 N*=1		45													50						
					44																			

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

Engineering Log - Machine Borehole

Client: **THE LAKES LTD (2012)**

Date started: **7.3.2014**

Principal:

Date completed: **7.3.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **SLC**

Machine Borehole

Location: **Crest of western slope**

Checked by: **RBT**

Drill model & mounting: Flight auger JD2	Easting: 368826.5 m	Slope: -90°	R.L. Surface: 56 m	Vane No:
Hole diameter: 100 mm	Drilling fluid:	Northing: 799891.63 m	Bearing:	Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects										
stratigraphy	method	support	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description		moisture condition	consistency/density index	weathering alteration	estimated strength			vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description			
									Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.				EW VW W MS S VS ES	25 50 75 100 125 150 175								number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)	particular	general
	AD	N	SPT 0,0,1 N*=1		43	13			Sandy SILT, low plasticity, pale brown grey with dark brown manganese inclusions, some clay. (continued)	M-W								50						
			SPT 0,0,0 N*=0		42	14												50						
			SPT 0,0,0 N*=0		41	15			Clay SILT, medium plasticity, pale grey.	W								30						
			SPT 0,0,0 N*=0		40	16																		
			SPT 0,0,0 N*=0		39	17												30						
					38	18																		

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

MACHINE BOREHOLE 13086AK_INVESTIGATION DATA.GPJ COFFEY.GDT 28.3.14

Engineering Log - Machine Borehole

 Client: **THE LAKES LTD (2012)**

 Date started: **7.3.2014**

Principal:

 Date completed: **7.3.2014**

 Project: **STAGE 3 - ZONE 2**

 Logged by: **SLC**

Machine Borehole

 Checked by: **RBT**

 Location: **Crest of western slope**

drilling information		material substance										rock mass defects										
stratigraphy	method	support	water	notes	RL	depth	graphic log	core recovery	classification	symbol	Material Description	moisture	consistency/	density index	weathering	alteration	estimated	vane shear	recovery %	RQD %	defect	defect description
				samples, tests, etc		metres					Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.	condition					strength	(remoulded /peak) kPa			spacing mm	number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)
MATUA SUB-GROUP	AD	N		SPT 0,0,0 N*=0	37	19	X				Clay SILT, medium plasticity, pale grey. (continued)	W							50			
				SPT 0,0,1 N*=1	36	20	X				EOBH, target depth. CFA04 terminated at 19.95 metres.								60			
					35	21																
					34	22																
					33	23																
					32	24																

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▽ 10/1/98 water level on date shown ▲ water inflow ▽ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

Engineering Log - Machine Borehole

Client: **THE LAKES LTD (2012)**

Date started: **7.3.2014**

Principal:

Date completed: **7.3.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **SLC**

Machine Borehole

Location: **Crest of western slope**

Checked by: **RBT**

Drill model & mounting: Flight auger JD2	Easting: 368826.5 m	Slope: -90°	R.L. Surface: 51 m	Vane No:
Hole diameter: 100 mm	Drilling fluid:	Northing: 800012.1 m	Bearing:	Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects							
stratigraphy	method	support	notes	RL	depth	graphic log	core recovery	classification	symbol	Material Description	moisture	consistency/	weathering	alteration	estimated	vane shear	recovery %	RQD %	defect	defect description	
			samples, tests, etc		metres					Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.	condition	density index			strength	(remoulded /peak) kPa			spacing mm	number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)	
																				particular	general
	AD	N			50	1				SILT, low plasticity, brown; trace fine sand.	D										
VOLCANIC ASHES																					
			groundwater not encountered		49	2															
					48	3				Silty SAND, fine to coarse, pale brown.	M										
					47	4				Sandy SILT, non plastic, pale brown with orange brown mottles, sand is fine to medium. Reworks to low plasticity.											
					46	5				Silty SAND, fine to medium, dark brown.											
										Sandy SILT, low plasticity, dark brown (non organic), some clay, sand is fine to coarse (possible remnants of lower Hamilton Ash). -4.5m, becoming pale brown.											
										Silty SAND, fine to medium, pale brown, pumiceous.	W										
										Sandy SILT, low plasticity, pale grey brown, wet, sand is fine to coarse. -5.3m, dark brown and orange brown mottles and streaks.											
										Clayey SILT, low to medium plasticity, pale grey.	M										
					45	6															

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

Engineering Log - Machine Borehole

Client: **THE LAKES LTD (2012)**

Date started: **7.3.2014**

Principal:

Date completed: **7.3.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **SLC**





Machine Borehole

Location: **Crest of western slope**

Checked by: **RBT**

Drill model & mounting: Flight auger JD2 Easting: 368826.5 m Slope: -90° R.L. Surface: 51 m Vane No:
Hole diameter: 100 mm Drilling fluid: Northing: 800012.1 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects								
stratigraphy	method	support	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description		moisture condition	consistency/density index	weathering alteration	estimated strength		vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description		
									Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.											number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)	particular	general
	AD	N			44	7			Clayey SILT, low to medium plasticity, pale grey. (continued) -6.0m, becoming medium plasticity.	M												
					43	8			-7.5m, some manganese inclusions.													
					42	9			-7.8m, becoming brown orange with pale grey and dark brown manganese inclusions.													
					41	10			-9.4m, becoming very dark brown with brown, pale brown, orange brown and pale grey mottles. Manganese rich lense @ <80%.													
					40	11			SILT, medium plasticity, orange, some clay and medium to coarse sand.													
					39	12			-11.6m, becoming brown with dark brown manganese deposits.													

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water  10/1/98 water level on date shown  water inflow  partial drill fluid loss  complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

MACHINE BOREHOLE 13086AK_INVESTIGATION DATA.GPJ COFFEY.GDT 28.3.14

Engineering Log - Machine Borehole

 Client: **THE LAKES LTD (2012)**

 Date started: **7.3.2014**

Principal:

 Date completed: **7.3.2014**

 Project: **STAGE 3 - ZONE 2**

 Logged by: **SLC**

Machine Borehole

 Checked by: **RBT**

 Location: **Crest of western slope**

 Drill model & mounting: Flight auger JD2 Easting: 368826.5 m Slope: -90° R.L. Surface: 51 m Vane No:
 Hole diameter: 100 mm Drilling fluid: Northing: 800012.1 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects					
stratigraphy	method	support	water	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength	vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description
AD	N					38	13	X		Sandy SILT, non plastic, brown, wet, sand is fine to coarse.	W								
								X		-13.0m, sand fraction increasing.									
								X		-13.5m, low plasticity.									
						37	14	X											
								X											
						36	15	X		-15.0m, becoming brown with dark brown manganese mottles.						95			
				SPT 0,1,2 N*=3				X											
								X											
						35	16	X											
								X											
								X											
						34	17	X		-16.5m, poor recovery.						80			
				SPT 0,2,5 N*=7				X											
								X											
						33	18	X											

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

Engineering Log - Machine Borehole

Client: **THE LAKES LTD (2012)**

Date started: **7.3.2014**

Principal:

Date completed: **7.3.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **SLC**

Machine Borehole

Location: **Crest of western slope**

Checked by: **RBT**

Drill model & mounting: Flight auger JD2	Easting: 368826.5 m	Slope: -90°	R.L. Surface: 51 m	Vane No:
Hole diameter: 100 mm	Drilling fluid:	Northing: 800012.1 m	Bearing:	Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects						
stratigraphy	method	support	water	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength	vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description	
MATUA SUB-GROUP	AD	N	groundwater not encountered	SPT 0,2,3 N*=5	32	19	[X pattern]			Sandy Clayey SILT, medium plasticity, brown and grey with dark brown manganese deposits, sand is medium to coarse. (continued)	W					95				
				SPT 1,1,2 N*=3	20	20				Silty CLAY, medium to high plasticity, pale grey. - no recovery below 19.4m. Silty CLAY continuation inferred below 19.										
					31	20				EOBH, target depth. CFA05 terminated at 19.95 metres.										
					30	21														
					29	22														
					28	23														
					27	24														

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▽ 10/1/98 water level on date shown ▲ water inflow ▽ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--



Machine Borehole No. **MH301**

Engineering Log - Machine Borehole

Sheet 1 of 4
Project No: **GENZTAUC13086AK**

Client: **THE LAKES LTD (2012)**

Date started: **15.1.2014**

Principal:

Date completed: **15.1.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **KMJ**

Machine Borehole

Location: **Crest of Section A-A**

Checked by: **RBT**

Drill model & mounting: T2 Tractor Mount Easting: 368841.822 m Slope: -90° R.L. Surface: 53 m Vane No:
Hole diameter: mm Drilling fluid: Northing: 799939.797 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects					
stratigraphy	method	support	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength	vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description	
TP	TT	C			52.5	0.5		OL	Organic SILT, no plasticity, organic odor, rootlets (TOPSOIL).	M	F								
					52.0	1.0		ML	SILT, no plasticity, yellow-brown, trace fine sand, minor rootlets. - becoming orange-brown, low plasticity						67				
			SPT 1,0,1 N*=1		51.5	1.5			- becoming pale brown & wet, trace rootlets - increasing plasticity from 1.5 to 2.6m	M-W									
					51.0	2.0									100				
					50.5	2.5			- becoming brown to orange-brown, black specks										
			SPT 1,1,0 N*=1		50.0	3.0													
					49.5	3.5									100				
					49.0	4.0			- increasing sand content										
					48.5	4.5		SP	SAND, fine to medium grained, pale grey, black & white specks, some silt.										
			SPT 9,11,8 N*=19		48.0	5.0		ML	Sandy SILT, no plasticity, yellow-brown, white & black specks, sand is fine grained.	W	F-St								
					47.5	5.5		ML	SILT, pink-grey, low plasticity, minor orange streaks.						93				
								SP											

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

MACHINE BOREHOLE 13086AK_INVESTIGATION DATA.GPJ COFFEY.GDT 28.3.14

Form GEO 5.3 Rev.6

VOLCANIC ASHES

Engineering Log - Machine Borehole

 Client: **THE LAKES LTD (2012)**

 Date started: **15.1.2014**

Principal:

 Date completed: **15.1.2014**

 Project: **STAGE 3 - ZONE 2**

 Logged by: **KMJ**

Machine Borehole

 Checked by: **RBT**

 Location: **Crest of Section A-A**

 Drill model & mounting: T2 Tractor Mount Easting: 368841.822 m Slope: -90° R.L. Surface: 53 m Vane No:
 Hole diameter: mm Drilling fluid: Northing: 799939.797 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects																						
stratigraphy	method	support	water	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength					recovery %	RQD %	defect spacing mm	defect description														
										Soil name; plasticity or grading, colour, secondary components. Moisture, sensitivity, strength. Structure, bedding, cementation, defects. Origin, additional observations. Rock name; grain size & type, colour, fabric, inclusions & minor components. Weathering, moisture, strength, defects.				EW	VW	W	MS	S	VS	ES	25	50	75	100	125	150	175	30	100	300	1000	3000	number, type, orientation, shape, roughness, aperture, infill description (refer to defect description explanation sheet)			
VOLCANIC ASHES	TT	C				47.0	6.0		SP (cont)	SAND, fine to medium grained, brown, mottled orange/black/white. (continued)	W	VL														93										
				SPT 1,1,0 N*=1	46.5	6.5			CH	Clayey SILT/Silty CLAY, medium to high plasticity, trace fine sand. - sand pockets, fine grained from 6.6 to 6.7m	F																	100								
MATUA SUBGROUP						46.0	7.0			- increasing sand content from 8 to 8.5m																										
				SPT 0,1,1 N*=2	45.5	7.5				- becoming pale grey, minor yellow-green mottles from 8.5 to 8.7m	D-M																									
				SPT 2,3,4 N*=7	44.0	9.0				- becoming dry to moist, non to low plasticity from 8.7m																										
				SPT 1,1,1 N*=2	43.5	9.5				- pale orange staining from 10.3 to 10.5m	M-W																									
					42.5	10.5																														
					42.0	11.0			ML	SILT, low plasticity, pink-grey, mottled orange-brown, black specks.																										

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

MACHINE BOREHOLE 13086AK_INVESTIGATION DATA.GPJ COFFEY.GDT 28.3.14

Engineering Log - Machine Borehole

 Client: **THE LAKES LTD (2012)**

 Date started: **15.1.2014**

Principal:

 Date completed: **15.1.2014**

 Project: **STAGE 3 - ZONE 2**

 Logged by: **KMJ**

Machine Borehole

 Checked by: **RBT**

 Location: **Crest of Section A-A**

 Drill model & mounting: T2 Tractor Mount Easting: 368841.822 m Slope: -90° R.L. Surface: 53 m Vane No:
 Hole diameter: mm Drilling fluid: Northing: 799939.797 m Bearing: Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects					
stratigraphy	method	support	water	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description	moisture condition	consistency/density index	weathering alteration	estimated strength	vane shear (remoulded /peak) kPa	recovery %	RQD %	defect spacing mm	defect description
TT	C					41.5	11.5	XXXXXX	ML (cont)	SILT, low plasticity, pink-grey, mottled orange-brown, black specks. (continued) - orange staining - becoming pale grey with orange staining	M-W	F				100			
				SPT 0,0,0 N*=0		41.0	12.0	XXXXXX	ML	SILT, non to low plasticity, pink-orange with black & orange staining, mottled grey & black.						100			
						40.5	12.5	XXXXXX		- grey silt mottles from 12.8 to 13.0m						100			
						40.0	13.0	XXXXXX		- trace fine sand						27			
				SPT 0,0,0 N*=0		39.5	13.5	XXXXXX	ML SM	SILT, no plasticity, dark orange-brown with significant limonite staining, trace to minor sand, very stiff to hard. Sample has fragmented to angular, hard & soft pieces in silt/sand matrix.		S							
						39.0	14.0	XXXXXX	ML	Mixed silts & sands with some clay seams, brown, dark orange & black; soft, wet to saturated. Sample probably disturbed by SPT.									
						38.5	14.5	XXXXXX		Sandy Clayey SILT, low plasticity, pink-orange, dark orange staining; sand is fine grained, dark orange-brown. - increasing clay content, high plasticity; minor sand - increasing dark orange sand content, low to medium plasticity									
				SPT 1,0,1 N*=1		38.0	15.0	XXXXXX	MH	SILT, medium to high plasticity, orange-grey, trace fine sand.									
						37.5	15.5	XXXXXX		- some dark orange sand pockets, with some dark orange staining - becoming low to medium plasticity									
						37.0	16.0	XXXXXX	SM MH	Silty SAND, fine to medium grained, black, trace silt. - becoming orange-brown, mottled black & orange	W								
						36.5	16.5	XXXXXX		SILT, medium to high plasticity, pink-orange grey.		F							

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▼ 10/1/98 water level on date shown ▲ water inflow ▲ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--



Machine Borehole No. **MH301**

Engineering Log - Machine Borehole

Sheet 4 of 4
Project No: **GENZTAUC13086AK**

Client: **THE LAKES LTD (2012)**

Date started: **15.1.2014**

Principal:

Date completed: **15.1.2014**

Project: **STAGE 3 - ZONE 2**

Logged by: **KMJ**

Machine Borehole

Location: **Crest of Section A-A**

Checked by: **RBT**

Drill model & mounting: T2 Tractor Mount	Easting: 368841.822 m	Slope: -90°	R.L. Surface: 53 m	Vane No:
Hole diameter: mm	Drilling fluid:	Northing: 799939.797 m	Bearing:	Datum: x/y = BOPC2000, z = Moturiki

drilling information				material substance										rock mass defects													
stratigraphy	method	support	water	notes samples, tests, etc	RL	depth metres	graphic log	core recovery	classification symbol	Material Description		moisture condition	consistency/density index	weathering alteration	estimated strength				vane shear (remoulded / peak) kPa	recovery %	RQD %	defect spacing mm	defect description				
MATUA SUBGROUP	TT	C		SPT 1.0,1 N*=1	36.0	17.0	[X pattern]		MH	- increasing sand content - 50mm fine brown sand lenses/layers - black specks, heavy orange staining		W	F														
					35.5	17.5				Sandy SILT, medium to high plasticity, dark pink-brown, dark orange staining, abundant black specks; sand is fine to medium grained, orange-brown.																	
					35.0	18.0				- decreasing sand content - becoming low plasticity, dark brown, black specks and orange mottles																	
					34.5	18.5				MH	SILT, medium to high plasticity, pink-orange, some black mottles.																
					34.0	19.0					ML																- increasing sand content Sandy SILT/ Silty SAND, low plasticity, pink-orange brown, white & black specks, sand is fine to medium grained.
33.5	19.5	- increasing sand content, orange & black staining																									
				SPT 0.0,0 N*=0	33.0	20.0				EOBH @ 19.95m, target depth TS = TOPSOIL MH301 terminated at 19.95 metres.																	
				SPT 1.1,3 N*=4	32.5	20.5																					
					32.0	21.0																					
					31.5	21.5																					
					31.0	22.0																					

method AD auger drilling OB open barrel TT triple tube W washbore support N nil C casing vane shear (kPa) ● remoulded × peak >>> peak greater than 200kPa UTP unable to penetrate	classification symbols and soil description based on Field Description of Soil and Rock, New Zealand Geotechnical Society Inc 2005 notes, samples, tests U ₅₀ undisturbed sample 50mm diameter U ₆₃ undisturbed sample 63mm diameter D disturbed sample N* SPT - sample recovered Nc SPT with solid cone Bs bulk sample E environmental sample	water ▽ 10/1/98 water level on date shown ▲ water inflow ▽ partial drill fluid loss ▲ complete drill fluid loss moisture D dry M moist W wet S saturated	consistency/ density index VS very soft S soft F firm St stiff VSt very stiff H hard VL very loose L loose MD medium dense D dense VD very dense	weathering UW unweathered SW slightly weathered MW moderately weathered HW highly weathered CW completely weathered RS residual soil rock mass strength EW extremely weak VW very weak W weak MS moderately strong S strong VS very strong ES extremely strong
--	---	---	--	--

MACHINE BOREHOLE 13086AK_INVESTIGATION DATA.GPJ COFFEY.GDT 28.3.14

Form GEO 5.3 Rev.6

Appendix D - Post Development Investigation Data

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 413**

Borehole ID: **HAL413**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Net Encountered	1		VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2		VS 190/41 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand.	M			FILL
	3		VS 160/18 kPa		1.0			SILT: non plastic to low plasticity, pale brown, with trace fine to coarse grained sand and with trace clay. 0.6 m: with minor to some fine to coarse grained sand 0.8 m: with minor to some fine grained sand				MATUA SUBGROUP
			VS >202 kPa		1.5			SAND: fine to coarse grained, pale brown, with trace silt.				
			VS >202 kPa		2.0			Clayey SILT: low to medium plasticity, brown, with trace fine grained sand.				
			VS >202 kPa		2.5			SILT: low plasticity, orange brown, with trace clay and with trace fine grained sand.				
			VS >202 kPa		3.0			1.8 m: with some clay 2.0 m: sand becomes absent				
			VS 163/46 kPa		3.5			2.5 m: low to medium plasticity				
			VS 122/32 kPa		4.0							
			VS >202 kPa		4.5							
		VS 178/46 kPa		5.0				Hand Auger HAL413 terminated at 3.5 m Target depth				

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration 	water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 415**

Borehole ID. **HAL415**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D	VSt to H		TOPSOIL
	2	VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand. Clayey SILT: low to medium plasticity, brown.	D to M M			MATUA SUBGROUP
	3	VS >202 kPa		1.0			1.0 m: becoming orange brown, low plasticity				
		VS >202 kPa		1.5			1.8 m: becoming medium plasticity				
		VS 122/ 29 kPa		2.0							
		VS 102/ 42 kPa		2.5			Hand Auger HAL415 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  no resistance ranging to refusal water 10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	--	--	---	--


* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 417**

Borehole ID: **HAL417**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1 2 3	Not Encountered	VS >202 kPa		0.5		SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components	ORGANIC SILT: non plastic, black.	D	St to VSt		TOPSOIL
			VS 165/ 25 kPa		0.5			SILT: low plasticity, orange brown, with minor clay and with trace manganese.	D to M		MATUA SUBGROUP	
			VS 125/ 15 kPa		1.0			0.5 m: with some clay. Becomes greasy when reworked	M			
			VS 85/ 15 kPa		1.0			0.9 m: with trace fine to coarse sand				
			VS 173/ 58 kPa		1.5			1.0 to 1.6 m: sensitive when disturbed				
			VS 122/ 32 kPa		2.0			1.2 m: sand becomes absent				
			VS 79/ 24 kPa		2.1			1.8 m: becoming pinky brown and sensitive when disturbed				
			VS 98/ 29 kPa		2.5			2.1 m: becoming pink				
					2.5			Hand Auger HAL417 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 419**

Borehole ID: **HAL419**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance				
method & support	penetration	samples & field tests	RL (m)	depth (m)	material description	moisture condition	consistency / relative density	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0 - 0.5	ORGANIC SILT: non plastic, black. SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine grained sand. SILT: low plasticity, orange brown, with some clay and with trace fine to coarse grained sand.	M	St to VSt	TOPSOIL FILL MATUA SUBGROUP
	2	VS 112/ 19 kPa		0.5 - 1.0	0.8 m: with trace manganese			
	3	VS 85/ 15 kPa		1.0 - 1.5	0.9 m: becomes sticky/greasy when reworked			
		VS 83/ 19 kPa		1.5 - 2.0				
		VS 117/ 35 kPa		2.0 - 2.5				
		VS 124/ 29 kPa		2.5 - 2.6				
		VS 112/ 18 kPa		2.6 - 2.7	Clayey SILT: low plasticity, pink orange-brown, with trace fine grained sand. Sticky.			
		VS 102/ 26 kPa		2.7 - 2.5	Hand Auger HAL419 terminated at 2.5 m Target depth			

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 420**

Borehole ID. **HAL420**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2		VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand. 0.5 m: with trace clay	M			YOUNGER ASH DEPOSIT
	3		VS >202 kPa		1.0			SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand, with trace clay and with trace manganese. Greasy when reworked.				MATUA SUBGROUP
			VS 177/29 kPa		1.5			Sandy SILT: non plastic, orange brown, sand is fine to coarse grained.		St		
			VS 98/26 kPa		2.0			SILT: low plasticity, orange brown, with minor clay and with trace fine to coarse grained sand.				
		VS 78/26 kPa		2.5			Hand Auger HAL420 terminated at 2.5 m Target depth					
		VS 71/24 kPa										
		VS 71/25 kPa										

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 424**

Borehole ID: **HAL424**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1 2 3	VS >202 kPa VS 148/ 41 kPa VS 139/ 19 kPa VS >202 kPa VS >202 kPa	VS >202 kPa VS >202 kPa	0.5 1.0 1.5 2.0 2.5		M	VS to H	ORGANIC SILT: non plastic, black.	TOPSOIL			
								SILT: low plasticity, orange brown, with trace fine grained sand and trace clay. 0.7 m: with minor clay. Low to medium plasticity		YOUNGER ASH DEPOSIT		
								SILT: non plastic, orange brown, with some fine to coarse grained sand. SAND: fine to coarse grained, yellow brown, with trace silt. 1.9 m: with some silt		MATUA SUBGROUP		
								SILT: non plastic to low plasticity, brown, with trace fine to coarse grained sand and with trace clay. Sticky.				
								Hand Auger HAL424 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY\GLB rev\AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 426**

Borehole ID. **HAL426**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2		VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	M			YOUNGER ASH DEPOSIT
	3		VS 156/35 kPa		1.0			0.9 m: with trace clay. Low plasticity				
			VS >202 kPa		1.5			1.2 m: sand becomes absent				
			VS 197/58 kPa		2.0			1.4 m: with minor to some clay. Low to medium plasticity				
			VS >202 kPa		2.5			Hand Auger HAL426 terminated at 2.5 m Target depth				
					3.0							
					3.5							
					4.0							
					4.5							
					5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 428**

Borehole ID. **HAL428**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.:

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2		VS >202 kPa		0.8			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	M			YOUNGER ASH DEPOSIT
	3		VS 156/44 kPa		1.4			0.8 m: with fine grained sand				
			VS >202 kPa		2.2			1.4 m: with minor clay. Low plasticity				
			VS 166/44 kPa		2.5			2.2 m: becomes low to medium plasticity				
			VS 182/109 kPa		2.5			Hand Auger HAL428 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 430**

Borehole ID: **HAL430**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **NM**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: DR2244

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >182 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt		TOPSOIL	
	2		VS >182 kPa		0.5			SILT: non plastic, orange brown, with minor fine grained sand. 0.6 m: becoming fine to medium grained sand				FILL	
	3		VS >182 kPa		1.0			SILT: non plastic, black, with minor fine to medium grained sand.					
				VS >182 kPa		1.5			SILT: non plastic, orange brown with mottled brown, with minor fine to medium grained sand. becoming grey brown with minor fine grained sand	M			YOUNGER ASH DEPOSIT
				VS 164/ 29 kPa		2.0				M to W			
			VS 148/ 36 kPa		2.5			Hand Auger HAL430 terminated at 2.5 m Target depth					
			VS 158/ 30 kPa		3.0								
			VS 166/ 30 kPa		3.5								
			VS 91/ 24 kPa		4.0								
					4.5								
					5.0								

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration 	water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


Borehole ID. **HAL432**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **17 Aug 2016**
 date completed: **17 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 432**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	samples & field tests	water	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1	VS 187/ 46 kPa			0.0			ORGANIC SILT: non plastic, black.	D	VSt		TOPSOIL	
	2	VS 156/ 38 kPa			0.5			SILT: low plasticity, orange brown, with trace fine grained sand and with trace clay.	D to M			YOUNGER ASH DEPOSIT	
	3	VS 122/ 26 kPa			1.0								
		VS 134/ 29 kPa			1.5				1.2 m: with some clay and with trace fine to coarse grained sand				
		VS 156/ 44 kPa			2.0								
	VS >202 kPa			2.5				SAND: fine to coarse grained, orange, with trace silt.	M			ROTOEHU ASH	
	VS 187/ 44 kPa			3.0				SILT: non plastic to low plasticity, pale brown with mottled orange brown, with minor clay and with trace fine to coarse grained sand.				MATUA SUBGROUP	
	VS 156/ 58 kPa			4.0				Hand Auger HAL432 terminated at 2.5 m Target depth					

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration  no resistance ranging to refusal	water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		





* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 434**

Borehole ID: **HAL434**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >202 kPa	0.5	0.5			SILT: non plastic, brown with mottled orange brown, with trace fine grained sand.	D	VSt		FILL
			VS >202 kPa									
HA	N	Not Encountered	VS >202 kPa	1.0	1.0			SILT: non plastic, orange brown, with trace fine to medium grained sand.	D to M			YOUNGER ASH DEPOSIT
			VS 166/32 kPa					0.9 m: with minor clay, low plasticity				
			VS 148/29 kPa					1.5 m: with trace fine grained sand				
			VS 187/44 kPa									
HA	N	Not Encountered	VS 122/38 kPa	2.0	2.0							
			VS 96/24 kPa									
HA	N	Not Encountered		2.5	2.5			2.4 m: with trace fine to coarse grained sand				
								Hand Auger HAL434 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:48

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 436**

Borehole ID: **HAL436**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SAND: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa		1.0			SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace to minor fine to coarse grained sand.				FILL	
	3		VS >202 kPa		1.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	M			YOUNGER ASH DEPOSIT	
			VS 192/49 kPa		1.5			1.5 m: with trace clay. Low plasticity					
			VS 161/36 kPa		1.8			1.8 m: with minor clay.					
		VS 185/39 kPa		2.0									
		VS 146/31 kPa		2.5									
					2.5			Hand Auger HAL436 terminated at 2.5 m Target depth					
					3.0								
					3.5								
					4.0								
					4.5								
					5.0								

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  water 	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	---	---	---	--


* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 438**

Borehole ID. **HAL438**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1	VS >202 kPa		0.5			ORGANIC SILT: non plastic, black. SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace to minor fine to coarse grained sand. Sandy SILT: non plastic, grey brown, sand is fine to coarse. With trace fine to coarse grained gravel. SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	D to M	VSt to H		TOPSOIL FILL	
	2	VS >202 kPa		1.0				M			YOUNGER ASH DEPOSIT	
	3	VS >202 kPa		1.5								
		VS >202 kPa		2.0				1.4 m: becomes brown. With trace clay. Low plasticity				
		VS >202 kPa		2.5				1.7 m: with minor clay				
		VS 173/41 kPa		2.5				Hand Auger HAL438 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 441**

Borehole ID: **HAL441**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **NM**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: DR2244

drilling information				material substance					structure and additional observations			
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition		consistency / relative density	vane shear (kPa)	
HA N Not Encountered	1	VS >182 kPa					ORGANIC SILT: non plastic, black.	D	VSt	50	TOPSOIL FILL VS UTP YOUNGER ASH DEPOSIT	
	2	VS >182 kPa		0.5			SILT: non plastic, orange brown, with some fine grained sand. 0.4 m: with trace clay			100		
	3	VS >182 kPa						0.8 m: becoming mottled dark brown and with some fine to medium grained sand	D to M			150
		VS >182 kPa		1.0				1.0 m: becoming mottled dark brown and white				200
		VS UTP							D			
		VS >182 kPa		1.5				SILT: non plastic, dark brown, with some organic silt and with minor fine grained sand.				
		VS >182 kPa		2.0				SILT: non plastic, yellow brown, with some fine grained sand.	M			
		VS >182 kPa		2.5					M to W			
	VS 116/23 kPa											
	VS 148/33 kPa			2.5			Hand Auger HAL441 terminated at 2.5 m Target depth					
				3.0								
				3.5								
				4.0								
				4.5								
				5.0								

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 442**

Borehole ID: **HAL442**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >202 kPa	0.5	0.5		D	SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand.	D	VSt	50	FILL
			VS >202 kPa					100				
			VS >202 kPa		1.0			1.1 to 1.2 m: with mottled black 1.2 to 1.3 m: with trace rootlets				
			VS >202 kPa		1.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	D to M			YOUNGER ASH DEPOSIT
			VS 156/ 34 kPa		2.0		1.8 m: with trace fine grained sand and with trace clay					
			VS 133/ 26 kPa		2.5			Hand Auger HAL442 terminated at 2.5 m Target depth				
			VS 112/ 22 kPa		3.0							
					3.5							
					4.0							
					4.5							
					5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


Borehole ID. **HAL445**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **NM**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 445**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: DR2244

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >182 kPa					ORGANIC SILT: non plastic, black.	M	VSt		TOPSOIL	
	2		VS >182 kPa		0.5			SILT: non plastic, orange brown, with minor fine grained sand.				FILL	
	3		VS >182 kPa					Sandy SILT: fine to coarse grained, non plastic, grey with mottled white, with fine to coarse grained sand and with trace angular gravel.	D				
			VS >182 kPa		1.0			SILT: low to medium plasticity, orange brown, with minor clay and with trace fine grained sand.					YOUNGER ASH DEPOSIT
			VS 173/36 kPa					1.2 m: becoming mottled red brown	M				
			VS >182 kPa		1.5			1.4 m: red brown mottling becomes absent. Becoming flecked white					
			VS >182 kPa		2.0								
			VS >182 kPa		2.1			2.1 m: becoming brown	D				
			VS >182 kPa		2.2			2.2 m: becoming black with mottled orange brown, non plastic, with minor fine to medium grained sand and with faint organic odour					
			VS >182 kPa		2.5			Hand Auger HAL445 terminated at 2.5 m Target depth					

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration 	water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		



* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 447**

Borehole ID. **HAL447**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.5			SILT: non plastic, orange brown with mottled brown and black, with trace fine to coarse grained sand.	D	VSt	50	FILL 
	2		VS 166/ 54 kPa				SILT: non plastic, black, with trace fine grained sand and with faint organic odour.	D to M				
	3		VS >202 kPa		1.0		SILT: non plastic to low plasticity, orange brown with mottled brown and black, with trace fine to medium grained sand and with trace clay.					
			VS 160/ 54 kPa		1.5		1.2 m: orange brown with mottled brown and with trace to minor clay					
			VS >202 kPa		2.0							
			VS >202 kPa		2.5		2.4 m: with mottled black					
			VS >202 kPa		3.0		Hand Auger HAL447 terminated at 2.5 m Target depth					
			VS >202 kPa		4.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 449**

Borehole ID: **HAL449**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **NM**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: DR2244

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >182 kPa		0.5	[Cross-hatched pattern]	[Symbol]	SILT: non plastic, orange brown with mottled brown, with minor fine grained sand.	D to M	VSt	50 100 150 200	FILL	
	2		VS UTP					SAND: fine to medium grained, purple grey.					
	3		VS >182 kPa		1.0			SILT: non plastic to low plasticity, orange brown, with minor clay.		VSt			
			VS >182 kPa		1.1			1.1 m: becoming mottled purple grey, white and red brown	M to W				
			VS >182 kPa		1.4			1.4 m: becoming brown with mottled orange brown	D to M				
			VS >182 kPa		2.0								
			VS >182 kPa		2.5			SILT: non plastic, yellow brown, with some fine grained sand.	D				YOUNGER ASH DEPOSIT
			VS >182 kPa		2.5			Hand Auger HAL449 terminated at 2.5 m Target depth					
					3.0								
					3.5								
				4.0									
				4.5									
				5.0									

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 452**

Borehole ID: **HAL452**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >202 kPa	0.5	0.5			ORGANIC SILT: non plastic, black.	D	VSt		TOPSOIL
			VS >202 kPa					SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand and with trace clay.				FILL
			VS >202 kPa		1.0							
			VS >202 kPa		1.5							
			VS >202 kPa		2.0			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand and with trace clay.	D to M			YOUNGER ASH DEPOSIT
			VS 101/29 kPa		2.5			Hand Auger HAL452 terminated at 2.5 m Target depth				
					3.0							
					3.5							
					4.0							
					4.5							
					5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoued (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 453**

Borehole ID: **HAL453**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1	VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2	VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL	
	3	VS >202 kPa		1.0								
		VS >202 kPa		1.5								
		VS >202 kPa		2.0				SILT: non plastic, black.				YOUNGER ASH DEPOSIT
		VS >202 kPa		2.5				SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.				
		VS 194/46 kPa		2.5			Hand Auger HAL453 terminated at 2.5 m Target depth					

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 455**

Borehole ID. **HAL455**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2	VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL
	3	VS >202 kPa		1.0							
		VS >202 kPa		1.5							
		VS >202 kPa		2.0				SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.			
		VS 190/ 51 kPa		2.5			Hand Auger HAL455 terminated at 2.5 m Target depth				
		VS 173/ 85 kPa		2.5							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  water 10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	--	--	---	--






* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



Borehole ID. **HAL457**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 457**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.0 - 0.5			ORGANIC SILT: non plastic, black.	D to M	H		TOPSOIL
	2		VS >202 kPa		0.5 - 1.0			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL
	3		VS >202 kPa		1.0 - 1.5							
				VS >202 kPa		1.5 - 2.0						
			VS >202 kPa		2.0 - 2.5			SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand.				YOUNGER ASH DEPOSIT
			VS >202 kPa		2.5 - 2.5			Hand Auger HAL457 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49






method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 459**

Borehole ID. **HAL459**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **18 Aug 2016**
 date completed: **18 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.0 - 0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa		0.5 - 1.0			SILT: low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand.				FILL	
	3		VS >202 kPa		1.0 - 1.5								
				VS >202 kPa		1.5 - 2.0			SILT: low plasticity, brown, with trace fine grained sand.	M			MATUA SUBGROUP
				VS 153/29 kPa		2.0 - 2.5			Clayey SILT: low to medium plasticity, orange brown, with fine grained sand.				
					2.5			Hand Auger HAL459 terminated at 2.5 m Target depth					

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 460**

Borehole ID. **HAL460**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear	structure and additional observations
	1 2 3							SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components			⊕ ⊗ ⊙ ⊚	
			VS >202 kPa					ORGANIC SILT: non plastic, black.	D to M	VSt		TOPSOIL
			VS 177/ 44 kPa		0.5			SILT: non plastic to low plasticity, orange brown, with trace fine grained sand. 0.6 m: with trace clay			⊕ ⊙	YOUNGER ASH DEPOSIT
			VS 117/ 38 kPa		1.0			SILT: low plasticity, orange brown, with trace clay and with trace fine to coarse grained sand. Greasy when reworked.	M		⊕ ⊙	MATUA SUBGROUP
			VS 113/ 52 kPa		1.5			SILT: non plastic, pale brown, with some fine to coarse grained sand.			⊕ ⊙	
			VS 109/ 32 kPa		2.0						⊕ ⊙	
			VS 121/ 31 kPa		2.5			2.3 m: with trace fine to coarse grained sand. Is sensitive in hand sample			⊕ ⊙	
			VS >202 kPa		3.0			Clayey SILT: low to medium plasticity, brown, with trace fine grained sand.			⊕ ⊙	
			VS >202 kPa		3.5						⊕ ⊙	
			VS >202 kPa		4.0						⊕ ⊙	
			VS >202 kPa		4.5						⊕ ⊙	
			VS >202 kPa		5.0						⊕ ⊙	
					3.5			Hand Auger HAL460 terminated at 3.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 10-Oct-12 water level on date shown water inflow water outflow	



Engineering Log - Hand Auger

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 461**

Borehole ID: **HAL461**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >202 kPa					ORGANIC SILT: non plastic, black.	D	VSt		TOPSOIL
			VS >202 kPa				SILT: low plasticity, brown, with minor clay.	M				MATUA SUBGROUP
			VS 184/34 kPa		0.5			0.5 m: becoming orange brown				
			VS >202 kPa		1.0							
			VS 156/41 kPa		1.5							
			VS 71/22 kPa		2.0			1.8 m: becomes sticky/greasy when reworked		St		
			VS 71/21 kPa		2.0			2.0 m: with trace fine grained sand				
			VS 75/18 kPa		2.5			Hand Auger HAL461 terminated at 2.5 m Target depth				
					3.0							
					3.5							
					4.0							
					4.5							
					5.0							

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 	

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

Engineering Log - Hand Auger

client: **THE LAKES**
principal:
project: **THE LAKES STAGE 3GH**
location: **Centre of lot 463**

Borehole ID: **HAL463**
sheet: 1 of 1
project no. **GENZTAUC13086AP**
date started: **22 Aug 2016**
date completed: **22 Aug 2016**
logged by: **ODS**
checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1 2 3	VS >202 kPa		0.5		SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components	ORGANIC SILT: non plastic, black.	D	VSt to H	50 100 150 200	TOPSOIL
		VS 184/ 39 kPa					SILT: low plasticity, orange brown, with trace fine grained sand with trace clay.	M			YOUNGER ASH DEPOSIT
		VS 166/ 29 kPa					1.6 m: with trace fine to coarse grained sand				
		VS 158/ 29 kPa		1.0							
		VS >202 kPa		1.5							
		VS >202 kPa		2.0							
		VS 187/ 65 kPa		2.5			SAND: fine to coarse grained, orange brown, with minor silt.				MATUA SUBGROUP
				2.5			Hand Auger HAL463 terminated at 2.5 m Target depth				
				3.0							
				3.5							
				4.0							
				4.5							
				5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoued (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 465**

Borehole ID. **HAL465**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
			VS >202 kPa				SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand.					FILL
			VS >202 kPa				1.3 m: with trace clay. Low plasticity	M				YOUNGER ASH DEPOSIT
			VS 194/44 kPa		1.5							
			VS 122/24 kPa		2.0							
			VS 151/39 kPa		2.5							
					2.5			Hand Auger HAL465 terminated at 2.5 m Target depth				
					3.0							
					3.5							
					4.0							
					4.5							
					5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger



Borehole ID. **HAL467**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 467**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5		SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components ORGANIC SILT: non plastic, black.	D to M	VSt to H	50 100 150 200	● remoulded ○ peak	TOPSOIL	
	2		VS >202 kPa		1.0							SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand.	FILL
	3		VS >202 kPa		1.5		1.5 m: becomes dark brown with mottled orange brown	M				YOUNGER ASH DEPOSIT	
			VS >202 kPa		2.0		SILT: non plastic to low plasticity, orange brown, with trace fine sand. 2.0 m: with trace clay						
			VS >202 kPa		2.5		Hand Auger HAL467 terminated at 2.5 m Target depth						
			VS 112/ 35 kPa		2.5								

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  no resistance ranging to refusal water  10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	---	--	---	--







* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



Borehole ID. **HAL469**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 469**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2	VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand.				FILL
	3	VS 197/ 58 kPa		1.0			SILT: non plastic to low plasticity, orange brown, with trace fine sand. 1.0 m: with trace clay	M			YOUNGER ASH DEPOSIT
		VS >202 kPa		1.5					St		
		VS 71/ 38 kPa		2.0							
		VS 96/ 29 kPa		2.5			Hand Auger HAL469 terminated at 2.5 m Target depth				
				3.0							
				3.5							
				4.0							
				4.5							
				5.0							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  no resistance ranging to refusal water  10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	---	---	---	--

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 471**

Borehole ID: **HAL471**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance				
method & support	penetration	samples & field tests	RL (m)	depth (m)	material description	moisture condition	consistency / relative density	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0 - 0.5	ORGANIC SILT: non plastic, black.	D to M	VSt to H	TOPSOIL
	2	VS >202 kPa		0.5 - 1.0	SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand.			FILL
	3	VS >202 kPa		1.0 - 1.5				
		VS >202 kPa		1.5 - 2.0	SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand.	M		YOUNGER ASH DEPOSIT
		VS >202 kPa		2.0 - 2.5	2.0 m: with trace clay			
	VS 187/52 kPa			2.5 - 2.5	Hand Auger HAL471 terminated at 2.5 m Target depth			

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  water 10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	--	--	---	--







* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


Borehole ID. **HAL472**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **30 Aug 2016**
 date completed: **30 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 472**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.0 - 0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa		0.5 - 1.0			SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine to coarse grained sand.				FILL	
	3		VS >202 kPa		1.0 - 1.25			0.7 to 0.8 m: with trace fine to coarse angular gravel					
				VS >202 kPa		1.25 - 1.5			1.25 to 1.35 m: dark brown with mottled grey and brown with trace organic odour				
				VS >202 kPa		1.5 - 1.75			SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand.				YOUNGER ASH DEPOSIT
				VS >202 kPa		1.75 - 2.0			Hand Auger HAL472 terminated at 2.0 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 476**

Borehole ID. **HAL476**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **NM**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: DR2244

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA	N	Not Encountered	VS >182 kPa		0.5			ORGANIC SILT: non plastic, black.	D	VSt		TOPSOIL
								SILT: non plastic, orange brown, with minor fine grained sand.			FILL	
								0.6 m: becoming flecked white and purple				
								0.9 m: becoming mottled brown with white and purple flecks absent, with trace clay	M			
								1.3 m: with minor clay and with trace fine to medium grained angular gravel	M to W			
VS >182 kPa		2.0			SILT: non plastic, yellow brown, with minor fine grained sand.						YOUNGER ASH DEPOSIT	
VS 127/42 kPa		2.5			Hand Auger HAL476 terminated at 2.5 m Target depth							

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 478**

Borehole ID: **HAL478**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	H		TOPSOIL	
	2		VS >202 kPa		1.0			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine grained sand.				FILL	
	3		VS >202 kPa		1.5								
				VS >202 kPa		2.0			1.8 to 1.9 m: becomes brown with mottled black 1.95 m: with trace coarse grained gravel				
				VS >202 kPa		2.5			SILT: non plastic, black, with trace fine grained sand. Trace organic odour. SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.				YOUNGER ASH DEPOSIT
				VS >202 kPa		2.5			Hand Auger HAL478 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <-DrawingFile>> 10/01/2017 09:49


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoued (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


Borehole ID. **HAL480**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **22 Aug 2016**
 date completed: **22 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 480**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS >202 kPa		0.0 - 0.5		SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components	ORGANIC SILT: non plastic, black.	D to M	VSt to H	50 100 150 200	TOPSOIL
	2		VS >202 kPa		0.5 - 1.0			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine grained sand.				FILL
	3		VS >202 kPa		1.0 - 1.5		SILT: non plastic to low plasticity, orange brown, with trace fine grained sand.	M	YOUNGER ASH DEPOSIT			
			VS >202 kPa		1.5 - 2.0		1.9 m: with trace to minor clay. Low to medium plasticity.					
			VS 175/44 kPa		2.0 - 2.5							
			VS 173/44 kPa		2.5 - 2.5				Hand Auger HAL480 terminated at 2.5 m Target depth			

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  no resistance ranging to refusal water 10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	--	--	---	--

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger

client: **THE LAKES**
principal:
project: **THE LAKES STAGE 3GH**
location: **Centre of lot 482**

Borehole ID. **HAL482**
sheet: 1 of 1
project no. **GENZTAUC13086AP**
date started: **22 Aug 2016**
date completed: **22 Aug 2016**
logged by: **ODS**
checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0 - 0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
	2	VS >202 kPa		0.5 - 1.0			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL
	3	VS >202 kPa		1.0 - 1.5			SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand.				YOUNGER ASH DEPOSIT
		VS >202 kPa		1.5 - 2.0			1.5 m: with trace fine grained sand				
		VS 185/39 kPa		2.0 - 2.5							
		VS 185/39 kPa		2.5 - 2.5			Hand Auger HAL482 terminated at 2.5 m Target depth				

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 484**

Borehole ID. **HAL484**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1	VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2	VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL	
	3	VS >202 kPa		1.0								
		VS >202 kPa		1.5				SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand.				YOUNGER ASH DEPOSIT
		VS 201/ 58 kPa		2.0				1.7 m: with trace fine grained sand, and with minor clay. Low to medium plasticity				
		VS 139/ 38 kPa		2.5			Hand Auger HAL484 terminated at 2.5 m Target depth					
		VS 173/ 58 kPa		2.5								

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		



Engineering Log - Hand Auger

client: **THE LAKES**
principal:
project: **THE LAKES STAGE 3GH**
location: **Centre of lot 486**

Borehole ID. **HAL486**
sheet: 1 of 1
project no. **GENZTAUC13086AP**
date started: **23 Aug 2016**
date completed: **23 Aug 2016**
logged by: **ODS**
checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance				
method & support	penetration	samples & field tests	RL (m)	depth (m)	material description	moisture condition	consistency / relative density	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0 - 0.5	ORGANIC SILT: non plastic, black.	M	VSt to H	TOPSOIL
	2	VS >202 kPa		0.5 - 1.0	SILT: non plastic to low plasticity, orange brown with mottled brown, with trace fine grained sand.			FILL
	3	VS >202 kPa		1.0 - 1.5	SILT: low plasticity, orange brown, with trace fine to coarse grained sand.			YOUNGER ASH DEPOSIT
		VS 177/44 kPa		1.5 - 2.0	1.5 m: with trace clay			
		VS 172/32 kPa		2.0 - 2.5				
		VS >202 kPa		2.5 - 2.5	Hand Auger HAL486 terminated at 2.5 m Target depth			

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration 	moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	water 		

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 488**

Borehole ID: **HAL488**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations		
HA N Not Encountered	1 2 3	Not Encountered	VS >202 kPa	0.0 - 0.4	[Symbol]		ORGANIC SILT: non plastic, black.	D to M	VSt	50 100 150 200	TOPSOIL		
			VS 190/61 kPa	0.4 - 1.0	[Symbol]		SILT: low plasticity, orange brown, with minor clay and with trace fine grained sand. 0.4 m: with trace fine to coarse grained sand. Greasy when reworked					YOUNGER ASH DEPOSIT	
			VS 89/22 kPa	1.0 - 1.6	[Symbol]		Sandy SILT: non plastic, orange brown, sand is fine to coarse grained.			St			MATUA SUBGROUP
			VS 92/51 kPa	1.6 - 2.0	[Symbol]		1.6 m: becomes pale brown						
			VS 156/67 kPa	2.0 - 2.5	[Symbol]		SILT: low plasticity, pale brown, with trace clay and with trace fine to coarse grained sand.			M to W	VSt		
			VS 114/29 kPa	2.5 - 2.55	[Symbol]		Silty CLAY: medium plasticity, brown, with trace fine grained sand.			M			
			VS >202 kPa	2.55 - 2.58	[Symbol]		Hand Auger HAL488 terminated at 2.5 m Target depth						

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration  no resistance ranging to refusal	water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 490**

Borehole ID. **HAL490**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance							
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1	VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	St to VSt		TOPSOIL
	2	VS 173/29 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand.	M			FILL
	3	VS 128/24 kPa		1.0			SILT: low plasticity, brown orange, with minor clay and with trace fine to coarse grained sand. Greasy when reworked.				MATUA SUBGROUP
		VS 85/18 kPa		1.5			1.0 m: becomes orange brown. With trace silt				
		VS 114/36 kPa		2.0			1.3 m: with minor fine grained sand and with trace clay				
		VS 112/24 kPa		2.5			SAND: fine to coarse grained, orange brown, with trace silt.				
	VS >202 kPa		2.5			SILT: low plasticity, brown, with some clay and with trace fine grained sand.					
	VS >202 kPa		2.5			Hand Auger HAL490 terminated at 2.5 m Target depth					

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <-DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 493**

Borehole ID: **HAL493**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
HA N Not Encountered	1		VS 130/ 19 kPa		0.5			ORGANIC SILT: non plastic, black.	M	VSt to H		TOPSOIL
	2		VS 136/ 22 kPa					SILT: low plasticity, orange brown, with minor clay and with trace fine to coarse grained sand.				MATUA SUBGROUP
	3		VS 89/ 44 kPa		1.0			SILTY SAND: fine to coarse grained, orange brown.				
			VS 165/ 41 kPa		1.5			SILT: non plastic to low plasticity, pale orange brown, with trace to minor fine to coarse grained sand. 1.4 m: with some fine grained sand. Becoming pale brown				
			VS >202 kPa		2.0			SAND: fine to coarse grained, grey brown, with trace silt. Clayey SILT: low to medium plasticity, brown, with trace fine grained sand.				
			VS >202 kPa		2.5			SILT: non plastic to low plasticity, brown, with trace fine grained sand and with trace clay.				
			VS >202 kPa		3.0			2.8 m: becoming orange brown 2.9 m: sand becomes absent				
			VS >202 kPa		3.5			3.1 m: with trace fine grained sand and with minor clay 3.4 m: with trace manganese and becoming orange				
			VS >202 kPa		4.0			4.0 m: greasy when reworked				
			VS 104/ 38 kPa		4.5							
		VS 128/ 71 kPa		5.0				4.8 m: with minor to some manganese				
Hand Auger HAL493 terminated at 5.0 m Target depth												

CDF_0_9_06_LIBRARY\GLB rev.AT Log_COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:49

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoued (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 494**

Borehole ID: **HAL494**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa					SILT: low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand and with trace clay.				FILL	
	3		VS >202 kPa		1.0			SILT: non plastic to low plasticity, orange brown, with trace fine sand.	M			YOUNGER ASH DEPOSIT	
			VS 166/41 kPa		1.1 m:			with trace clay					
			VS >202/58 kPa		1.5			1.6 m: with minor clay. Low plasticity					
			VS 160/36 kPa		2.0								
			VS 96 kPa		2.5			SILT: low plasticity, orange brown, with minor clay and with trace fine to coarse grained sand.					MATUA SUBGROUP
			VS >202/69 kPa		3.0			Sandy SILT: non plastic to low plasticity, orange brown, sand is fine to coarse grained.					
			VS 182 kPa		3.5			SAND: fine to coarse grained, orange brown, with trace to minor silt.					
			VS >202 kPa		4.0			SILT: non plastic to low plasticity, orange brown, with trace fine to coarse grained sand and with trace clay.					
		VS >202 kPa		4.5			SILT: non plastic, brown, with trace to minor fine grained sand.						
		VS >202 kPa		5.0			SAND: fine to coarse grained, grey brown, with trace silt.						
		VS >202 kPa		5.0			Clayey SILT: low to medium plasticity, brown, with trace fine grained sand.						
		VS >202 kPa		5.0			SILT: low plasticity, orange brown, with minor clay and with trace fine grained sand and with trace manganese.						
		VS 160/75 kPa		5.0			4.6 m: with trace to minor manganese						
		VS 106/52 kPa		5.0			Hand Auger HAL494 terminated at 5.0 m Target depth						

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:50


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoued (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 495**

Borehole ID. **HAL495**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations		
method & support: HA hand auger N nil	penetration: VS >202 kPa	samples & field tests: VS >202 kPa	RL (m): Not Encountered	0.0		classification symbol: M	ORGANIC SILT: non plastic, black.	moisture condition: M	consistency / relative density: VSt to H	vane shear (kPa): VS >202	TOPSOIL		
				0.5			SILT: low plasticity, orange brown with mottled grey and brown, with trace fine to coarse grained sand and with trace clay.				FILL		
				1.0									
				1.5									
				2.0									
				2.5									
				3.0									
				3.5									
				4.0			VS 173/ 52 kPa				SILT: non plastic to low plasticity, orange brown, with trace fine grained sand and trace clay.		YOUNGER ASH DEPOSIT
				4.5			VS 194/ 46 kPa				3.7 m: with minor clay 4.0 m: becoming brown. Sand becomes absent.		
5.0	VS >202 kPa	4.5 m: with trace fine sand											
Hand Auger HAL495 terminated at 5.0 m Target depth													

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit		

Engineering Log - Hand Auger


client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 499**

Borehole ID. **HAL499**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	M	VSt to H		TOPSOIL	
	2		VS >202 kPa					SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL	
	3		VS >202 kPa		1.0								
			VS >202 kPa		1.5								
			VS >202 kPa		2.0								
			VS >202 kPa		2.5			2.3 m: with trace clay					
			VS 156/49 kPa		2.5								
			VS 173/52 kPa		3.0								
			VS 190/54 kPa		3.0								
			VS >202 kPa		3.5				3.7 to 4.0 m: becoming mottled black				
		VS >202 kPa		4.0				SILT: low plasticity, orange brown, with trace fine grained sand and with trace clay.				YOUNGER ASH DEPOSIT	
		VS >202 kPa		4.5									
		VS 156/52 kPa		4.5									
		VS 154/62 kPa		5.0				Hand Auger HAL499 terminated at 4.9 m Squeezing					

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 501**

Borehole ID. **HAL501**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance								
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations
	1 2 3							SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components			50 100 150 200	
HA	N							ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL
			VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL
			VS >202 kPa									
			VS >202 kPa		1.0							
			VS >202 kPa									
			VS >202 kPa		1.5							
			VS >202 kPa									
			VS 156/ 62 kPa		2.0							
			VS 190/ 62 kPa		2.5							
			VS >202 kPa					SILT: low plasticity, orange brown, with trace to minor clay and with trace fine grained sand.	M			YOUNGER ASH DEPOSIT
			VS >202 kPa		3.0							
			VS >202 kPa									
			VS >202 kPa		3.5							
			VS >202 kPa					3.6 m: with trace clay. Non to low plasticity				
			VS 194/ 52 kPa		4.0							
			VS >202 kPa					4.2 m: becoming brown orange with minor clay. Low plasticity				
			VS 166/ 66 kPa		4.5							
					5.0							
Hand Auger HAL501 terminated at 5.0 m Target depth												

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED 13086AP - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 502**

Borehole ID. **HAL502**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Net Encountered	1		VS >202 kPa		0.0			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled brown and grey, with trace fine to coarse grained sand.				FILL	
	3		VS >202 kPa		1.0			SILT: non plastic, orange brown, with trace fine sand.				YOUNGER ASH DEPOSIT	
			VS >202 kPa		1.5			1.4 m: with trace clay. Non to low plasticity					
			VS >202 kPa		2.0			2.3 m: becoming mottled brown					
			VS >202 kPa		2.5			2.6 m: becoming brown					
			VS >202 kPa		3.0			2.9 m: becoming orange brown					
			VS 178/39 kPa		3.5			3.3 m: with minor clay. Low plasticity					
			VS 184/46 kPa		4.0			Clayey SILT: low to medium plasticity, orange brown, with trace fine grained sand.	M				MATUA SUBGROUP
			VS 148/35 kPa		4.5								
		VS 190/52 kPa		4.6									
		VS >202 kPa		4.6				Hand Auger HAL502 terminated at 4.6 m Squeezing					

CDF_0_9_06_LIBRARY.GLB rev.AT Log_COF_BOREHOLE:NON CORED_13086AP-STAGE 3GH-ODS.GPJ <<DrawingFile>> 10/01/2017 09:50


method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	

Engineering Log - Hand Auger



client: **THE LAKES**
 principal:
 project: **THE LAKES STAGE 3GH**
 location: **Centre of lot 503**

Borehole ID. **HAL503**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **23 Aug 2016**
 date completed: **23 Aug 2016**
 logged by: **ODS**
 checked by: **RBT**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90°
 drill model: drilling fluid: hole diameter : 50 mm vane id.: SL588

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	structure and additional observations	
HA N Not Encountered	1		VS >202 kPa		0.5			ORGANIC SILT: non plastic, black.	D to M	VSt to H		TOPSOIL	
	2		VS >202 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled grey, with trace fine to coarse grained sand.	M			FILL	
	3		VS >202 kPa		1.0			SILT: non plastic to low plasticity, orange brown, with trace fine sand. 0.8 m: with trace fine to coarse grained sand 0.9 m: with trace clay. Low plasticity.				YOUNGER ASH DEPOSIT	
			VS 156/38 kPa		1.5								
			VS 156/38 kPa		2.0			SILT: low plasticity, brown orange, with minor clay and with trace fine to coarse grained sand. Greasy when reworked.					MATUA SUBGROUP
			VS 194/49 kPa		2.5								
			VS 170/38 kPa		3.0			SILT: non plastic to low plasticity, brown, with trace clay and with trace fine grained sand. 2.9 m: with some clay. Low plasticity					
			VS >202 kPa		3.5			3.3 m: becoming orange brown					
			VS >202 kPa		4.0			Hand Auger HAL503 terminated at 4.0 m Squeezing					
			VS >202 kPa		4.5								
		VS >202 kPa		5.0									

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED - STAGE 3GH - ODS.GPJ <<DrawingFile>> 10/01/2017 09:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  water 	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remouded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	---	---	---	--

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger

client: **The Lakes 2012 LTD**

principal: -

project: **The Lakes Stage 3 GCR**

location: **Centre of Lot 236**

Borehole ID. **HAL236**

sheet: 1 of 1

project no. **GENZTAUC13086AP**

date started: **16 Mar 2016**



date completed: **16 Mar 2016**

logged by: **NM**

checked by: **RBT**

position: Not Specified	surface elevation: Not Specified	angle from horizontal: 90°	DCP id.:
drill model: Hand Auger	drilling fluid:	hole diameter : 50 mm	vane id.:

drilling information				material substance								
method & support	penetration	water	samples & field tests	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations
HA N Not Encountered	1 2 3	VS >240 kPa VS 147/40 kPa VS 111/25 kPa VS 103/25 kPa VS 78/18 kPa VS 206/40 kPa		0.0 - 0.5		ML	TOPSOIL: SILT: low plasticity, brown, with minor fine grained sand, trace fine grained angular gravel.	D	H	⊕	2	TOPSOIL
				0.5 - 1.0		ML	SILT: non plastic to low plasticity, orange brown, with some fine grained sand.	D to M	VSt	⊕	3	YOUNGER ASH
				1.0 - 1.5		ML	Sandy SILT: non plastic, orange brown, with fine to medium grained sand.			⊕	4	
				1.5 - 2.0		SP	SILTY SAND: fine to medium grained, orange brown.		MD to D	⊕	5	
				2.0 - 2.5		ML	Sandy SILT: low plasticity, pale pink, with lenses of fine to medium grained pale pink sand.		St	⊕	6	
				2.5 - 3.0		SP	SAND: fine to medium grained, orange brown. At 1.6m: becoming white.		MD		7	
				3.0 - 3.5		ML	SILT: low plasticity, orange brown, with trace fine grained sand.		H	⊕	8	
				3.5 - 4.0			Hand Auger HA3D-236 terminated at 2.0 m Target depth					
				4.0 - 4.5								
				4.5 - 5.0								

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration  no resistance ranging to refusal	water 10-Oct-12 water level on date shown  water inflow water outflow	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED + DCP GCR HA - 09-03-2016 ODS.GPJ <<DrawingFile>> 10/01/2017 14:26

Engineering Log - Hand Auger



Borehole ID: **HAL237**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **16 Mar 2016**
 date completed: **16 Mar 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **The Lakes 2012 LTD**
 principal: -
 project: **The Lakes Stage 3 GCR**
 location: **Centre of Lot 237**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.: 2244-02

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations
HA	N	Not Encountered	VS >183 kPa		0.0			SILT: low plasticity, brown mottled pink, white and orange, with minor fine grained sand, trace fine to medium grained angular gravel.	D	MD			TOPSOIL
			VS >183 kPa		0.5			SILTY SAND: fine to coarse grained, brown with mottled pink brown, with trace fine to medium gravel.					FILL
			VS >183 kPa		1.0			0.7 m: becoming mottled dark brown SILT: non plastic, orange brown, with some fine to medium sand.	D to M	VSt			
			VS >183 kPa		1.5			1.0 m: sand becomes trace and plasticity becomes low 1.25 m: becoming mottled pink					
			VS >183 kPa		2.0			SILT: low plasticity, orange brown, with trace fine sand. 1.85 m: becoming mottled pale pink and dark brown					
			VS >183 kPa		2.0			Hand Auger HA3D-237 terminated at 2.0 m Target depth					

CDF_0_9_06_LIBRARY\GLB rev.AT Log COF BOREHOLE: NON CORED + DCP GCR HA - 09-03-2016 ODS.GPJ <<DrawingFile>> 10/01/2017 14:26

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
penetration 	water 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		




* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



Borehole ID: **HAL238**
 sheet: 1 of 1
 project no: **GENZTAUC13086AP**
 date started: **16 Mar 2016**
 date completed: **16 Mar 2016**
 logged by: **NM**
 checked by: **RBT**

client: **The Lakes 2012 LTD**
 principal: -
 project: **The Lakes Stage 3 GCR**
 location: **Centre of Lot 238**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.:

drilling information				material substance																					
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations												
HA N Not Encountered	1 2 3	VS 176/ 33 kPa VS >240 kPa VS >240 kPa VS >240 kPa VS >240 kPa VS >240 kPa	VS 176/ 33 kPa VS >240 kPa VS >240 kPa VS >240 kPa VS >240 kPa	0.5 1.0 1.5 2.0		ML ML ML ML ML	SILT: low plasticity, brown mottled pink, white and orange, with minor fine grained sand, trace fine to medium grained angular gravel. SILT: low plasticity, orange brown mottled brown, with trace fine grained sand, trace pockets of sandy silt. SILT: non plastic, pale orange, with some fine to medium grained sand. Sandy SILT: non plastic, pale brown mottled white and orange, streaked black, with fine to medium grained sand.. SILT: low plasticity, orange brown, with trace fine grained sand, trace clay.	D H	VSt H			FILL													
													Hand Auger HA3D-238 terminated at 2.0 m Target depth												

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED + DCP GCR HA - 09-03-2016 ODS.GPJ <<DrawingFile>> 10/01/2017 14:26

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	

Engineering Log - Hand Auger



Borehole ID. **HAL239**
 sheet: 1 of 1
 project no. **GENZTAUC13086AP**
 date started: **16 Mar 2016**
 date completed: **16 Mar 2016**
 logged by: **ODS**
 checked by: **RBT**

client: **The Lakes 2012 LTD**
 principal: -
 project: **The Lakes Stage 3 GCR**
 location: **Centre of Lot 239**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.: 2244-02

drilling information				material substance										
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations	
HA N Not Encountered	1		VS >183 kPa		0.0			SILT: low plasticity, brown mottled pink, white and orange, with minor fine grained sand, trace fine to medium grained angular gravel.	D	VSt	50	2	TOPSOIL	
	2		VS >183 kPa		0.5			SILT: non plastic to low plasticity, orange brown with mottled pale pink, with trace clay and trace fine sand. 0.5 m: trace gravel becoming present- are grey, medium to coarse and angular	D to M		100	3	FILL	
	3		VS >183 kPa		1.0			SILT: low plasticity, pink with mottled dark brown, with trace clay and trace to minor manganese. SAND: fine to coarse grained, pale brown, with some silt. 1.0 m: silt becomes trace 1.1 m: becomes brown 1.2 m: silt becomes minor		MD	150	4	MATUA SUBGROUP	
				VS >183 kPa		1.5			SILT: non plastic to low plasticity, orange brown, with some sand.			200	5	
				VS >183 kPa		2.0			SILTY SAND: fine to coarse grained, orange brown with mottled pale brown.				6	
				VS >183 kPa		2.0			Hand Auger HA3D-239 terminated at 2.0 m Target depth				7	
				VS >183 kPa		2.0							8	

CDF_0_9_06_LIBRARY.GLB rev.AT Log COF BOREHOLE: NON CORED + DCP GCR HA - 09-03-2016 ODS.GPJ <<DrawingFile>> 10/01/2017 14:26

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear: peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit	water 	

Appendix E – Fill Test Summary Tables

FILL TEST RESULTS FROM 2013 - 2015 EARTHWORKS PERIOD							
Summary of earthfill test data							
Test Number	Date	Test RL (m)	Result			Pass/Fail	
			Air Voids (%)	Shear Vane (kPa)	Scala (blows per 100mm)		
A-5	18/10/2013	58.44	0.8	127	-	Fail - area reworked	
A-6		58.83	2.2	209	-	Pass	
A-7		58.91	0.4	UTP	-	Pass	
A-8		58.38	2.7	236+	-	Pass	
A-9		59.09	1.9	UTP	-	Pass	
A-10		58.77	3.8	236+	-	Pass	
A-11		58.51	4.3	176	-	Pass	
A-12		58.71	3.5	86	-	Fail - Retested HAL447	
A-13		58.08	3.7	UTP	-	Pass	
A-29		30/10/2013	28.83	1.6	UTP	-	Pass
A-30	59.33		2.6	236+	-	Pass	
A-31	58.46		1.6	149	-	Pass	
A-32	59.00		0.0	180	-	Pass	
A-33	58.32		4.4	171	-	Pass	
A-34	58.81		0.0	220	-	Pass	
A-35	58.22		0.8	138	-	Marginal Pass	
A-36	58.67		0.3	UTP	-	Pass	
A-37	58.01		0.0	236+	-	Pass	
A-38	58.50		0.0	236+	-	Pass	
A-39	57.76		0.0	195	-	Pass	
A-40	58.28		5.6	UTP	-	Pass	
A-41	58.18		0.0	97	-	Fail - Retested HAL457	
A-42	58.24		4.9	UTP	-	Pass	
A-43	58.24		0.5	205	-	Pass	
A-44	58.53		0.0	197	-	Pass	
A-45	58.86		6.3	236+	-	Pass	
A-46	59.58		3.0	138	-	Marginal Pass	
A-47	59.43		1.3	9999	-	Pass	
A-48	59.23		5.8	236+	-	Pass	
B-01	15/10/2014	52.59	1.5	112	-	Pass - Retest done, see B11	
B-02		52.13	2.8	200	-	Pass	
B-03		52.06	-0.3	187	-	Pass	
B-04		51.71	-0.4	154	-	Pass	
B-05		52.2	0.2	84	-	Pass - Retest done, see B28	
B-06		58.72	2.6	226	-	Pass	
B-07		58.51	1.5	170	-	Pass	
B-08		58.77	-0.3	119	-	Fail - Retested HAL469-HAL471	
B-09		59.11	0.5	112	-	Fail - Retested HAL472	
B-10		59.09	1.8	167	-	Pass	
B-11	5/11/2014	52.8	3.6	187	-	Pass	
B-12		52.59	2.5	140	-	Pass	
B-13		52.08	0.5	109	-	Pass - Retest done, see B28	
B-14		53.62	4.1	204	-	Pass	
B-15		53.19	9.4	179	-	Pass	
B-16		53.58	2.4	158	-	Pass	
B-17		53.4	-0.1	171	-	Pass	
B-18		53.05	0.4	166	-	Pass	
B-19		53.06	4.5	189	-	Pass	
B-20		53.53	0.4	169	-	Pass	
B-21	14/11/2014	53.06	1	164	-	Pass	
B-22		52.68	2.4	157	-	Pass	
B-26		51.85	5.5	227	-	Pass	
B-27		53.12	6.2	184	-	Pass	
B-28		52.07	4	148	-	Pass	
B-29		55.4	2.4	179	-	Pass	
B-30		54.9	1.3	231	-	Pass	
B-31		27/11/2014	55.1	3.9	176	-	Pass
B-32			54.76	1.6	198	-	Pass
B-33			54.26	6.4	187	-	Pass
B-48	1/12/2014	55.55	4.5	166	-	Pass	
B-49		55.44	7.6	209	-	Pass	
B-50		55.22	4.8	150	-	Pass	
B-51	5/12/2014	54.95	6	174	-	Pass	
B-52		54.68	6.3	193	-	Pass	
B-53		56.26	3.2	219	-	Pass	
B-54		55.97	2	193	-	Pass	
B-55		55.98	1.2	231	-	Pass	
B-56		56.35	-0.2	213	-	Pass	
B-57		55.95	2.8	222	-	Pass	
B-58		56.06	11.3	220	-	Pass	
B-59		56.47	4.5	231	-	Pass	
B-60		57.02	6.6	227	-	Pass	


Test Number	Date	Test RL (m)	Result			Pass/Fail
			Air Voids (%)	Shear Vane (kPa)	Scala (blows per 100mm)	
B-61	9/12/2014	57.06	1.9	159	-	Pass
B-62		56.9	-1.9	222	-	Pass
B-63		56.81	1.2	163	-	Pass
B-64		56.65	3.1	204	-	Pass
B-65		56.06	4.5	221	-	Pass
B-168	16/02/2015	46.99	5	232	-	Pass
B-169		45.83	1.5	231	-	Pass
B-170		45.35	3.8	230	-	Pass
B-175	20/02/2015	49.28	-2.9	224	-	Pass
B-176		48.50	1.5	210	-	Pass
B-177	24/02/2015	48.99	1.8	220	-	Pass
B-178		48.76	7.7	225	-	Pass
B-179		49.55	0.8	203	-	Pass
B-180		50.17	1.3	232	-	Pass
B-181		47.50	1.4	232	-	Pass
B-182	26/02/2015	47.00	4.4	195	-	Pass
B-183		34.00	4.4	219	-	Pass
B-186	3/03/2015	53.69	2.5	232	-	Pass
B-187		53.67	2.1	230	-	Pass
B-190	9/03/2015	56.91	-1.6	232	-	Pass
B-191		57.67	4.3	195	-	Pass
B-192		57.37	11.9	210	-	Pass
B-193		58.66	4.7	226	-	Pass

Notes


- 1 Shear strength for NDM tests calculated from average of 4 vane tests at each test location.
- 2 A target Soilds Density of 2.44 t/m³ to 2.60 t/m³ was assumed for silt/ash fill.
- 3 UTP = Unable to Penetrate
- 4 Failed test areas were observed by Coffey and retested with sheervane and/or scala penetrometer.
- 5 All test locations and elevations surveyed by JMC Ltd.

Appendix F – Static Settlement Results


SETTLEMENT VS TIME



SETTLEMENT VS TIME (LOG SCALE)




SETTLEMENT VS TIME



DATE

SETTLEMENT VS TIME (LOG SCALE)



**Appendix G – Stage 3G Retaining Wall
Certification**

2 February 2017

Our ref: GENZTAUC13086AB-AF

The Lakes (2012) Ltd
C/- Harrison Grierson Consultants Ltd
Level 1 Harrison Grierson House
141 Cameron Road
Tauranga

Attention: Tony Mills

Dear Tony

The Lakes Stage 3G – Northern Boundary Retaining Wall Observation and Certification

This letter confirms that Coffey Services (NZ) Ltd (Coffey) visited the above site on numerous occasions to observe works associated with the construction of the timber pole retaining wall which runs along the northern boundary of Stage 3G. The observations were completed in general accordance with Coffey's design report¹ dated 16 June 2016 and the Tauranga City Council building consent number 55971.

The following items were checked or carried out on site:

- Verification of pre-drilled pile hole diameters depths and spacing's;
- Confirmation of soil conditions encountered within the boreholes;
- Verification of timber pole upright heights and diameters;
- Verification of timber lagging, dimensions and placement;
- Confirmation of safety fence installation.

As a result of our observations and site measurements, Coffey are satisfied that the subject retaining wall has been built in general accordance with the requirements of the design report and building consent.

A producer statement (PS4 – Construction Review) is attached to this letter.

¹ Coffey (2016) Retaining Wall Design Report for Stage 3G The Lakes, The Lakes Subdivision, Tauriko. Dated: 16 June 2016, Ref: GENZTAUC13086AB-AB

Limitations

This report has been prepared solely for the use of our client, The Lakes (2012) Limited and their professional advisors and contractors in relation to the specific project described herein. No liability is accepted in respect of its use for any other purpose or by any other person or entity. All future owners of this property should seek professional geotechnical advice to satisfy themselves as to its ongoing suitability for their intended use.

This document should always be read in its entirety and is not to be split for further distribution.

For and on behalf of Coffey



Rob Telford
Senior Engineering Geologist

Letter reviewed by:



David Sullivan, BSc, MBA, CE (Calif.), MIPENZ, CPEng,
TCC Category 1 Geotechnical Engineer
Principal Geotechnical Engineer
CPEng No. 1025183

Attachments

Site photographs

Producer Statement – PS4 – Construction Review

Photograph 1: Photo taken on the 10/11/16 of predrilled Pile holes 47 to 126.




Photograph 2: Photo taken on the 22/11/16 of the placement of piles.



CLIENT: The Lakes (2012) Ltd	PROJECT: 13086AB	DESIGNED: N.M	SITE PHOTOGRAPHS
	DWG #: A	DRAWN: N.M	
	REVISION:		
PROJECT TITLE: Stage 3G -Retaining Wall Observations and Certification	SCALE: NA	STATUS: FINAL	 <small>A TETRA TECH COMPANY</small>
	DATE: 23.01.17		

Photograph 3: Photo taken on the 22/11/16 of the final placement and alignment of retaining wall piles.



CLIENT: The Lakes (2012) Ltd	PROJECT: 13086AB	DESIGNED: N.M	SITE PHOTOGRAPHS
	DWG #: A	DRAWN: N.M	
	REVISION:		
PROJECT TITLE: Stage 3G -Retaining Wall Observations and Certification	SCALE: NA	STATUS: FINAL	 A TETRA TECH COMPANY
	DATE: 23.01.17		



PRODUCER STATEMENT – PS4 – CONSTRUCTION REVIEW

(Guidance notes on the use of this form are printed on page 2)

ISSUED BY: COFFEY SERVICES (NZ) LIMITED.....
(Construction Review Firm)

TO: THE LAKES (2012) LIMITED
(Owner/Developer)

TO BE SUPPLIED TO: TAURANGA CITY COUNCIL.....
(Building Consent Authority)

IN RESPECT OF: TIMBER POLE RETAINING WALL DESIGN.....
(Description of Building Work)

AT: THE LAKES STAGE 3G.....
(Address) LOT... 1001... DP 486181..... SO

COFFEY SERVICES (NZ) LTD has been engaged by THE LAKES (2012) LTD.....
(Construction Review Firm)

To provide CM1 CM2 CM3 CM4 CM5 (Engineering Categories) or observation as per agreement with owner/developer

or other PERIODIC INSPECTIONS DURING RETAINING WALL CONSTRUCTION..... services
(Extent of Engagement)

in respect of clause(s) B1/VM4 & F4..... of the Building Code for the building work described in

documents relating to Building Consent No. 55971..... and those relating to

Building Consent Amendment(s) Nos. N/A..... issued during the

course of the works. We have sighted these Building Consents and the conditions of attached to them.

Authorised instructions / variations(s) No. N/A..... (copies attached)

or by the attached Schedule have been issued during the course of the works.

On the basis of this these review(s) and information supplied by the contractor during the course of the works and on behalf of the firm undertaking this Construction Review, I believe on reasonable grounds that All Part only of the building works have been completed in accordance with the relevant requirements of the Building Consent and Building Consent Amendments identified above, with respect to Clause(s) B1/VM4 & F4..... of the Building Code.

I also believe on reasonable grounds that the persons who have undertaken this construction review have the necessary competency to do so.

I, David Sullivan..... am: CPEng No. ... 1025183.....
(Name of Construction Review Professional)

Reg Arch No.

I am a Member of: IPENZ NZIA and hold the following qualifications:

The Construction Review Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000*.

The Construction Review Firm is a member of ACENZ:

SIGNED BY ... David Sullivan..... ON BEHALF OF COFFEY SERVICES (NZ) LTD.....

Date: 3-2-17 Signature:

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000*.

This form is to accompany Forms 6 or 8 of the Building (Form) Regulations 2004 for the issue of a Code Compliance Certificate.

FORM OF PRODUCER STATEMENT PS3 – CONSTRUCTION

At project completion, this form shall be completed by the building contractor and supplied to the Engineer.

ISSUED BY: HIGGINS CONTRACTORS LTD
(Building Contractor)

TO: THE LAKES 2012
(Owner/Principal)

IN RESPECT OF: RETAINING WALL LAKES 3G
(Description of Contract Works)

AT: 3110L PYES PA RD
(Address)

T/A: TCC **BUILDING CONSENT No:** 55971
(Territorial Authority / Building Consent Authority)

The above Building Contractor has contracted to the above Owner/Principal to carry out and complete certain building works in accordance with the contract, titled

RETAINING WALL LAKES 3G ("the contract")
(Title of building contract)

STEVE PAPA a duly authorised representative of the
(Builder's Authorised Agent)

above building contractor, believe on reasonable grounds that the above building contractor has carried out and completed

All Part only as specified in the attached particulars

of the building works in accordance with the contract.


(Signature of Authorised Agent on behalf of the Building Contractor)

13/2/2017
(Date)


92 HEWLETTS RD
MT MAUNGANUI
(Address)

This producer statement is confirmation by the builder(s) that they have carried out the building work in accordance with the drawings, specifications (and site amendments) that are part of the contract / building consent documents.

Work covered by this statement should have been supervised and checked by suitably qualified tradespersons.

The Engineer requires this producer statement and a copy of the T/A's building consent conditions, to confirm that items of the contract that he has not personally examined, have in fact been built according to the documents, so that the Engineer may issue appropriate documents to the T/A for it to release the Code Compliance Certificate.

**Appendix H – Stage 3H Stormwater
Pipeline Drawings**



		ISO 9001 QUALITY ASSURED ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND <small>THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF HARTSON ENGINEERING AND MAY NOT BE REPRODUCED OR ALTERED WITHOUT THE WRITTEN CONSENT OF HARTSON ENGINEERING LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.</small>				Tauranga Office Level 4, Harbour Green House 100 Harbour Green T +64 7 978 023 W www.hartsonengineering.com		Summit THE LAKES (2012) LIMITED, TAURANGA		PROJECT: STAGE 3H STORMWATER LAYOUT PLAN		DRAWING NO: 138804-403 PROJECT NO: 1500-138804-01 SCALES: 1:1000 - A1 1:1000 - A3		CONSTRUCTION A1 REV	
DRAWN BY: RJM DATE: 20.10.16	CHECKED BY: TRS DATE: 15.06.16	DESIGNED BY: RJM DATE: 20.10.16	SURVEYED BY: RJM DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	SURVEYED BY: GPR DATE: 20.10.16	

NOTES:

- ALL WORKS TO BE CARRIED OUT TO TCC IDC 2011 AND ALL SUBSEQUENT AMENDMENTS.
- ALL STORMWATER AND WASTEWATER CONNECTIONS TO BE 150mm NB UPVC.
- ALL MANHOLES TO BE 1050mm DIA UNLESS OTHERWISE SHOWN.
- ALL STORMWATER PIPES ARE RCFRP UNLESS OTHERWISE STATED.
- ALL CONCRETE PIPES TO BE CLASS 2 UNLESS OTHERWISE STATED.
- ALL PVC PIPES TO BE SN16 UNLESS OTHERWISE STATED.
- ALL DEEP DRAINAGE CONNECTIONS TO BE RAMPED UP TO WITHIN 1.5m OF SURFACE.


LEGEND:

- PROPOSED STORMWATER
- EXISTING STORMWATER
- PROPOSED WASTEWATER
- EXISTING WASTEWATER
- PROPOSED STORMWATER MANHOLE
- EXISTING STORMWATER MANHOLE
- PROPOSED WASTEWATER MANHOLE
- EXISTING WASTEWATER MANHOLE
- PROPOSED STORMWATER RODDING EYE
- EXISTING STORMWATER RODDING EYE
- PROPOSED WASTEWATER RODDING EYE
- EXISTING WASTEWATER RODDING EYE
- EXISTING STORMWATER DOUBLE SUMP
- EXISTING WASTEWATER DOUBLE SUMP
- BUILDING LINE RESTRICTION
- EXISTING DRAIN

REFER TO SHEET 483 FOR OUTLET DETAILS


MANAKO STREAM

STAGE 3G



STORMWATER LINE AA LONGITUDINAL SECTION

SCALE HOR 1:500 - A1, 1:1000 - A3
VER 1:100 - A1, 1:200 - A3



STORMWATER LINE AB LONGITUDINAL SECTION

SCALE HOR 1:500 - A1, 1:1000 - A3
VER 1:100 - A1, 1:200 - A3

NO.	DATE	BY	DATE	BY	REVISIONS
1	15/06/16	RJM	20/10/16	RJM	ISSUED FOR CONSTRUCTION
2	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
3	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
4	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
5	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
6	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
7	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
8	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
9	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
10	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
11	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
12	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
13	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
14	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
15	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
16	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
17	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
18	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
19	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
20	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
21	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
22	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
23	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
24	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
25	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
26	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
27	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
28	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
29	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
30	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
31	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
32	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
33	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
34	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
35	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
36	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
37	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
38	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
39	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
40	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
41	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
42	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
43	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
44	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
45	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
46	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
47	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
48	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
49	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
50	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
51	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
52	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
53	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
54	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
55	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
56	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
57	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
58	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
59	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
60	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
61	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
62	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
63	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
64	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
65	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
66	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
67	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
68	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
69	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
70	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
71	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
72	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
73	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
74	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
75	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
76	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
77	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
78	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
79	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
80	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
81	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
82	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
83	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
84	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
85	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
86	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
87	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
88	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
89	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
90	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
91	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
92	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
93	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
94	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
95	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
96	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
97	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
98	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
99	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION
100	15/06/16	TKS	20/10/16	GPR	ISSUED FOR CONSTRUCTION

HCG

Tauranga Office
Level 1, Harbour Green House
100-102, Victoria Road, Tauranga 3111
T +64 7 578 0023
W www.hcgtauranga.co.nz


Summit

THE LAKES (2012) LIMITED, TAURANGA


PROJECT: STORMWATER LONGITUDINAL SECTION

STAGE 3H

ISSUE STATUS:	CONSTRUCTION
PROJECT NO: 1500-18804-01 <td>AS SHOWN</td>	AS SHOWN
SCALE: 1:500 - A1, 1:1000 - A3 <td></td>	
DRAWING NO: 138804-435 <td></td>	
REV	B



A PE PIPE CONNECTION SWMH AA/1
SCALE NTS
403



B SWHW AA/0 OUTLET DETAILS
SCALE 1:150 - 7/5
403


ROCK RIPRAP APRON GRADING TABLE

SEIVE SIZE	% PASSING
345 - 391	100
276 - 322	85
230 - 322	50
92 - 138	15


GRADING FOR IMPORTED BEDDING

SEIVE SIZE	% ALL PASSING
19.00	100
2.36	100 - 50
0.60	90 - 20
0.30	60 - 10
0.15	25 - 0
0.08	10 - 0


- NOTES:**
- ALL CONCRETE PIPE BEDDING HAS BEEN DESIGNED TO H2 SUPPORT TYPE.
 - REFER TO THE SPECIFICATION FOR MINIMUM COMPACTION STANDARDS OF THE BEDDING MATERIAL.
 - CONTRACTOR TO PROVIDE GRADING CURVE OF PROPOSED BEDDING MATERIAL TO ENGINEER FOR APPROVAL.
 - ALL DIMENSIONS ARE MINIMUM, AND MAY BE INCREASED ON SITE.
 - ALL WORK WITH CONCRETE PIPES TO BE IN ACCORDANCE WITH AS/NZS 3722.
 - ALL WORK WITH GRANULAR MATERIALS TO BE IN ACCORDANCE WITH AS/NZS 2566.



1 ANCHOR BLOCK DETAIL
SCALE 1:10 - A1
1:20 - A3




2 ANCHOR BLOCK CROSS SECTION
SCALE 1:10 - A1
1:20 - A3



BEDDING DETAILS uPVC PIPES

PIPE SIZE (mm)	X	Y	Z
100	75	100	100
150	75	100	100



BEDDING DETAILS CONCRETE PIPES

PIPE SIZE (mm)	X	Y	Z	O
300	100	110	665	150

		Summit THE LAKES (2012) LTD, TAURANGA		PROJECT: STAGE 3H DRAINAGE DETAILS TITLE:		ISSUE STATUS: CONSTRUCTION PROJECT NO: AS SHOWN DRAWING NO: 138804-483	
ISO 9001 QUALITY ASSURED ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF HARTSON ENGINEERING AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARTSON ENGINEERING. CONSULTANTS LIABILITY LIMITED, NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.		TARAUNGA OFFICE LEVIN HARBOR OFFICE 1500-18804-01 T 481 578 8023 W www.hartsonengineering.com		ISO 9001 QUALITY ASSURED ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF HARTSON ENGINEERING AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARTSON ENGINEERING. CONSULTANTS LIABILITY LIMITED, NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORIZED USE OF THIS DRAWING.		DATE: 26.09.16 DRAWN BY: TRS CHECKED BY: TRS APPROVED BY: TRS DATE: 26.09.16 DRAWN BY: TRS CHECKED BY: TRS APPROVED BY: TRS	
ISSUED FOR CONSTRUCTION BY: DATE:		REVISIONS		DATE: 26.09.16 DRAWN BY: TRS CHECKED BY: TRS APPROVED BY: TRS		DATE: 26.09.16 DRAWN BY: TRS CHECKED BY: TRS APPROVED BY: TRS	

PRODUCER STATEMENT – PS1 – DESIGN

(Guidance notes on the use of this form are available upon request)

ISSUED BY: *The Engineer Limited*
(Design Firm)TO: **Paul Marsh**
(Owner/Developer)TO BE SUPPLIED TO: **Tauranga City Council**
(Building Consent Authority)IN RESPECT OF: **Design of timber pole retaining wall**
(Description of Building Work)AT: **16 Okataina St, The Lakes**
(Address)**Tauranga**..... **LOT 237**..... **DP 507200** **SO**We have been engaged by the owner/developer referred to above to provide **Structural Design**
..... services in respect of the requirements of
(Extent of Engagement)Clause(s) **B1 Structure, B2 Durability**of the Building Code forAll or Part only (as specified in the attachment to this statement), of the proposed building work.

The design carried out by us has been prepared in accordance with:

 Compliance Documents issued by the Ministry of Business, Innovation & Employment **B1/VM1, B2/AS1**or
(verification method / acceptable solution) Alternative solution as per the attached schedule.....The proposed building work covered by this producer statement is described on the drawings titled **Marsh****16 Okataina St, The Lakes**and numbered **18031944 (27/3/2018)**.....; together with
the specification, and other documents set out in the schedule attached to this statement.

On behalf of the Design Firm, and subject to:

- (i) Site verification of the following design assumptions
- foundation conditions**
-
-
- (ii) All proprietary products meeting their performance specification requirements;

I believe on reasonable grounds that a) the building, if constructed in accordance with the drawings, specifications, and
other documents provided or listed in the attached schedule, will comply with the relevant provisions of the Building Code
and that b), the persons who have undertaken the design have the necessary competency to do so. I also recommend
the following level of construction monitoring/observation: CM1 CM2 CM3 CM4 CM5 (Engineering Categories) or as per agreement with owner/developer (Architectural)I, **Bruce Cameron**..... am: **CPEng 173256**#
(Name of Design Professional)I hold the following qualifications: **CPEng, BE, NZCE**. The Design Firm issuing this statement holds a current policy
of Professional Indemnity Insurance no less than \$200,000*.SIGNED BY **Bruce Cameron**..... ON BEHALF OF **The Engineer Limited**.....
(Design Firm)Date **27 March 2018** (signature)..... *Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the
Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building
Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of
\$200,000*.*This form is to accompany **Form 2 of the Building (Forms) Regulations 2004** for the application of a Building Consent.

CANTILEVER TIMBER POLE RETAINING WALL DESIGN

Client: Marsh
 Project: 16 Okataina Street, Lot 237 The Lakes


Project Number : 18031944
 Wall Location : Subdivision Retaining

Retaining Wall Design Features Report / Construction Summary

Wall Height H m	Pole Spacing S m	SED Pole Size mm	Embedment hole size Ø mm	Embedment depth E m	Rail size and mm	Rail Layers #
0.50	1.2	175	350	0.9	150x50	1 layer
1.00	1.2	200	350	1.5	150x50	1 layer
1.50	1.2	225	400	2.1	150x50	1 layer

notes:

- ~ Construction to be in accordance with the Specification for Timber Retaining Walls, including cut timber treatment
 - ~ Design assumes level firm ground at the base of the wall
 - ~ Poles to be place with large end into embedment holes
 - ~ Confirm site conditions match design assumptions
 - ~ Timber Rails Grade = VSG8 or Grade 8
 - ~ Timber Treatment; H4 Rails; H5 Poles
 - ~ Design assumes cohesion less or sandy type soils, water level depth > E
- 0 ° backfill slope
 5 kPa potential surcharge



TCC - Approved Building Consent Document - BC182234 - Pg 330 of 387 - 14/12/2018 - mkim

CANTILEVER TIMBER POLE RETAINING WALL DESIGN

Client: Marsh
Project: 16 Okataina Street, Lot 237 The Lakes

Project Number : 18031944
Wall Location : Subdivision Retaining

Retaining Wall

Soil Type : Cohesion less
Validation : surrounding excavation experience, BH water table > +2m depth

H = Retained height (m)	(Peak height)	1.5 m	
S = Pole spacing (m)		1.2 m	
β = Wall slope (°)		0 °	
ω = Backfill slope (°)		0 °	
q = Surcharge (kPa)		5 kPa	Adjacent to neighbour bdy, potential bid/veh surcharge
γ = Soil Density (kN/m ³)		16 kN/m ³	
φ = Internal friction angle (°)		30 °	
δ = Wall friction (allow $\frac{2}{3} * \phi$) (°)		20 °	
Ka = Active earth coefficient		0.30	
Ko = At rest earth coefficient		0.50	
Kp = Passive earth coefficient		6.44	

3.00 ignore wall slope, ground backslope & wall friction for foundation embedment design

Timber Pole Design

Timber Load Factors

G = 1.5 Q = 1.5 *Critical load case low (< 3m) routine retaining*

Timber pole properties

φ = Strength reduction factor	0.8	
k1 = Load duration factor	0.6	
K20 = Machine shaving / peeling	0.9	
K21 = Steaming factor	0.85	
fb = Bending strength (MPa)	38 MPa	(Density, med 38MPa, high 52MPa)
t = Tapper rate (mm/m)	8 mm/m	

Pole sizes (SED)

H (m) =	H + q _c =	Trial Dia (mm) =	∅M =	@ H + q _c	∅M >= M*	M*
0.50	0.97	175	8.4	ok	2.3 kN/m	Ok if within 5%
1.00	1.77	200	13.5	ok	8.1 kN/m	
1.50	2.57	225	20.3	ok	17.4 kN/m	

Timber Rail Design

150 x 50 H4 rails over multiple spans

Timber rail properties

φ = Strength reduction factor	0.8	
k1 = Load duration factor	0.6	
k4 = Load sharing factor	1	(assume 1.0 for conservative analysis)
fb = Bending strength (MPa)	14 MPa	VSG8 or Grade 8

Rail Size width (mm) 50 mm Single rail
depth (mm) 150 mm

∅M (kN/m) per rail = 2.8 kN/m

Trial depth (m) = 1.50 C (kPa) = 12.9 M* (kN/m) = 1.5 M* <= ∅M ∅M (kN/m) = 2.8 *Ok depth per single rail layer*

NZS3603 s.2.1.3, dry
continuous over multiple spans
M* = G * L² / 10

Pole Embedment Design

Drained (cohesion less / long term), Broms; short free head critical

Foundation Load Factor	1.5 AS/NZS 1170.0 2002 s.4.2.3(f)(ii)
s = Spacing factor (0.25 * $\frac{3}{D}$)	
D = Foundation hole dia (mm)	
φ Strength reduction factor	0.6

NZBC VM4 / SESOC Vol 10 No 2 Dec 1997


4.3.4 a) i) / 7.1(a) 16

4.3.4 a) i) / 7.1(a) 17


H (m) =	D (mm) =	Trial E (m) =	s =	f (m) =	Short	∅*s*Hu (kN) =	∅*s*Hu >= P*	P* (kN) =	g _c (m) =
0.50	350	0.9	0.86	0.21	5.5	2.8	ok	2.4	0.47
1.00	350	1.5	0.86	0.40	14.9	7.7	ok	7.0	0.77
1.50	400	2.1	0.75	0.57	33.3	15.0	ok	13.6	1.07

TCC - Approved Building Consent Document - BC182234 - Pg 331 of 387 - 14/12/2018 - mkim

ICC - Approved Building Consent Document - BC182234 - Pg 332 of 387 - 14/12/2018 - mkim



ORIGINAL SITE CONTOUR PLAN



2007-2012 EARTHWORKS CONTOUR PLAN

NOTES:
 1. Contour data of original pre-earthworks landform from Harrison Grierson Consultants Ltd, May 2007.
 2. Contours shown at 1.0m intervals to Moturiki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

NOTES:
 1. Cut/Fill contours show difference between 2007 and March 2012 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.


LEGEND

— EXTENT OF STAGES IN THIS GCR

— CUT CONTOURS

--- FILL CONTOURS

rev	description	drawn	approved	date



drawn	DBC
approved	RBT
date	17-2-2017
scale	1:750
original size	A3


coffey
A TETRA TECH COMPANY

client: **The Lakes (2012) Ltd**

project: **The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report**

title: **Original Contour & 2007-2012 Earthworks Plan**

project no: **13086AP-AK** figure no: **4** rev: **-**



2012 CONTOUR PLAN



2013-2015 EARTHWORKS CONTOUR PLAN

NOTES:
 1. Contour data of 2012 landform from Harrison Grierson Consultants Ltd.
 2. Contours shown at 1.0m intervals to Moturiki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

NOTES:
 1. Cut/Fill contours show difference between 2012 and March 2016 surveys. Provided by Harrison Grierson Consultants Ltd. Contours are at 1m intervals.
 2. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.

LEGEND

— EXTENT OF STAGES IN THIS GCR


— CUT CONTOURS

--- FILL CONTOURS

⊕ B-01 2014-2015 NDM TEST LOCATION (PASSED)

⊖ B-01 2014-2015 NDM TEST LOCATION (FAILED)

rev	description	drawn	approved	date



drawn	DBC
approved	RBT
date	17-2-2017
scale	1:750
original size	A3

coffey
A TETRA TECH COMPANY


client: **The Lakes (2012) Ltd**

project: **The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report**

title: **2012 Contour & 2013-2015 Earthworks Plan**

project no: **13086AP-AK** figure no: **5** rev: **-**

TCC - Approved Building Consent Document - BC182234 - Pg 333 of 387 - 14/12/2018 - mkim



NOTES:
 1. Contour data of March 2016 landform from Harrison Grierson Consultants Ltd.
 2. Contours shown at 1.0m intervals to Motuariki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.
 4. Hand auger boreholes are numbered according to the relevant lot number.

NOTES:
 1. Contour data of March 2016 landform from Harrison Grierson Consultants Ltd.
 2. Contours shown at 1.0m intervals to Motuariki Datum.
 3. Lot layout and numbering from Harrison Grierson Consultants Ltd, November 2016.
 4. Hand auger boreholes are numbered according to the relevant lot number.

LEGEND

- EXTENT OF STAGES IN THIS GCR
- CUT CONTOURS
- FILL CONTOURS
- SETTLEMENT MONITORING POINTS
- EXTENT OF 2m TOPSOIL PRELOAD
- BUILDING RESTRICTION LINE (BRL)
- HAND AUGER BOREHOLE LOCATIONS

rev	description	drawn	approved	date	drawn	approved	date	client:	The Lakes (2012) Ltd
					DBC	RBT	17-2-2017	project:	The Lakes - Lots 236 to 239 of Stage 3D Geotechnical Completion Report
					scale:	1:750		title:	Settlement Monitoring & 2016 Contour Plan
					original size:	A3		project no.:	13086AP-AK
								figure no.:	6

COFFEY A TERRATECH COMPANY
 Engineering Log - Hand Auger
 Client: The Lakes 2012 LTD
 Project: The Lakes Stage 3 GCR
 Location: Centre of Lot 237
 Principal: [Redacted]
 Date completed: 16 Mar 2016
 Logged by: ODS
 Checked by: RBT

method	support	sample & field tests	classification symbol & soil description	consistency / relative density
AS hand auger	M casing	B bulk disturbed sample	VS very soft	VS very soft
HA hand auger	N nil	E disturbed sample	SI soft	SI soft
HA hand auger	N nil	U# undisturbed sample from diameter	H hard	H hard
HA hand auger	N nil	HP hand penetrometer (KPa)	Fb friable	Fb friable
HA hand auger	N nil	N standard penetration test (SPT)	VL very loose	VL very loose
HA hand auger	N nil	NC vane shear; peak/undrained (kPa)	MD medium dense	MD medium dense
HA hand auger	N nil	R releasal	D dense	D dense
HA hand auger	N nil	HB hammer bounding	VD very dense	VD very dense

SPECIFICATION FOR TIMBER RETAINING WALLS:

EARTHWORKS

Excavation is to be done as close to the time constructing the retaining wall as possible. Any subsidence and damage that may result is the responsibility of the contractor.

If batters need to be exposed, temporary propping may need to be considered. Plastic covers over exposed ground will minimise surface washout during rain.

Extra care should be taken with excavations greater than 1.8m in height or closer than 1.2m to a boundary. If necessary, the excavations should be staged to reduce the length of unsupported ground.

The excavations for posts shall be made by mechanical auger. The engineer shall inspect the holes prior to concrete encasement.

TIMBER

Poles shall comply with NZS 3605 *Timber piles and poles for use in building*. The poles shall be tanalised to at least 16 kg/m³ ie H5 or better.

Poles are described by their small end diameter (SED) with an average taper of 8mm per metre length. Poles shall be identified with their hazard class stamp on the butt end. Normally poles are placed SED upwards when concrete encased and SED downwards when driven.

Poles shall be handled carefully. Any damaged poles may be rejected.

Any rebates or bored holes shall be treated with painted tanalised, ensele, pentachlorophenol or tanalith are approved. Any such areas shall not be placed in ground contact.

Timber rails shall be rough sawn Grade 8 or VSG8, tanalised to 12 kg/m³ ie H4 or better. They shall span over at least three poles, and joints shall be staggered.

Rails shall be nailed to the rear of the poles with 100mm by 4mm galvanised flat head nails.

The wall may be constructed vertically, or with a backwards rake of up to 1 in 10.

For walls in excess of 1.8m in height, visible outward deflections may occur after or during backfilling. A minimum back slope of 50mm over the out of ground height is recommended for walls between 1.8m and 2.4m in height, and 100mm for walls between 2.4m and 3.3m.

CONCRETE

Concrete for pole encasement shall be ordinary grade concrete with a minimum 28 day strength of 17.5MPa.

Site mixed concrete shall consist of a 6:1 ratio of builders mix to cement. The minimum amount of water shall be added to allow placement.

Concrete encasement shall be well vibrated or rodded to ensure the poles are fully encased.

The poles are to be braced prior to placing the concrete, and for at least 48 hours after concrete placement.

BACKFILLING

If shown on drawings a 100mm Novaflow drain shall be placed at the base of the rear of the wall, its invert at least 100mm below ground level at the front of the wall. Otherwise gaps or weep holes will be required to let water seep through the wall.

The pipe shall have a minimum fall of 1 in 100, and shall outlet where possible into a sealed stormwater system or suitable outlet point. The pipe shall be encased all round with no fines drainage metal, which is to be fully wrapped in BIDIM A29 or equivalent filter cloth where indicated.

The retaining wall is to be backfilled and moderately compacted.

Selected granular material free of clay is to be used (eg roading aggregate, sand, drainage metal). Care must be taken to not over compact and deflect the wall. If the ground immediately above the wall is not to be paved, the top 200mm shall consist of 100mm topsoil on 100mm of clay.

For walls retaining fill material, drainage blankets are permissible against the wall. Drainage material or sand is still required in the base 1 metre of wall. Backfill above this may be free draining silt or sand, but not clay. This material shall be lightly compacted only. Machine compaction of backfill shall be kept outside the 45 degree line from the base of the wall.

OTHER

The building code requires a safety fence when the vertical fall height exceeds 1 metre. It is the owner's responsibility to ensure such a fence is constructed, or alternatively to ensure that pedestrian access is prevented to above the wall (in cases where that is the practical option).

Retaining wall construction including drainage backfill shall be entirely with the subject property.

11 December 2018

Ref: 062/18

19 Willow St, PO Box 1029,
Tauranga, 3110

Simon Fitzpatrick
Simon.fitzpatrick@tauranga.govt.nz

RE: 16 & 18 OKATAINA STREET, TAURANGA

As requested, we have undertaken a review of the retaining walls constructed on 16 and 18 Okataina Street. These walls were constructed as part of the subdivision of 16 Okataina Street into 2 separate lots – lot 1 is 18 Okataina Street, on the north side of the site, and lot 2 is 16 Okataina Street, on the south side of the site.

During the course of the subdivision, 3 retaining walls were constructed across the lots;

- Bottom wall on the south side of 16 Okataina Street. This wall retains up to 1.5m.
- Middle wall on the south side of lot 1, between lots 1 and 2. This wall retains up to 1.1m
- Upper wall, on the north side of lot 1. This wall retains up to 1.3m and supports the neighbours property (11 Okataina Street).

Building consent applications have been submitted for dwellings on both of the above properties and the council had asked for details of these walls. The wall design that has been submitted to the council appears to be a design by The Engineer Ltd, dated 27/03/2018. This is a design for timber pole walls up to 1.5m high supporting a 5kPa surcharge. Also submitted is a PS4 from The Engineer Ltd, dated 5 June 2018, along with some site notes, indicating that the pole wall foundations were inspected on the 9/5/2018.

The Tauranga City Council are not accepting Producer Statements from Bruce Cameron (The Engineer Ltd) and we have been asked to review the designs. Our check on the design of the wall, indicates that the wall is adequate to support the retained height of soil, as well as a 5.0kPa surcharge.

16 OKATAINA STREET (LOT 2)

1. The retaining wall (bottom) is along the south boundary and retains up to 1.5m.
2. The retaining wall heights (and consequently the fill depths) exceeds the limits set in the geotechnical report (Coffey geotechnical report for The Lakes Stages 3G and 3H and Lots 239-239 (Stage 3D), section 8.2.3). As the height is over 1.0m, a TCC Category 1 or 2 geo-professional was required to approve this.
3. Some of the pole diameters do not meet the design – for walls over 1.0m high, the SED should be 225mm whereas a significant number of the poles are 200-210 SED. However, our design check indicates that the “as-built” size is adequate.
4. Fill has been placed over the Building Restriction Line along the east side of the property, which contravenes the Coffey geotechnical report for The Lakes Stages 3G and 3H and Lots 239-239 (Stage 3D). Section 8.3.2 does not allow any filling over the BRL.

5. The building consent application for lot 2 (16 Okataina Street), shows that 2 corners of the proposed dwelling is approx. 0.9m off the bottom retaining wall. In our opinion, this is sufficient separation to assume that the dwelling does not surcharge the retaining wall and there are no other obvious significant potential surcharges on this wall. Therefore this wall can be deemed to be exempt building works under section 20 of schedule 1 on the NZ Building Act.
6. We have not verified the hole diameters or depths. Because this wall is not surcharged, the footings have been inspected by an engineer and the wall did not require a building consent, we believe, on reasonable grounds, that this wall is adequate.
7. There is currently up to 700mm of pumice sand fill in front of this bottom retaining wall, between the wall and the boundary fence. This will need to be removed as it appears that the fence may be retaining this material.

18 OKATAINA STREET (LOT 1)

There are 2 walls on this lot ; the middle wall, between lots 1 and 2 that retains up to 1.1m and the upper wall which retains up to 1.3m.

Middle Wall

1. Some of the middle wall heights exceed the 1.0m noted in section 8.2.3 of the geotech report. However, the height difference is minimal and. At least some if not all, of the ground has been cut, so the fill is less than 1.0m, negating the reason for the height restriction.
2. The pole diameters meet the requirements of the design submitted.
3. The building consent application for lot 1 (18 Okataina Street), shows that the proposed dwelling is approx. 0.8m off the middle retaining wall. As long as the proposed dwelling does not surcharge this wall, the wall can be deemed to be exempt building works under section 20 of schedule 1 on the NZ Building Act. With a minimum of 0.8m separation, it is our opinion that the dwelling does not surcharge the retaining wall.
4. This wall does extend over the Building Restriction Line, but the ground has been cut, and not filled, and therefore the requirement of 8.3.2 has been negated.
5. We have not verified the hole diameters or depths. Because this wall is not surcharged, the footings have been inspected by an engineer and the wall did not require a building consent, we believe, on reasonable grounds, that this wall is adequate.

Upper Wall

1. This wall is up to 1.3m high and retains the neighbours property (11 Okataina Street). The accessway onto this lot directs future traffic to the ground behind this wall and it is probable that the ground behind the wall will form part of the driveway to the future dwelling. Because this wall supports a neighbours property and a potential driveway surcharge, the wall should have had a building consent.
2. The pole diameters do not meet the design – for walls over 1.0m high, the SED should be 225mm whereas the poles are 200 SED.
3. This wall does extend over the Building Restriction Line, but the ground has been cut, not filled and therefore the requirement of 8.3.2 has been negated.

4. We have not verified the hole diameters or depths. However, the designBecause this wall is not surcharged, the footings have been inspected by an engineer and the wall did not require a building consent, we believe, on reasonable grounds, that this wall is adequate.

SUMMARY

- There are some issues of non-compliance with the original geotechnical report for the bottom wall on 16 Okataina Street (wall height and fill over the BRL).
- From a building consent perspective, the bottom wall and the middle wall did not require building consents as they fall within the scope of Schedule 1 of the NZ Building Act, as long as they are not surcharged by the dwellings.
- Notwithstanding the requirement for a building consent, the walls need to comply NZBC and it appears, on reasonable grounds, that the bottom and middle walls do comply, although we have not been able to verify the pole footing diameters or the pole embedments.
- The proposed dwellings should not surcharge these walls. This can be achieved by either distance from the wall or deeper foundations.
- The upper wall (on 18 Okataina Street) should have had a building consent because it supports a neighbours property and the wall will probably be subject to a surcharge (from vehicles). The design of the wall is adequate for a 5.0kPa surcharge but we have not been able to verify the pole footing diameters or the pole embedments.

Yours faithfully,

G.B. Cox

Chartered Professional Engineer
BE(Civil), CPEng, CMEngNZ
Director – CHS Engineers Ltd.



96 Cameron Road
Tauranga
3110 New Zealand

t: +64 7 571 6081
f: +64 7 571 6085
coffey.com

9 February 2019

Our ref: 773-TRGGE226846

Venture Developments Limited
Unit 1, 16 Ashley Place
Papamoa Beach, Papamoa 3118

Attention: Jarod Thorpe

**Report of Geotechnical Plan Review
Proposed Residence at 16 Okataina, The Lakes, Tauriko, Tauranga**

1. Introduction

It is proposed to construct a single-storey residence at the property located at 16 Okataina Street in The Lakes subdivision, Tauriko and legally described as Lot 2 DP 514907. As requested, Coffey Services (NZ) Limited (Coffey) has conducted a geotechnical review of residential design plans and supporting documentation for the proposed development.

This work has been completed in accordance with the short-form agreement¹ signed on 4 February 2019. This report is intended to be submitted in support of a Building Consent application with Tauranga City Council (TCC) and to address issues raised by TCC in relation to earthworks undertaken prior to building consent application.

2. Background Information

In conducting this geotechnical plan review, information from the following sources was reviewed:

- Development drawings by Huis Design Limited (Huis), dated 28/9/2018, Reference WD-A, Job 18062;
- Geotechnical Completion Report, The Lakes – Stages 3G, 3H & Lots 236-239 (Stage D), by Coffey Services (NZ) Limited, dated 17 February 2017, Reference GENZTAUC13086AP-AK;
- *Proposed Subdivision of Lot 237 DP 507200, 16 Okataina Street*, by S&L Consultants Limited (S&L), Revision 2, dated 06/17, Drawing No. 21809-RC1;
- *Asbuilt Plan, 16 Okataina Street, The Lakes*, by S&L Consultants Limited, Revision 1, dated 06/18, Drawing No. 21809-AB01;
- Asbuilt wall heights by S&L Consultants Limited, unnamed, undated.

¹ "Short Form Agreement for Consultant Engagement", ref: P226846, signed 4 February 2019.

- *Producer Statement – PS4 – Construction Review, Timber pole retaining wall construction and investigation and certification, 16 Okataina Street, by The Engineer Limited, dated 5 June 2018;*
- *Producer Statement – PS4 – Construction Review, Building foundation ground preparation construction investigation and certification, 16 Okataina Street, by The Engineer Limited, dated 5 June 2018;*
- Email correspondence from TCC, by Simon Fitzpatrick, dated 10 January 2019;
-

2.1. Proposed Development

The client has applied for building consent with Tauranga City Council based on the development plans by Huis. The plans depict a single-storey residence supported at-grade by a Firth rib-raft foundation. Stormwater runoff from roof and hardstand is shown to be directed to an existing stormwater reticulation connection at the southwest corner of the property. The plans show the proposed residence to be located at least 1m from an existing retaining wall (See Section 2.3) along the southern property boundary.

2.2. Subdivision Earthworks

The subject property has undergone extensive earthworks as part of the development of Stage 3D of The Lakes subdivision. The property was formed when previous Lot 237 was further subdivided into two parcels. The property is located on the southern half of previous Lot 237. See attached subdivision plan by S&L.

Earth works on Lot 237 comprised up to 14m of engineered filling in what was referred to as the Southern Gully. See photo 1 below. Earthworks were largely complete by 2015 when the Geotechnical Completion Report was issued for Stage 3D; however, on-going monitoring indicated that the Southern Gully fill was continuing to undergo settlement and Lot 237 was excluded from the GCR. At this time a 2m high surcharge was placed across several lots, including Lot 237, to hasten the settlement process. See photo 2 below.

By 2017, monitoring indicated that settlement of the Southern Gully fill was within tolerable limits, and a GCR was issued covering Lot 237 (dated 17/2/2017). In the GCR, it was recommended that additional filling during lot development be restricted to a maximum depth of 1m to reduce possible future settlement. A building restriction line (BRL) was placed parallel to the eastern property boundary to prevent building or fill surcharges from destabilising the slope below which had been engineered with a 2.5H:1V batter. No BRL was placed along the southern boundary as this slope had been engineered with a 3H:1V batter.

Photo 1: Aerial photo 18 February 2015



Photo 2: Aerial photo 6 March 2016



2.3. Unconsented Earthworks

Sometime after completion of subdivision earthworks (after February 2017 based on aerial photos), additional earthworks were carried out on the subject property on behalf of a previous owner. The additional earthworks comprised construction of a timber retaining wall and creation of a level building platform with cut and fill. See photos 3 and 4 below. A building consent was not obtained; however, these earthworks were documented by The Engineer Limited in two Producer Statements. See attached.

Photo 3: Aerial photo 5 February 2017



Photo 4: Aerial photo 9 April 2018



According to the Producer Statements, the site was stripped, and fill placed such that the site could be considered "good ground" in terms of NZS3604 3.1.3. A comparison of the spot elevations shown on the subdivision plan by S&L to the development plans by Huis, indicates that approximately 0.5m of material was cut from the northern portion of the site and up to about 1m of fill was placed behind the retaining wall at the southern portion of the site. The retaining wall and fill extend beyond the BRL at the eastern property boundary, with fill and wall heights decreasing from a maximum of approximately 0.6m at the BRL down to 0m within a few metres of the property boundary.

2.4. Building Consent Application

Based on unconsented works taking place on the property, TCC has issued a hold on the building consent as allowed for under Section 37 of the Resource Management Act 1991 (as amended) pending a request for further information. Specifically, in the provided email correspondence dated 10 January, TCC has requested the following in relation to the proposed development:

1. *Have the fill over the BRL assessed by a Cat 1 Geo-Professional. Carry out any remedial works that this may require.*
2. *Have the areas of fill exceeding 1.0m, assessed by a Cat 1 Geo-Professional.*
3. *Have the retaining wall assessed by a Cat 1 Geo-Professional.*
4. *Ensure the dwelling is no closer to the top of the wall than the walls height at that location.*
5. *Remove the up to 0.7m of pumice sand fill from against the noise wall.*

3. Site Observations

Coffey visited the site on 23 January to meet the client and observe site conditions. During the site visit, the constructed building platform, slopes to the south and east, and retaining walls along the southern and northern property boundaries were observed. See Photos 5 and 6 below. Along the eastern property boundary, the landform appears to be relatively unaltered. Although there is evidence of ground disturbance, it does not appear that the ground surface has been elevated with fill within 1 to 2 metres of the eastern property boundary. See Photos 7 and 8.

Photo 5: Site facing south



Photo 6: Site facing west



Photo 7: Eastern slope facing south



Photo 8: BRL and eastern slope facing south



During the site visit, fill material was observed between the southern retaining wall and the privacy fence. This material had evidently collected as a result of erosion of fill from the building platform. The client had excavated a small pit which indicated the depth of this material was on the order of 0.5m. See photos 9 and 10 below. The fill material does not appear to have left the property. See photos 11 and 12. The client advised that this material would be removed from between the retaining wall and fence.

Photo 9:



Photo 10:



Photo 11: Southern slope facing southwest



Photo 12: Site facing west-southwest



4. Geotechnical Review

For this geotechnical review, Coffey was only provided with PS4 Construction Review documentation. No design documents, calculations or Design Producer Statements (PS1) have been sighted by Coffey for work carried out after completion of subdivision earthworks.

4.1. Fill Depth

A review of the available PS4 producer statements for the wall and fill, survey information from S&L, and Coffey's own observations indicate that the unconsented wall height and post-subdivision fill depths appear not to exceed 1m. Based on the GCR for the subdivision which allow for up to 1m of fill and the preload that had been place on the site prior to issuance of the GCR, Coffey considers that the depth of fill placed meets the GCR depth requirement. The quality of this fill is unknown and undocumented and Coffey does not provide comment on the quality of the fill or compactive effort. The fill depth and quality should be confirmed during the building construction phase.

4.2. BRL Encroachment

Based on review of available information and Coffey's own site observations, it appears that minor fill has been placed across the BRL, increasing from 0m to 0.6m at the BRL and only in the south eastern corner of the property. A review of previous stability analyses indicates that this amount of fill would not significantly increase the risk of instability along the eastern slope.

4.3. Existing Retaining wall

4.3.1. Foundation Loads

It is unknown if the retaining wall allowed for a surcharge load in its design. Although maintaining a setback distance from the top of the wall (measured from the retained side of the top plank) equal to the height of the wall should be sufficient so that the wall is mostly out of the 45-degree zone of influence of the building foundation loads, wall stability is still an integral part of the support of the building. Although the building may not increase the load on the wall or otherwise decrease the stability of the wall, excessive movement of the wall or wall failure by other means could have a destabilizing effect on the building foundations.

Were the wall to be absent, the granular subgrade soils would typically be battered at a 3H:1V slope to maintain stability with a setback distance imposed from the top of the slope for foundations. In other words, for the stability of a foundation to be independent of the stability of the retaining wall below, the setback would need to be greater than the height of the wall.

4.3.2. Wall Drainage

The wall does not appear to be designed to withstand hydrostatic pressure as evidenced by a design note stating that the water level depth is assumed to be greater than the embedment depth. Therefore, the design likely relies on good drainage behind the wall to alleviate hydrostatic pressure.

Although filter fabric was observed during Coffey's site visit attached to the back of the top plank of the wall, the plans attached to the PS4 do not show filter fabric. Therefore, it is assumed that the granular backfill material is not encased within filter fabric. It is Coffey's opinion that granular backfill without filter fabric may lose its free-draining capacity over time as fine particles migrate into the material and clog pore spaces. This may lead to a progressive wall failure due to build-up of hydrostatic pressure during times of rainfall and perched water table conditions.

Additionally, it appears to be assumed that any water that enters the granular backfill would be allowed to escape through the face of the wall between planks. This may not be a reliable assumption if spaces close due to swelling when planks become wet.

Therefore, it is recommended that remedial measures be undertaken to ensure adequate drainage behind the wall. See Section 5.1 for remedial recommendations.

5. Recommendations

5.1. Existing Retaining Wall

A failure of the southern wall may result in a loss of support to foundation subgrade soils. Although the building foundations are located a sufficient distance to minimise loading on the wall, a wall failure could still adversely impact the building foundations. Therefore, Coffey recommends that edge foundations within 2m of the retaining wall and parallel to the retaining wall be deepened to a minimum 400mm below finished grade.

Coffey also recommends improving the robustness of the wall drainage to decrease the risk of wall failure due to hydrostatic pressure. Several suitable drainage options are presented below:

- Install a 110mm perforated draincoil ('Novaflo' or similar) within bottom 1/3 of base of the wall surrounded by free draining material wrapped in Strength Class B geotextile below 300mm (min.) topsoil cap. Draincoil is to be directed to an appropriate stormwater outlet. Drainage material is to be 300mm thick as measured from back of wall; or,
- Install drainage mat ('Cirtex Secudrain' or similar) behind the wall beginning beneath 300mm topsoil cap, extending to within bottom 1/3 of base of the wall and wrapped around 110mm draincoil ('Novaflo' or similar). Draincoil is to be directed to an appropriate stormwater outlet; or,

Install drainage mat ('Cirtex Secudrain' or similar) behind the wall beginning beneath 300mm topsoil cap, extending to the base of the wall, and tucked under the lowest retaining wall rail to allow seepage out of the face of the wall.

5.2. Existing Filling

Although the fill depths, as reported, appear to be acceptable in terms of site stability and in accordance with the recommendations in the GCR, it is recommended that confirmatory testing be carried out during construction. In particular, it is recommended that a minimum of two boreholes are carried out to depths of 2m to confirm that the site had been adequately stripped prior to fill placement. Additionally, testing of the fill should be conducted such that each fill lift is tested and show adequate material quality, strength and relative compaction test results.

6. Conclusion

An assessment of the impact of the quantity of filling over the BRL has been carried out. Based on Coffey's site observations, assessment and the provided documentation, it appears that this filling is unlikely to significantly decrease the stability of the eastern slope. Based on Coffey's observations of the site in its current state and the previous surcharging of the site, it is unlikely that the approximately 1m of fill placed in the southern portion of the property would significantly decrease the stability of the site or cause excessive settlement.

Based on a qualitative assessment of the features of the retaining wall that are easily visible and the provided documentation, it is Coffey's opinion that remedial works are required. It is recommended that building foundations near the retaining wall be deepened and that additional drainage be installed behind the wall as described in Section 5.1 during construction. It is also recommended that confirmatory testing of fill depth and quality be carried out during construction. It is Coffey's understanding that the fill between the retaining wall and noise wall along the southern boundary will be removed.

The conclusions and recommendations presented in this report are based on previous assessments carried out by Coffey for Stage 3D of The Lakes subdivision and Coffey's recent observations, assessments and review of the information provided. Based upon this review and upon satisfactory completion of the remedial works and confirmatory testing recommended in this report, it is Coffey's opinion that the unconsented earthworks carried out to date do not increase the risk of natural hazards of a geotechnical nature in terms of Section 106 of the Resource Management Act 1991 (as amended) or Section 71 of the Building Act 2004.

7. Limitations

While this letter presents a summary of the geotechnical conditions for this area it does not provide a complete discussion of geotechnical issues affecting the Lakes Stage 3D area or previous earthworks undertaken on the site. It is therefore recommended that designers working on the new lots are also familiar with the contents of the original Stage 3D GCR.

This letter has been prepared solely for the use of our client, their professional advisers and the relevant territorial authorities in relation to the specific project described herein. No liability is accepted in respect of its use for any other purpose or by any other person or entity. All future owners of this property should seek professional geotechnical advice to satisfy themselves as to its on-going suitability for their intended use.

Please do not hesitate to contact the undersigned if you require any further information.

Regards,



Lowry Shuler
Senior Geotechnical Engineer
CPEng No. 1029886
TCC Category 2 Geotechnical Engineer





David Sullivan
Principal Geotechnical Engineer
CPEng No. 1025183
TCC Category 1 Geotechnical Engineer

Attachments:


Development drawings by Huis Design Limited
Geotechnical Completion Report, The Lakes – Stages 3G, 3H & Lots 236-239 (Stage D)
Proposed Subdivision of Lot 237 DP 507200, 16 Okataina Street, by S&L
Asbuilt Plan, 16 Okataina Street, The Lakes, by S&L
Asbuilt wall heights by S&L
Producer Statement – PS4 – Construction Review, Timber pole retaining wall
Producer Statement – PS4 – Construction Review, Building foundation ground preparation
Email correspondence from TCC

LOT 2 DP 514907	
WIND ZONE:	HIGH
EARTHQUAKE ZONE:	1
CORROSION ZONE:	ZONE C
DISTANCE TO ESTUARY OR OCEAN:	5040m
SNOW LOADING:	UP TO 1kPa
BUILDING FOOTPRINT:	16761m ²
SITE COVERAGE:	40.78%



EASEMENT B
RIGHT TO DRAIN WATER & SEWAGE,
GAS & WATER TELECOMMUNICATION
& COMPUTER MEDIA

NOTE
PIPE LOCATIONS TO BE CONFIRMED.
PIPE LOCATIONS TO BE CONFIRMED
TO ASSESS PROXIMITY TO FOUNDATION



ROOF 1
A: 196.59 m²

PIPE SIZES AND GRADIENTS AS/NZS3500

FIXTURES DISCHARGING TO DISCHARGE GULLIES

PIPE SIZE	GRADE
DN 40	1:40
DN 40	1:40
DN 50	1:40

FIXTURES DISCHARGING TO DISCHARGE UNVENTED BRANCH DRAIN

PIPE SIZE	GRADE
DN 40*	1:40
DN 40*	1:40
DN 40*	1:40
DN 50	1:40
DN 50*	1:40
DN 100	1:60

VENT SIZES

PIPE SIZE	GRADE
DN 50	N/A

SANITARY DRAINAGE

PIPE SIZE	GRADE
DN 100	1:60
DN 100	1:60
DN 65	1:40

STORMWATER DRAINAGE

PIPE SIZE	GRADE
100 Ø	1:20
80 Ø	N/A

* = DISCHARGE PIPE DISCHARGES TO UNVENTED DN65 BRANCH DRAIN AT FLOOR LEVEL

SANITARY SEWER PLUMBING AND DRAINAGE TO AS/NZS 3500.2. STORMWATER DRAINAGE TO NZBC E1/AS1. PIPE SIZES, GRADES, AND LAYOUT, TO BE CONFIRMED BY A REGISTERED PLUMBER/DRAIN LAYER.

GUTTER CAPACITY

Calculation to NZ metal roof and wall cladding code of practice, Roof drainage 8 V.2.2 Page 258


Roof pitch: 10°-25° (Factor 1.1)
Rainfall intensity: 126mm/hr (Factor 1.26)
Roof area: 46,75m²

Factorised Catchment Area
46,75m² x 1.1 = 51,425m²
Calculation: 51,425 x 1,26 x 1,1 = 71,275m²

External Gutter Area = 100mm² x 71,275m² = 7128mm²
Cross-sectional Gutter area required = 7128mm²
Use SKI Customline Gutter with Cross-sectional area of 7163mm²

NOTE 1

COLD WATER TO DISCHARGE TO MAIN LINE VIA 40mm PVC PIPE
PRESSURE RELIEF VALVE DRAIN TO DISCHARGE TO UNPAVED GROUND VIA 20mm COPPER PIPE




ELEVATION 3.

SG SAFETY GLAZING IN ACCORDANCE WITH NZS 4223.3:2016
FOR ALL WINDOWS AND DOORS
PART 3: HUMAN IMPACT SAFETY REQUIREMENTS



ELEVATION 4.



FOUNDATION NOTES

PLAN TO BE READ IN CONJUNCTION WITH FIRTH RIBRAFT TECHNICAL MANUAL FOUNDATION DESIGNED BASED ON BUILDING FOUNDATION GROUND INVESTIGATION & CERTIFICATION - PS4 THE ENGINEER LIMITED DATED: 5 JUNE 2018

ALSO REFER TO THE GEOTECHNICAL COMPLETION REPORT THE LAKES - STAGE 3G, 3H & LOT 236-239 (STAGE D) DATED: 17 FEBRUARY 2017 REF: GENZALUCI3086AP-AK LOT 2 WAS ORIGINALLY APART OF LOT 237 BEFORE IT WAS SUBDIVIDED

IF BUILDER FINDS THIS INCORRECT WHILE EXCAVATING HE IS TO MAKE CONTACT WITH THE DESIGN LBP IMMEDIATELY.

ENTIRE FLOOR SLAB SHALL BE 20mPa CONCRETE WITH REINFORCED WITH REINFORCING SEISMIC MESH S662 500E 2.0 X 4.5 CVR 75SGM SUPPORTED ON 40MM MESH CHAIRS SITTING ON FIRTH RIBRAFT TECHNICAL MANUAL

LOCATION OF SERVICES IN RIBRAFT FOUNDATION TO BE LOCATED AS PER FIGURE 12 & 13 OF THE FIRTH RIBRAFT TECHNICAL JAN 2012

PERIMETER
A: 160,95 m²

NOTE 1
85MM THICK 20mPa FIRTH RIBRAFT MIX CONCRETE SLAB REINFORCED WITH REINFORCING SEISMIC MESH S662 500E 2.0 X 4.5 CVR 75SGM OR EQUIVALENT ON 2/40MM CHAIRS PER POD

NOTE 2
1100mm SO. POLYSTYRENE PODS 220mm THICK, REFER TO RIBRAFT MANUAL FOR LAYOUT

NOTE 3
LOAD BEARING WALLS, REFER TO FLOOR PLAN FOR POSITION, INTERNAL LOAD BEARING RIBRAFT RIB UNDER

NOTE 4
50mm RECESSED SLAB FOR TILED SHOWER

NOTE 5

90x65mm DEEP REBATE TO ENTRY DOOR & 2 SLIDERS JOINERY MANUFACTURE TO CONFIRM SIZE WITH BUILDER




The Lakes (2012) Ltd

The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D)

Geotechnical Completion Report

17 February 2017



Experience
comes to life
when it is
powered by
expertise

This page has been left intentionally blank

The Lakes - Stages 3G, 3H & Lots 236-239 (Stage D)

Prepared for
The Lakes (2012) Ltd
C/- Harrison Grierson Consultants Ltd
PO Box 13 025
Tauranga 3141
Tauranga

Prepared by
Coffey Services (NZ) Ltd
96 Cameron Road, Tauranga
Tauranga Central 3110 New Zealand
t: +64 7 577 42866081

17 February 2017

Document authorisation

Our ref: GENZTAUC13086AP-AK

For and on behalf of Coffey



David Cullen
Engineering Geologist

Quality information

Revision history

Revision	Description	Date	Author	Reviewer	Signatory
Draft	Draft for review	23 Jan 2017	D Cullen	D Sullivan	D Cullen
Final	Final for issue	17 Feb 2017	D Cullen	D Sullivan	D Cullen

Distribution

Report Status	No. of copies	Format	Distributed to	Date
Final	1	PDF	The Lakes (2012) Ltd	17 Feb 2017
Final	1	PDF	Harrison Grierson Consultants Ltd	17 Feb 2017
Final	2	Hardcopy	Tauranga City Council	17 Feb 2017

Table of contents

1. INTRODUCTION AND SCOPE.....	1
2. DESCRIPTION OF SUBDIVISION.....	1
3. RELATED REPORTS.....	2
3.1. Geotechnical Assessments.....	2
3.2. Earthworks Completion Report.....	2
4. INVESTIGATIONS COMPLETED.....	3
5. OVERVIEW OF GEOLOGICAL CONDITIONS.....	3
6. EARTHWORKS OPERATIONS.....	4
6.1. Plant.....	4
6.2. Construction Programme.....	4
6.2.1. 2007 – 2012.....	4
6.2.2. 2013 – 2014 & 2014 – 2015 Earthworks Seasons.....	4
7. QUALITY CONTROL.....	5
7.1. Site Preparation Observations.....	5
7.2. Fill Control.....	5
7.2.1. Compaction Control Criteria.....	5
7.2.2. Test Results.....	5
8. ENGINEERING EVALUATION AND RECOMMENDATIONS.....	6
8.1. Fill Quality.....	6
8.2. Static Settlement.....	6
8.2.1. Stage 3H.....	6
8.2.2. Lots 236-239 (Stage D).....	6
8.2.3. Fill Development Restrictions.....	7
8.3. Slope Stability.....	7
8.3.1. Lots 413, 458, 460 and 493-503.....	7
8.3.2. Lots 236-239 (Stage 3D).....	7
8.3.3. Slope Development Restrictions.....	7
8.4. Stage 3G Retaining Wall.....	8
8.4.1. Retaining Wall BRL.....	8
8.4.2. Retaining Wall Development Restrictions.....	8
8.5. Stage 3H Stormwater Pipe Line.....	8
8.6. Foundation Design & Bearing Capacity.....	9
8.7. Stormwater Management.....	9
9. CONCLUSION.....	9
10. LIMITATIONS.....	9

Important information about your Coffey Report

Appendices

Appendix A - Figures

Appendix B - Geotechnical Suitability Statement & Geotechnical Data Summary Table

Appendix C - Pre Development Investigation Data

Appendix D - Post Development Investigation Data

Appendix E – Fill Test Summary Tables

Appendix F – Static Settlement Results

Appendix G – Stage 3G Retaining Wall Certification

Appendix H – Stage 3H Stormwater Pipeline Drawings

1. INTRODUCTION AND SCOPE

This Geotechnical Completion Report (GCR) has been prepared by Coffey Services (NZ) Ltd (Coffey) for the Lakes (2012) Limited following completion of earthworks for Stage 3G, Stage 3H (collectively known as 3GH) and Lots 236 to 239 within Stage D of the Lakes Subdivision and in general accordance with the conditions of Council resource consent number RC21332.

This GCR contains the results of site investigations together with as-built plans derived from Harrison Grierson Consultants Ltd (HGCL) topographical data. It describes bulk earthworks completed during the 2007-2008, 2013-2014 and 2014-2015 earthworks seasons.

The extent of earthworks observed by Coffey is shown on the appended plans (Figures 1 to 6, Appendix A). A Statement of Professional Opinion (Form G2) and Summary of Technical Data (Form G3) for the works described herein are also appended.

2. DESCRIPTION OF SUBDIVISION

Stages 3GH and Lots 236 to 239 within Stage D of the Lakes subdivision are located near the intersection of Pyes Pa Road and Takitimu Drive (State Highway SH26) in Pyes Pa, Tauranga. The site location and original ground contours are shown on Figures 1 (Stage 3GH) and 4 (Lots 236 to 239) in Appendix A. Stage 3G, Stage 3H and Lots 236 to 239 consists a total of 80, 11 and 4 lots respectively.

Before earthworks began, the majority of Stage 3G consisted of a flat or gently rolling north-south oriented plateau at approximately RL 55-65m (Moturiki Datum, 1953). During the 2013-2014 earthworks season, filling was placed over the northern portion of Stage 3G. The following 2014-2015 earthworks season, excavation of the elevated plateau was undertaken in the southeast of Stage 3G and additional filling was placed in the north and eastern extent. Combined cut/fill contours of the works completed are shown on Figure 2.

Stage H comprised a sloping terrace on the edge of the plateau before earthworks proceeded, dipping from approximately RL 59m in the western extents to approximately RL 49m in the east. During the 2014 to 2015 earthworks season, filling commenced over much of Stage 3H, with the exception of minor cut in the north-western and south-western extents.

Lots 236 to 239 within Stage 3D originally comprised of steeply sloping ground over much of the lots, dipping in a southeast and western direction where a deeply incised gully extended into the lots. Earthworks commenced in this area with the placement of fill over Lots 237 to 239 during the 2007 to 2008 earthworks season, followed by unsupervised filling thereafter, likely between 2010 and 2012 and discussed later in this report. Cut/fill contours are shown on Figure 4. The 2012 ground surface is shown on Figure 5. Further earthworks were completed during the 2014-2015 work season, with cut/fill contours for the 2014-2015 earthworks also shown on Figure 5.

Construction of a cantilever timber pole retaining wall was completed in 2017 adjacent to the northern perimeter of Stage 3G. Additionally in 2016, a stormwater pipe was thrust beneath the slope to the east of Stage 3H to an outlet structure above the stream in the valley below. The location of the stormwater pipe and indicative location of the retaining wall is shown on Figure 3.

Civil infrastructure for these stages and lots of the subdivision was installed in 2015 and 2016. The finished ground surface is shown on Figures 3 and 6.

3. RELATED REPORTS

The following documents were prepared prior to or during the design and development of Stages 3G, 3H & Lots 236-239 (Stage D):

1. *'Pyes Pa West Urbanisation Development, Tauranga – Geotechnical Assessment Report'*, report prepared by S&L Consultants Ltd (Ref: 16944, dated October 2003).
2. *'Geotechnical Investigation Report for the Lakes Subdivision – Stage 3 (Phase 1) at Pyes Pa, Tauranga'*, report prepared by Coffey (Ref: GENZTAUC13086AF-AA, dated 29 April 2013).
3. *'Geotechnical Investigation Report for the Lakes Subdivision – Stage 3 Zone 2 at Pyes Pa, Tauranga'*, report prepared by Coffey (Ref: GENZTAUC13086AK-AC, dated 7 April 2014).
4. *'The Lakes Subdivision Stage 3 Zone 1 Earthworks Completion Report'*, report prepared by Coffey (Ref: GENZTAUC13086AF-AE, dated 15 August 2014).
5. *'The Lakes Stage 3 - Zone 3, Geotechnical Investigation Report (Addendum 1)'*, report prepared by Coffey (Ref: GENZTAUC13086AQ-AB, dated 10 July 2015).
6. *'Building Restriction Lines above Western Slope and Collector Road, The Lakes Subdivision Stage 3 – Zone 2'*, memo prepared by Coffey (Ref: GENZTAUC13086AQ-AC, dated 25 August 2015).
7. *'Retaining Wall Design Report for Stage 3G The Lakes, The Lakes Subdivision, Tauriko'*, report prepared by Coffey (Ref: GENZTAUC13086AB-AB, dated 16 June 2016).

Key conclusions of the main documents are summarised below.

3.1. Geotechnical Assessments

The original geotechnical assessment for the Lakes subdivision was completed by S&L Consultants Ltd and contained an overview of geotechnical conditions for the entire Lakes project. The report concluded that the site was generally adequate for subdivision and residential development, subject to appropriate design and construction.

Subsequent geotechnical investigation reports by Coffey in April 2013 and April 2014 summarised additional investigations that were completed to specifically assess the Stage 3 area. These investigations generally confirmed the S&L conclusion that the site was adequate for subdivision.

3.2. Earthworks Completion Report

The August 2014 Earthworks Completion Report (ECR) concluded that the bulk earthworks undertaken in 2007-2008 and 2013-2014 were generally completed in accordance with the relevant standards and guidelines including NZS 4431 (Code of Practice for Earth Fill for Residential Development) and the Tauranga City Council Infrastructure Development Code (TCC IDC). The report did however identify several areas that needed to be re-visited in this GCR. These were:

1. Some of the fill materials placed towards the end of the 2013-2014 season did not pass the required Nuclear Density Meter (NDM) tests. The failed tests were attributed to the highly variable source materials being used (silts, sands and clays) which resulted in fills that could not be easily assessed with a NDM. It was therefore decided that the affected fill would be re-tested using hand-auger boreholes with undrained shear strength measurements and/or Dynamic Cone Penetrometer (DCP) testing as appropriate for the individual soils.
2. The ECR also commented on the presence of undocumented filling that was encountered during excavations in 2013 within lots 238 & 239 and elsewhere within the Lakes development. This filling is understood to have been placed between 2010 and 2012, when

works on site were not closely managed by either Grasshopper Farms Ltd or The Lakes (2012) Ltd.

3. Finally, the ECR recommended that the stability of the eastern slope should be reassessed in the GCR and an appropriate Building Restriction Line (BRL) be defined for lots along the crest of this slope.

These issues are addressed in the following sections of this report.

The ECR also referred to the presence of subsurface erosion features ('tomos') found in other stages of the Lakes Subdivision, indicating soils below the plateau may be subject to erosion and scouring. While 'tomos' have not been observed within these subject Stages and Lots, it is possible erosional features may be encountered during construction on these lots.

4. INVESTIGATIONS COMPLETED

Geotechnical investigations have been undertaken on this and adjacent sites during each stage of the Lakes subdivision's design and construction. The investigations used for this report are listed below. Logs of each investigation are included in Appendix C.

- Three test pits excavated in 2012 within or near Stage 3G to maximum depths of up to 5m to assess shallow ground conditions before the 2013-2014 work season (Coffey, TP07–TP09 on Figure 1);
- One Cone Penetrometer Test (CPT) to a depth of approximately 13 meters below the existing ground level using a truck mounted rig supplied by Geotech Drilling Limited (Coffey, CPT314 on Figure 1);
- One machine borehole drilled to a depth of approximately 20.0m. Standard Penetration Tests (SPT) were carried out at 1.5m intervals (Coffey, MH301 on Figure 1);
- Two flight-auger machine boreholes drilled to a maximum depth of 20.0m within Stage 3H. SPT tests were conducted at specific depths within these boreholes to provide strength estimates and relatively undisturbed samples of key lithologies encountered (Coffey, CFA04 & CFA05 on Figure 1).

On completion of the bulk earthworks in 2016, Coffey drilled a total of 50 hand-auger boreholes to target depths of 2m or 2.5m (and in some cases, up to 5m depth) on approximately every second lot to confirm finished subgrade conditions. The location of each borehole is shown on Figures 3 & 6. Although labels are not shown on the plan, the boreholes are numbered according to the relevant lot number. For example, the hand auger borehole on Lot 413 in Stage 3G is referred to as HAL413. Logs of these boreholes are included in Appendix D.

5. OVERVIEW OF GEOLOGICAL CONDITIONS

The subject areas of Stage 3G and Lots 236 to 239 within Stage 3D are located on an elevated, gently sloping plateau. Below the topsoil layer, the pre-development soil profile across this plateau comprised of volcanic ashes including the Hamilton Ash and Rotoehu Ash. This ash sequence is common throughout the Tauranga area. At this location the volcanic ashes overlie ancient alluvial deposits of the Matua Sub-Group and weakly cemented pumice sands of the Te Ranga Ignimbrite.

Stage 3H is located on a gently to moderately sloping terrace formed from ancient alluvial deposits of the Matua Subgroup.

Excavations during the 2013-2015 period reduced the thickness of the volcanic ashes across the southeast of the Stage 3G plateau by up to 7m. The subsoils below many of the finished lots therefore

comprise volcanic ash silts but in some areas excavations have penetrated through the ash layers and the finished lots are underlain by variable Matua Sub-Group soils. These include silts, sands and clays which can be highly sensitive to reworking. Areas underlain by fill are discussed in Section 6.2.

6. EARTHWORKS OPERATIONS

6.1. Plant

Earthworks during the 2007-2008 season were completed by Bob Hicks Earthmovers Ltd. The contractor for the 2013-2014 and 2014-2015 seasons was JMC Civil Construction Ltd.

The main items of plant used during each of the bulk earthworks phase comprised Terex motor-scrappers and bulldozer or tractor towed 'scoops', hydraulic excavators, bulldozers, articulated all-terrain dump trucks (ADT's) and sheep's-foot rollers.

6.2. Construction Programme

6.2.1. 2007 – 2012

Under ownership of Grasshopper Farms Ltd, earthworks during this period included excavations of up to 1m depth over Lot 237 (Stage D) as shown on Figure 4. Filling took place over Lots 237 to 239 (Stage D), however as cut & fill contours for this period are not available, fill contours were calculated by HGCL (Harrison Grierson Consultants Ltd) by subtracting the original ground surface (surveyed in 2007) from a survey completed by HGCL in 2012. This resulted in indicated fill depths of up to 11m across the lots.

Excavations in the filling in Lots 237 to 239 encountered soils that consisted of highly sensitive silts and clays with a relatively high moisture content and low undrained shear strength. Based on a series of unlogged test pits within the fill, it was considered that the non-engineered filling could remain in place provided that later fill in these areas was placed appropriately and that static settlements were monitored and reviewed prior to issue of the GCR. This later filling is discussed in more detail below.

No cut or fill took place over Stages 3GH during 2007 to 2012.

6.2.2. 2013 – 2014 & 2014 – 2015 Earthworks Seasons

In 2012 ownership of the Lakes subdivision passed from Grasshopper Farms Ltd to The Lakes (2012) Ltd. During this period the remaining earthworks were completed to form the current ground surface. Earthworks during the 2013-14 and 2014-15 summers included excavations of up to 7m depth on the main plateau of Stage 3G and 1m cuts in the north and south of Stage 3H, as shown on Figure 2.

Excavated material was used for filling up to approximately 2m deep in the northern portion of Stage 3G during both summer periods, and up to 4m deep along the eastern boundary of Stage 3G and over much of Stage 3H during the 2014-15 season.

Further cut and fill was undertaken over Lots 236 to 239 of Stage D. Lot 236 and 237 underwent cut of up to 1m and all of the lots had fill placed to varying depths, with filling of up to 8m deep in places as shown on Figure 5.

7. QUALITY CONTROL

7.1. Site Preparation Observations

During 2013-2014 and 2014-2015, Coffey undertook regular observations of fill areas to ensure topsoil, vegetation or unsuitable materials had been removed before filling.

7.2. Fill Control

As mentioned previously, filling placed over Lots 237 to 239 of Stage 3D during 2007-2012 was not tested or certified by Coffey and no other records or test results have been located.

For Stages 3GH and Lots 236 to 239 of Stage 3D in the 2013-2014 and 2014-2015 seasons, Nuclear Density Meter (NDM), laboratory moisture content and undrained shear strength tests were carried out by Geotechnics & Fulton Hogan on behalf of JMC Limited. The locations of the tests completed are shown on Figure 2 and 5.

In cases where of the above tests recorded low undrained shear strengths, retests were undertaken to assess the ground conditions and fill strength, either as additional NDM tests or subsequent hand-auger boreholes in close proximity to the original test.

7.2.1. Compaction Control Criteria

The compaction control criteria for this project were specified using the 'minimum allowable shear strength and maximum allowable air voids' method as defined below:

- Air voids percentage (defined in NZS 4402:1986 and as measured by NDM) targeting an average value less than 10% over any 10 consecutive tests and maximum single value no greater than 12%.
- Undrained shear strength measured by hand held shear vane calibrated using the NZGS 2001 method. A single undrained shear strength 'test' was defined as the average of four individual shear vane readings at each NDM location. The target test values were an average value greater than 150kPa and minimum single value no less than 140kPa.

The hand-auger boreholes drilled to re-test filling used field shear vane measurements with the same target result as above.

7.2.2. Test Results

Summary tables showing the results of the laboratory fill tests for bulk earthworks at Stages 3G, 3H & Lots 236-239 (Stage D) are included in Appendix E and the locations of the tests are shown on Figures 2 and 5. The majority of tests met or exceeded the compaction control criteria given above. Failed tests are shown in red on the relevant figures.

Three tests during the 2013-2014 season did not meet the required values, with test numbers A-05, A-12, and A-41 being deemed to have failed due to low undrained shear strength readings. The fill surrounding these tests were either reworked or retested with hand-auger boreholes at a later date (passing thereafter), indicating the failed result was either due to an incorrect test value or an isolated pocket of filling.

During the 2014-2005 season, three tests being B-01, B-05 and B-13 initially failed due to low undrained shear strength readings but were retested and subsequently passed. As these tests were superseded by later testing, the tests are not showing as failed results on the site plan.

Two further tests, B-08 and B-09, failed due to low undrained shear strength readings and were retested with hand-auger boreholes at a later date, again with passing results indicating the failed tests were either due to an incorrect test value or an isolated pocket of filling.

8. ENGINEERING EVALUATION AND RECOMMENDATIONS

8.1. Fill Quality

Based on the appended earth fill quality control test data and reliance on the diligence of the bulk earthworks contractor at times when engineering staff were not present on site, results indicate that the compaction control criteria were generally met during the bulk earthworks periods in 2013-2014 and 2014-2015.

8.2. Static Settlement

The majority of the area, specifically Stage 3G, was either located in zones of cut or received evenly distributed filling over volcanic ashes with soils not expected to be subject to significant settlement. Static settlements were therefore not monitored in Stage 3G.

However, Stage 3H and Lots 236-239 (Stage D) received up to 4m and 8m of fill material respectively during the 2013-14 season. Settlement monitoring points were therefore installed in these areas. The monitoring pins consisted of steel rods attached to plates installed at the base of the filling. The data from these pins are presented graphically in Appendix F and settlement marker locations shown on Figures 2 and 6 for Stage 3H and Lots 236-239 (Stage D) respectively.

8.2.1. Stage 3H

Static settlements below the 2014 filling were monitored at two locations shown as SM26 and SM27 on Figure 2. Measured settlements were 205mm and 390mm for SM26 and SM27.

The data show the majority of consolidation settlement below the filling occurred within 2 to 3 months of earthworks being completed. Thereafter, settlement entered a long term 'creep' phase. Extrapolating the data out for a period of 50 years indicated that lots in this area may be affected by up to 100mm of future creep settlement over the assumed life of the proposed dwellings. However, differential settlements within the affected lots would be expected to be within the allowable range recommended by MBIE (i.e. 25mm/6m length), provided additional fill does not exceed 0.6m.

8.2.2. Lots 236-239 (Stage D)

Static settlements were monitored over Lots 236-239 during and after the 2013-2014 and 2014-2015 work seasons.

Three settlement markers were installed, SM15, SM28, and SM28A as shown on Figure 6, however only SM28 remained functional during the whole monitoring period as the other two markers were either damaged or moved during fill placement.

In regards to SM28, monitoring from April 2015 to August 2016 indicated the filling had induced static settlements of 68mm and that settlement was ongoing. Extrapolating the data out for 50 years indicated long-term settlement may exceed 60mm, with a high likelihood of excessive differential settlement beneath the building platforms.

The area was therefore pre-loaded with 2m of topsoil in April 2016 as shown in Figure 6. Continuing monitoring indicated this pre-load induced an additional settlement of up to 47mm. Following the completion of monitoring in August 2016, the pre-load was removed.

Following preloading we consider that the potential for future static settlements beneath these lots has been reduced, and long term differential settlements would be expected to be within accepted limits, provided additional fill does not exceed 1.0m.

8.2.3. Fill Development Restrictions

To reduce possible future settlements, any additional filling the lots listed below should not exceed the following depths without the approval of the TCC Category 1 or 2 Geo-Professional:

- 1.0m for lots 236-239
- 0.6m for lots 495-502

8.3. Slope Stability

While the majority of proposed lots within Stage 3G are located on gently sloping ground, the lots within this stage adjacent to the eastern perimeter and all lots within Stage 3H are located above a steeper slope. Lots 236-239 are also positioned above steeper slopes to the east and south of the lot boundaries.

8.3.1. Lots 413, 458, 460 and 493-503

The adjacent slope below the plateau exhibited a few areas of instability. Colluvial soils were encountered in hand auger boreholes and test pits in this area and topographic evidence also suggested that this slope has been affected by larger scale ancient instability.

Stability analyses of this slope noted that values were generally less than required by the IDC for residential development and indicated that further instability may occur on this slope in the future during extreme rainfall events or under seismic loads.

As the slope is insufficiently stable for residential development, the lots are subject to a building restriction line (BRL) as shown on Figure 3. The BRL has been defined by either projecting a 1V:2.5H line from the toe of the steepest adjacent slope, or by measuring 15m back from the slope crest, whichever is smaller. The proposed setback distance is considered adequate for the residential development in this area.

8.3.2. Lots 236-239 (Stage 3D)

Slopes adjacent to Lots 236-237 have been engineered with a gradient of 1V:2.5H for which this gradient is considered to be an adequately stable slope angle for Tauranga soils. However, this does not allow for surcharge from residential buildings or fill and therefore a BRL has been placed on these lots, setback 3-5m from the slope crest as shown on Figure 6.

The slope south of lots 237-239 have been engineered with a gradient of 1V:3H and therefore are adequate for residential development without a BRL.

8.3.3. Slope Development Restrictions

For lots 236-237, 413, 458, 460 and 493-503, it should be understood that the inclusion of a BRL on a lot does not specifically preclude development beyond the restriction line. However, any development between the BRL and slope will require specific geotechnical input and may need additional slope protection works such as retaining walls, deepened foundations, etc. The following restrictions are recommended for these lots:

- Any part of a dwelling or structure which extends beyond the BRL must be reviewed and approved by a TCC Category 1 Geo-Professional prior to the building consent application. A geotechnical report must be provided including the specific design of any mitigation works proposed.

- Any filling between the BRL and slope must be reviewed and approved by a TCC Category 1 Geo-Professional with a report to be provided to Council before work begins.
- Stormwater from any paved or impermeable surfaces including roofs and driveways on these lots must be collected and piped to the site's stormwater system. Stormwater must not be disposed via ground soakage on these lots and any concentration of runoff over the slope must be avoided.

8.4. Stage 3G Retaining Wall

The construction of the timber pole retaining wall along the northern boundary of Stage 3G was observed by Coffey. This included regular site visits to confirm borehole and post dimensions and ground conditions along the wall alignment as specified in the retaining wall design report.

Based on our observations we consider the wall has been built in accordance with the design. A separate certification letter has been provided for the wall, a copy of which is included in Appendix G.

8.4.1. Retaining Wall BRL

As the wall has not been designed for additional surcharge loads, a BRL has been defined with a setback distance equal to the height of the wall. The BRL has been assigned to lots 441, 442, 444 to 455, 457 and 458 within Stage 3G as shown on Figure 3.

8.4.2. Retaining Wall Development Restrictions

Specifically for lots 441, 442, 444 to 455, 457 and 458, in regards to the BRL adjacent to the Stage 3G retaining wall, the following restrictions are recommended:

- Any part of a dwelling or structure which extends beyond the BRL must be reviewed and approved by a TCC Category 1 or 2 Geo-Professional prior to the building consent application. A geotechnical report must be provided including the specific design of any mitigation works proposed. Specific design may include, deepened foundations past the 45° zone of influence from the toe of the retaining wall.
- No filling is to take place between the BRL and crest of wall without review and approval by a TCC Category 1 or 2 Geo-Professional. Due to the height of the existing retaining wall, any additional filling or retaining structures above the wall and within the BRL may require a Resource Consent.
- Stormwater from any paved or impermeable surfaces including roofs and driveways on these lots must be collected and piped to the site's stormwater system and not allowed to flow over the the retaining wall.

8.5. Stage 3H Stormwater Pipe Line

As mentioned in Section 2, a stormwater pipeline was horizontally drilled or 'thrust' beneath the slope to the east of Stage 3H as part of the civil infrastructure installation in 2016. The pipeline was designed by Harrison Grierson Consultants Ltd. Coffey provided advice regarding the pipeline alignment and recommended the pipe was installed at least 3.0m below existing ground level to reduce the risk of damage in the event of slope failure

A copy of Harrison Grierson's design drawings for the pipeline is included in Appendix G. Based on our observations during drilling and as-built survey information from Harrison Grierson, we consider the pipeline has been installed along an appropriate alignment. The survey data indicate the pipe is at least 3.0m deep below the existing ground surface as recommended.

8.6. Foundation Design & Bearing Capacity

The lots within Stage 3G and Lots 236-239 (Stage D) are underlain by either engineered fill or natural soils that meet or exceed the conditions for 'good ground' as defined by NZS 3604. Dwellings on these sites may therefore be supported on standard shallow foundations designed for a geotechnical ultimate bearing capacity of 300kPa.

Lots 493 to 503 within Stage 3H also meet or exceed the conditions for 'good ground' as defined by NZS 3604. However, as the lots are moderately steeply sloping, development on these lots may require deep excavation to form a level building platform. We recommend that whenever the proposed depth of excavation exceeds 1.5m, additional investigation should be undertaken by a TCC Category 1 or 2 Geo-Professional at the design/building consent stage to confirm soil conditions below the proposed foundations. A consent notice to this effect should be added to the affected lots (see Form G3, Appendix B).

It should be understood that due to the volcanic nature of the natural soils on this site, it is possible that local soil conditions may vary from those discussed above. Some soils observed onsite are also potentially prone to sub-surface erosion (e.g. 'tomos'). It is therefore important that any potentially soft or unsuitable soils encountered in the foundation excavations are brought to the attention of a geotechnical professional.

8.7. Stormwater Management

To further reduce the potential for surface and sub-surface erosion, all stormwater from impervious areas within the development will need to be carefully collected and piped to a safe disposal point or to the reticulated network. Particular care should be taken to avoid areas of ponded stormwater or concentrated flows around and under buildings or structures.

9. CONCLUSION

Based on the observations and investigations presented in this report and with reliance on the diligence of the earthworks contractors, it is concluded that the earthworks and subdivision of Stages 3GH and Lots 236-239 of Stage 3D have been completed in general accordance with previous recommendations and current Tauranga City Council Infrastructure Development Code.

This report presents site-specific recommendations including Building Restriction Lines (BRLs) on some lots located above steeper slopes or adjacent to retaining walls. Provided these recommendations are followed and prudent development practices are adopted, it is considered that the finished lots are at low risk of erosion, falling debris, subsidence, inundation or liquefaction and these sites are therefore adequate for residential development without the need for Section 72 restrictions under the New Zealand Building Act.

Development outside the BRL (i.e. between the restriction line and the slope/retaining wall) is subject to further geotechnical input per Sections 8.3.3 and 8.4.2 of this report. The placement of additional filling is also restricted on some lots as per Section 8.2.3. The need for a Section 72 restriction on affected lots may therefore need to be re-assessed at the building consent stage.

10. LIMITATIONS

This report has been prepared solely for the use of the client, The Lakes (2012) Limited, their professional advisers and the relevant Territorial Authorities in relation to the specific project described herein. No liability is accepted in respect of its use for any other purpose or by any other person or entity. All future owners of this property should seek professional geotechnical advice to satisfy themselves as to its ongoing suitability for their intended use.

The opinions, recommendations and comments given in this report result from the application of normal methods of site investigation. As the post construction factual evidence has been obtained solely from boreholes and test pits, which by their nature only provide information about a relatively small volume of subsoils, there may be special conditions pertaining to this site which have not been disclosed by the investigation and which have not been taken into account in the report.

For and on behalf of Coffey

Report Prepared By:



D B CULLEN
Engineering Geologist

Report Reviewed By:



D SULLIVAN
Principal Geotechnical Engineer
BSc, MBA, CE (Calif.), MIPENZ, CPEng, TCC Category 1 Geotechnical Engineer
CPEng No. 1025183


Geotechnical Suitability Statement Signed By:



R TELFORD
TCC Category 2 Geotechnical Engineer

As Built.

(6 Nov (Requested by SF.))



Note:
 Coordinates in terms of Bay of Plenty 2000 Circuit
 Elevations are in terms of TCC BM 1341
 RL: 56.47
 Moturiki Datum

Wastewater connections and laterals are uPVC SN16
 25 OD Dry Riser water connection MOPE PN 12.5
 Stormwater connections and laterals are uPVC SN16
 Water Meter WBX 1 is 20mm Sensus C620M, Serial # 17M1560444, Manifold Type - Acuflo, Meter Size - 20mm, Manufacturer - Sensus Model - 620

Issue No	Issue Date	Issue Description	Author
1	Issued for 224	DP18	

S & L CONSULTANTS LTD
 SURVEYORS ENGINEERS PLANNERS
 10 Okataina Street, Mt Maunganui, New Zealand
 P.O. Box 271, P.O. 070174059
 Fax 07577 4065
 Email: info@sandl.co.nz
 Web Site: www.sandl.co.nz

Northing	Easting	Code
799428.93	368840.10	SWC 1
799429.02	368840.42	SSC 1
799426.93	368835.69	CP 1
799445.31	368819.90	WBX 1
799425.07	368835.76	SSRE 1
799407.37	368835.85	SWRE 2
799407.30	368837.04	SWC 2
799408.08	368836.03	SSRE 2
799407.94	368837.32	SSC 2
799424.42	368835.60	SWI1
799424.33	368835.73	SSI1
799407.41	368834.95	SWI2
799408.14	368835.12	SSI2

Lakes Homes Ltd
 10 Okataina Street, The Lakes

Asbuilt Plan
 Checked on this drawing is correct
 Drawing No: 21809 - AB01
 Date: 06-18
 Revision: 1

PRODUCER STATEMENT – PS4 – CONSTRUCTION REVIEW

(Guidance notes on the use of this form are available upon request)

ISSUED BY: *The Engineer Limited*
(Construction Review Firm)

TO: Paul Marsh
(Owner/Developer)

TO BE SUPPLIED TO: Tauranga City Council
(Building Consent Authority)

IN RESPECT OF: Building foundation ground preparation construction investigation and certification
(Description of Building Work)

AT: 16 Okataina St, Lot 2
(Address)
The Lakes LOT 237 DP 507200... SO

The Engineer Limited has been engaged by Paul Marsh

To provide CM1 CM2 CM3 CM4 CM5 (Engineering Categories) OR observation as per agreement with owner/developer
or other **Construction Monitoring** services
(Extent of Engagement)
in respect of clause(s) **B1 Structure** of the Building Code for the building work described in

documents relating to Building Consent No. and those relating
to Building Consent Amendment(s) Nos. issued during
the course of the works. We may have sighted these Building Consents and the conditions of attached to them.

Authorised instructions / variations(s) No. (copies attached)
or by the attached Schedule have been issued during the course of the works.

On the basis of this these review(s) and information supplied by the contractor during the course of the works
and on behalf of the firm undertaking this Construction Review, I believe on reasonable grounds that All Part
only of the building works have been completed in accordance with the relevant requirements of the Building Consent
and Building Consent Amendments identified above, with respect to Clause(s) **B1** of the Building Code. I also
believe on reasonable grounds that the persons who have undertaken this construction review have the necessary
competency to do so.

I, **Bruce Cameron** am: CPEng No. **173256**
(Name of Construction Review Professional)

I hold the following qualifications: **CPEng, BE, NZCE**

The Construction Review Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less
than \$200,000*.

SIGNED BY **Bruce Cameron** ON BEHALF OF **The Engineer Limited**

Date: ... **5 June 2018** Signature: 

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the
Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building
Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of
\$200,000*.

This form is to accompany **Forms 6 or 8 of the Building (Form) Regulations 2004** for the issue of a Code Compliance
Certificate.

SITE INSPECTION RECORD


Job No: 18031944

Date: 1/6/18

Job Name: Marsh - 16 Okatina St

Weather/Ground Conditions: lot 2

ITEM	Comments – Observations	Action Required
	Building requirements; SED / <u>Good Ground</u>	
	❖ Good Ground check. NZS3604 3.1.3. Reasonable inquiry;	
	• Site observation of; Site stripped <input checked="" type="checkbox"/>	
	a) Buried services <input checked="" type="checkbox"/>	
	b) Land slips/surface creep <input checked="" type="checkbox"/>	
	c) Uncertified fill <input checked="" type="checkbox"/>	
	d) Buried topsoil/unsuitable soils <input checked="" type="checkbox"/>	
	• Confirmation of;	
	e) Specific testing <input checked="" type="checkbox"/>	
	f) Immediate locality ok <input checked="" type="checkbox"/>	
	g) GCR <input checked="" type="checkbox"/>	
	• Ground bearing > 100kPa (allowable) or SED. <input checked="" type="checkbox"/>	
	Good Ground found. <input checked="" type="checkbox"/>	
	❖ SED requirements ? ;	
	(*1) 1070 (*2) 1070 820/10 800/6 530 590 4.0/6 350 290 230 180 130/3	Ok to proceed with construction <input checked="" type="checkbox"/>



236
DP 507200

235
DP 494113

973 DP 507200

238
DP 507200

239
DP 507200

1005
DP 507200

Okataina Street
Sealed - 15.00 Width & Over

Proposed Easements			
Purpose	Shown	Serv. Ten.	Dom. Ten.
ROW, Right to Convey Water, Electricity, Gas & Telecom	A	Lot 3 hereon	Lots 1 & 2 hereon
Right to Drain Sewage & Water	A	Lot 3 hereon	Lot 1 hereon
Right to Drain Sewer & Water	B	Lot 2 hereon	Lot 1 hereon

Area C and D are subject to an existing consent notice.

Amalgamation Conditions

The Lot 3 hereon (legal access) be held as to two undivided one half shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.

The Lot 173 DP 507200 (legal access) be held as two undivided one quarter shares by the owners of Lots 1 and 2 hereon and individual certificates of title be issued in accordance therewith.

APPROVED
Resource Consent
PLAN 14-14-2017

returned area

This plan has been prepared for the purposes of Section 224 of the Resource Management Act 1991 and should not be relied on for any other purpose.

Proposed Subject of Lot 237 DP 507200

16 Okataina Street

Engineered by D. Tennant Limited (Resource Consent)

1:100

1:100

ESL CONSULTANTS LTD
100 Okataina Street
Dunedin, New Zealand

1005
DP 507200

PRODUCER STATEMENT – PS4 – CONSTRUCTION REVIEW

(Guidance notes on the use of this form are available upon request)

ISSUED BY: *The Engineer Limited*
(Construction Review Firm)

TO: Paul Marsh
(Owner/Developer)

TO BE SUPPLIED TO: Tauranga City Council
(Building Consent Authority)

IN RESPECT OF: Timber pole retaining wall construction investigation and certification
(Description of Building Work)

AT: 16 Okataina St, Lot 2
(Address)
The Lakes LOT 237 DP 507200... SO

The Engineer Limited has been engaged by Paul Marsh

To provide CM1 CM2 CM3 CM4 CM5 (Engineering Categories) or observation as per agreement with owner/developer

or other Construction Monitoring services
(Extent of Engagement)

in respect of clause(s) B1 Structure, B2 Durability of the Building Code for the building work described in

documents relating to Building Consent No. -..... and those relating

to Building Consent Amendment(s) Nos. issued during

the course of the works. We may have sighted these Building Consents and the conditions of attached to them.

Authorised instructions / variations(s) No. (copies attached)

or by the attached Schedule have been issued during the course of the works.

On by the basis of this these review(s) and information supplied by the contractor during the course of the works and on behalf of the firm undertaking this Construction Review, I believe on reasonable grounds that All Part only of the building works have been completed in accordance with the relevant requirements of the Building Consent and Building Consent Amendments identified above, with respect to Clause(s) B1, B2 of the Building Code. I also believe on reasonable grounds that the persons who have undertaken this construction review have the necessary competency to do so.

I, Bruce Cameron am: CPEng No. 173256
(Name of Construction Review Professional)

I hold the following qualifications: CPEng, BE, NZCE

The Construction Review Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000*.

SIGNED BY Bruce Cameron ON BEHALF OF The Engineer Limited

Date: 5 June 2018 Signature: 

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000*.

This form is to accompany Forms 6 or 8 of the Building (Form) Regulations 2004 for the issue of a Code Compliance Certificate.

SITE INSPECTION RECORD

Job No: 18031944

Date: _____


Time: _____

Job Name: Marsh - lot 2, 16 Okatana St.

Weather/Ground Conditions: _____

ITEM	Comments - Observations	Action Required
	<p>Timber Poles Retaining Walls.</p> <ul style="list-style-type: none">- Leon - BOP Retaining - Builders.- TEL design 27/3/18- Foundations - 9/5/18. ✓- Drainage/Rails - ✓- Backfill ✓- As per design	<p>OK to Proceed.</p>

18031944



18031944

16 Okatana St.

27/5/18.


CANTILEVER TIMBER POLE RETAINING WALL DESIGN

Client: Marsh
Project: 16 Okatana Street, Lot 237, The Lakes
Project Number: 18031944
Wall Location: Subdivision Retaining

Retaining Wall Design Features Report/Construction Summary

Wall Height H (m)	Pole Spacing S (m)	SED Pole Size (mm)	Embedment hole size Ø (mm)	Embedment depth E (m)	Rail size and #	Rail Layers
0.50	1.2	175	350	0.9	150x50	1 layer
1.00	1.2	200	350	1.5	150x50	1 layer
1.50	1.2	225	400	2.1	150x50	1 layer

- Notes:**
- Construction to be in accordance with the Specification for Timber Retaining Walls, including cut timber treatment.
 - Design assumes level firm ground at the base of the wall
 - Poles to be placed with large end into embayment holes
 - Confirm site conditions match design assumptions
 - Timber Rails Grade = VSG8 or Grade 8
 - Timber Treatment: H4 Rails; H5 Poles
 - Design assumes cohesion less or sandy type soils, water level depth > E
 - 0° backfill slope
 - 5 kPa potential surcharge



Retaining

Shuler, Lowry

From: Willy Bedford <willy.bedford@venturedevelopments.co.nz>
Sent: Wednesday, January 23, 2019 10:42 AM
To: Shuler, Lowry
Subject: Fwd: BC182234

Hi Lowry,

See below email thread with the Okataina RFI's

Let me know if you need anything else.

Kind regards,

Willy Bedford • Marketing Consultant

D. [64 7 542 0101](tel:6475420101) • M. [+64 21 191 9800](tel:+64211919800) • W. www.venturedevelopments.co.nz

E. willy@venturedevelopments.co.nz



Begin forwarded message:

From: Nicole Holmes <nicole.holmes@venturedevelopments.co.nz>
Date: 10 January 2019 at 12:32:22 PM NZDT
To: Ben Graham <ben.graham@venturedevelopments.co.nz>, Willy Bedford <willy.bedford@venturedevelopments.co.nz>, Allen Burr <allen.burr@venturedevelopments.co.nz>
Cc: Michelle Paddison <michelle@regionalchambers.co.nz>
Subject: FW: BC182234

FYI

Kind Regards

Nicole Holmes • Operations Assistant
D. 07 542 0114 • W. www.venturedevelopments.co.nz
E. nicole@venturedevelopments.co.nz



From: Simon Fitzpatrick <Simon.Fitzpatrick@tauranga.govt.nz>
Sent: Thursday, 10 January 2019 12:31 PM
To: Nicole Holmes <nicole.holmes@venturedevelopments.co.nz>
Subject: RE: BC182234

Hi Nicole

I have discussed the issue of the earthworks and unconsented walls on these lots with Council's legal team. They agree with me. These works were not part of the resource consent. Therefore, it will be up to Venture to work through the issues below with the developer. These will still need to be completed for CCC to be issued.

- **BC182223, 18 Okataina St**

Development Engineer requested for COA on upper wall.

- **BC182234, 16 Okataina St**

S37, RMA hold – Advise notes added.

1. Have the fill over the BRL assessed by a Cat 1 Geo-Professional. Carry out any remedial works that this may require.
2. Have the areas of fill exceeding 1.0m, assessed by a Cat 1 Geo-Professional.
3. Have the retaining wall assessed by a Cat 1 Geo-Professional.
4. Ensure the dwelling is no closer to the top of the wall than the walls height at that location.
5. Remove the up to 0.7m of pumice sand fill from against the noise wall.

Cheers

Simon Fitzpatrick | Team Leader, Land Development Engineering
Tauranga City Council | 07 577 7000 | 021 277 7302 | simon.fitzpatrick@tauranga.govt.nz | www.tauranga.govt.nz

From: Nicole Holmes <nicole.holmes@venturedevelopments.co.nz>

Sent: Monday, 7 January 2019 9:46 a.m.

To: Simon Fitzpatrick <Simon.Fitzpatrick@tauranga.govt.nz>

Subject: BC182234

Hi Simon,
Happy New Year
Back onto this issue....did your legal team get anywhere with it?

Thanks

Kind Regards

Nicole Holmes • Operations Assistant
D. 07 542 0114 • W. www.venturedevelopments.co.nz
E. nicole@venturedevelopments.co.nz



The contents of this e-mail and any attachments is confidential and may be privileged and/or subject to copyright. Unauthorised use, distribution or copying of the contents is expressly prohibited. If you are not the intended recipient, notify the sender immediately, delete the email and attachments and all copies from your system, and do not use, read, distribute, disclose or copy its contents. Violation of this notice may be unlawful. Views expressed in this e-mail and attachments are those of the author, and not necessarily those of Tauranga City Council. Tauranga City Council does not accept liability for any loss, damage or consequence arising from this email and/or attachments containing any virus, defect, data corruption or transmission error.

This email has been scrubbed for your protection by SMX. For more information visit smxemail.com

22 February 2019

Our ref: 773-TRGGE226846AB

Venture Developments Limited
Unit 1, 16 Ashley Place
Papamoa Beach, Papamoa 3118

Attention: Jarod Thorpe

Dear Jarod Thorpe ,

**Addendum to Geotechnical Plan Review Report
Proposed Residence at 16 Okataina, The Lakes, Tauriko, Tauranga**

1. Introduction

It is proposed to construct a single-storey residence at the property located at 16 Okataina Street in The Lakes subdivision, Tauriko and legally described as Lot 2 DP 514907. Coffey Services (NZ) Limited (Coffey) has previously conducted a geotechnical review of residential design plans and supporting documentation for the proposed development, dated 9 February 2019.

As stated in the Geotechnical Plan Review, TCC has requested the following in relation to the proposed development:

1. Have the fill over the BRL assessed by a Cat 1 Geo-Professional. Carry out any remedial works that this may require.
2. Have the areas of fill exceeding 1.0m, assessed by a Cat 1 Geo-Professional.
3. Have the retaining wall assessed by a Cat 1 Geo-Professional.
4. Ensure the dwelling is no closer to the top of the wall than the wall's height at that location.
5. Remove the up to 0.7m of pumice sand fill from against the noise wall.

Based on the geotechnical plan review, in order to address the concerns raised by TCC and to provide adequate support for the proposed development, the following measures were recommended:

- Install an appropriate drainage system behind the existing retaining wall;
- Deepen foundations adjacent to the existing retaining wall by 400mm to account for uncertainty of fill quality and retaining wall adequacy; and,
- Conduct confirmatory testing of fill compaction and quality.

In accordance with the terms and conditions of the short-form agreement¹ signed on 4 February 2019, Coffey has completed the observations and testing recommended in the Geotechnical Plan Review.

This addendum report includes the results of testing, site observations and further recommendations, and is intended to accompany the 9 February Geotechnical Plan Review report to be submitted in support of the Building Consent application with Tauranga City Council (TCC).

2. Construction Testing and Observation

As recommended in the Geotechnical Plan Review, Coffey carried out confirmatory testing of the constructed building platform subgrade soils on 13 February 2019. The results of this testing indicated that fill within a couple metres of the retaining wall and beneath the south eastern corner of the proposed building footprint had not been adequately compacted. On 15 February, further testing was conducted to delineate the area of loose fill. In these areas, Scala penetrometer results of 1 to 4 blows per 100mm penetration were recorded to depths of 900mm with lowest results at the surface and base of filling. Scala results were most commonly 3 or less.

On 18 February 2019, loose fill material was removed from the area between the retaining wall and approximately 1m inside of the southern house foundation line and the area within the south eastern corner of the building. The recommended drainage was placed behind the wall comprising perforated drainage pipe in drainage metal and wrapped in filter fabric. Existing fill was replaced in relatively thin lifts and compacted with a vibratory roller. Additional import granular fill was required to reach finished grade due to the additional compaction achieved within the fill.


Photo 1: Drainage pipe



Photo 2: Drainage metal



Photo 3: Filter fabric



On 19 February 2019, Coffey visited the site to observe and test the remediated areas of fill. At this time, the granular material which had been deposited between the retaining wall and the boundary fence had been removed. Within the remediated fill, Scala penetrometer results of 5 to 10 blows per 100mm penetration were recorded. Scala results were slightly lower than 5 blows per 100mm within 200mm to 300mm of the surface; however, lower penetration resistance this close to the surface would be more a function of the dynamic nature of the test itself and the granular fill being unconfined. Therefore, the fill is considered to be adequately compacted and suitable for foundation support.

¹ "Short Form Agreement for Consultant Engagement", ref: P226846, signed 4 February 2019.


Photo 4: Fill excavation



Photo 5: Fill re-compaction



Photo 6: Over wash removed



3. Revised Foundation Recommendations

It is common to recommend that building foundations maintain a distance equal to the height of the wall so that foundation loads do not influence the wall. As noted in the Geotechnical Plan Review, although a building may not influence an otherwise stable wall at this distance, a retaining wall that fails could influence a building foundation at a greater distance. Due to the uncertainty of the site works and wall construction, it was recommended that drainage be placed behind the wall as discussed previously and that foundations within 2m of the wall be deepened by 400mm. The deepening of foundations was largely to account for uncertainty in the overall quality of site preparation.

With the over excavation of loose fill that was conducted and adequate re-compaction of the fill from the retaining wall to within the building footprint, it is Coffey's opinion that an adequate building platform is present and that the risk of a retaining wall failure causing a loss of support to the foundation subgrade soils at the proposed building location has been adequately mitigated. Therefore, based on foundations being located a minimum distance from the back of the wall equal to the retained height, it is no longer considered necessary to deepen foundations and standard rib-raft type foundation in accordance with NZS3604:2011 may be used.

4. Conclusion

Remedial measures recommended in the Geotechnical Plan Review dated 9 February have been carried out and testing of site subsoils including remediated structural fill indicates that a stable building platform is now present offering adequate support for conventional shallow foundations specifically designed for a nominal (ultimate) geotechnical bearing capacity of 300kPa or detailed in accordance with NZS3604:2011.

The following sections summarise the resolution of the individual issues raised by TCC:

4.1. Have the fill over the BRL assessed by a Cat 1 Geo-Professional. Carry out any remedial works that this may require.

An assessment of the impact of the quantity of filling over the BRL has been carried. Based on Coffey's site observations, assessment and the provided documentation, it appears that this filling is unlikely to significantly decrease the stability of the eastern slope.

4.2. Have the areas of fill exceeding 1.0m, assessed by a Cat 1 Geo-Professional.

Based on Coffey's observations of the site in its current state and the previous surcharging of the site, it is unlikely that the approximately 1m of fill placed in the southern portion of the property would significantly decrease the stability of the site or cause excessive settlement.

4.3. Have the retaining wall assessed by a Cat 1 Geo-Professional.

Based on a qualitative assessment of the features of the retaining wall that were easily visible and the provided documentation, it was recommended in the Geotechnical Plan Review that additional drainage be installed behind the wall. This drainage has now been installed. Based on the installation of drainage, the remediation of filling between the wall and the proposed building foundations, and the proposed distance of the residence from the wall, it is unlikely that the retaining wall represents a significant risk to the stability of the site at the proposed building location.

4.4. Ensure the dwelling is no closer to the top of the wall than the walls height at that location.

It appears that the development plans have located the building an adequate distance from the retaining wall to satisfy this requirement. It is recommended that distance from the retaining wall be verified during construction once foundation formwork has been placed but prior to concrete placement.

4.5. Remove the up to 0.7m of pumice sand fill from against the noise wall.

Based on observations on 19 February, it appears that this fill has been removed.

5. Limitations

While this letter presents a summary of the geotechnical conditions for this area it does not provide a complete discussion of geotechnical issues affecting the Lakes Stage 3D area or previous earthworks undertaken on the site. It is therefore recommended that designers working on the new lots are also familiar with the contents of the original Stage 3D GCR.

This letter has been prepared solely for the use of our client, their professional advisers and the relevant territorial authorities in relation to the specific project described herein. No liability is accepted in respect of its use for any other purpose or by any other person or entity. All future owners of this property should seek professional geotechnical advice to satisfy themselves as to its on-going suitability for their intended use.

Addendum to Geotechnical Plan Review Report
Proposed Residence at 16 Okataina, The Lakes, Tauriko, Tauranga

Please do not hesitate to contact the undersigned if you require any further information.

Regards,



Lowry Shuler
Senior Geotechnical Engineer
CPEng No. 1029886
TCC Category 2 Geotechnical Engineer



David Sullivan
Principal Geotechnical Engineer
CPEng No. 1025183
TCC Category 1 Geotechnical Engineer

Attachments:

Test Location Plan
Hand Auger Bore Logs
Penetration Resistance Test Results

Engineering Log - Hand Auger

client: **Venture Developments Limited**

principal:

project: **16 Okataina street, Pyes Pa**

location: **See attached site plan**

Borehole ID: **HA01**

sheet: 1 of 1

project no. **773-TRGGE226846**





date started: **13 Feb 2019**

date completed: **13 Feb 2019**



logged by: **ML**

checked by: **LS**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.: 2459

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations
	1 2 3							SOIL TYPE: plasticity or particle characteristic, colour, secondary and minor components			50 100 150 200	2 4 6 8 10	
HA	N	Not Encountered			0.5			SAND: fine to coarse grained, white grey, pumice sand.	D to M	L to MD			PUMICE SAND FILL
			VS 122/ 46 kPa		1.0			Silty CLAY: medium plasticity, brown.	M	St to VSt	⊕ ⊙		VOLCANIC ASHES
			VS 82/ 30 kPa		1.5						⊕ ⊙		
			VS 114/ 27 kPa		2.0			Hand Auger HA01 terminated at 2.0 m Target depth			⊕ ⊙		

CDF_0_9_06_LIBRARY/GLB rev:AR Log COF BOREHOLE: NON CORED + DCP 226846 16 OKATAINA ST GINT.GPJ <<DrawingFiles>> 22/02/2019 11:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud N nil C casing penetration  no resistance ranging to refusal water 10-Oct-12 water level on date shown  water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
---	--	--	---	--









* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit

Engineering Log - Hand Auger



Borehole ID. **HA02**
 sheet: 1 of 1
 project no. **773-TRGGE226846**
 date started: **13 Feb 2019**
 date completed: **13 Feb 2019**
 logged by: **ML**
 checked by: **LS**

client: **Venture Developments Limited**
 principal:
 project: **16 Okataina street, Pyes Pa**
 location: **See attached site plan**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.: 2459

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations
HA	N	Not Encountered			0.5			SAND: fine to coarse grained, white grey, pumice sand with trace gravels.	D to M	MD to D			PUMICE SAND FILL
			VS >190 kPa		1.0			Clayey SILT: low to medium plasticity, orange brown mottled brown.	M	VSt to H			SUBDIVISION FILL
			VS >190 kPa		1.5								
			VS >190 kPa		2.0			Hand Auger HA02 terminated at 1.8 m Target depth					

CDF_0_9_06_LIBRARY/GLB rev:AR Log COF BOREHOLE: NON CORED + DCP 226846 16 OKATAINA ST GINT.GPJ <<DrawingFiles>> 22/02/2019 11:50

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 10-Oct-12 water level on date shown 	moisture D dry M moist W wet S saturated Wp plastic limit WI liquid limit		

Engineering Log - Hand Auger



Borehole ID. **HA03**
 sheet: 1 of 1
 project no. **773-TRGGE226846**
 date started: **13 Feb 2019**
 date completed: **13 Feb 2019**
 logged by: **ML**
 checked by: **LS**

client: **Venture Developments Limited**
 principal:
 project: **16 Okataina street, Pyes Pa**
 location: **See attached site plan**

position: Not Specified surface elevation: Not Specified angle from horizontal: 90° DCP id.:
 drill model: Hand Auger drilling fluid: hole diameter : 50 mm vane id.: 2459

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	classification symbol	material description	moisture condition	consistency / relative density	vane shear (kPa)	DCP (blows/100 mm)	structure and additional observations
HA	N	Not Encountered	VS >190 kPa		0.5			SAND: fine to coarse grained, grey white, pumice sand.	D				PUMICE SAND FILL
			VS >190 kPa		1.0			Clayey SILT: low to medium plasticity, brown mottled orange brown and dark brown.	M	VSt to H			SUBDIVISION FILL
			VS >190 kPa		1.5			Hand Auger HA03 terminated at 1.3 m Target depth					

CDF_0_9_06_LIBRARY/GLB rev:AR Log COF BOREHOLE: NON CORED + DCP 226846 16 OKATAINA ST GINT.GPJ <<DrawingFiles>> 22/02/2019 11:51

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	classification symbol & soil description based on Unified Classification System	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense	moisture D dry M moist W wet S saturated Wp plastic limit Wl liquid limit
---	--	---	---	--	---	--	--

* bit shown by suffix
 e.g. AD/T
 B blank bit
 T TC bit
 V V bit



**PENETROMETER
PENETRATION RESISTANCE
(Scala)**

Client: Venture Developments Limited

Job No 226846

Project: 16 Okataina Street

Date 13-Feb-19 / 15-Feb-19

Test Area: Building platform

By: ML **Checked:** LS

Test No	DCP 1	DCP 2	DCP3	DCP 4	DCP 5	DCP 6	DCP 7	DCP 8
Date Tested	13-Feb	13-Feb	13-Feb	13-Feb	13-Feb	15-Feb	15-Feb	15-Feb
Test Location								
Start depth (mm)	0	0	0	0	0	0	0	0
100	1	4	1	1	2	1	1	6
200	5	3	2	3	3	1	2	6
300	6	3	2	4	4	2	6	7
400	6	3	2	3	4	4	8	5
500	6	1	1	3	3	4	6	4
600	5	3	1	1	4	4	6	4
700	3	2	2	1	2	3	4	6
800	2	2	1	1	1	3	3	4
900	2	2	1	1	2	4	2	2
1000								
Test No	DCP 9	DCP 10	DCP 11	DCP 12	DCP 13	DCP 14	DCP 15	
Date Tested	15-Feb	15-Feb	15-Feb	15-Feb	15-Feb	15-Feb	15-Feb	
Test Location								
Start depth (mm)	0	0	0	0	0	0	0	
100	6	6	2	4	5	4	4	
200	8	6	4	3	6	9	7	
300	6	3	4	6	10	6	7	
400	4	4	3	5	6	6	6	
500	2	3	3	6	5	8	6	
600	3	3	3	4	7	7	2	
700	2	1	2	3	6	4	3	
800	2	1	2	3	5	2	4	
900	1	2	2	2	5	2	3	
1000								

Notes:



**PENETROMETER
PENETRATION RESISTANCE
(Scala)**

Client: Venture Developments Limited

Job No 226854

Project: 16 Okataina St

Date 19-Feb-19

Test Area: Building Platform

By: ML **Checked:** LS

Test No	DCP 16	DCP 17	DCP 18	DCP 19	DCP 20	DCP 21	DCP 22	
Date Tested	19-Feb	19-Feb	19-Feb	19-Feb	19-Feb	19-Feb	19-Feb	
Test Location								
Start depth (mm)	0	0	0	0	0	0	0	
100	1	3	3	3	3	4	3	
200	4	4	4	5	5	5	5	
300	4	4	5	6	6	6	6	
400	5	6	8	7	8	10	7	
500	7	8	8	9	8	8	9	
600	8	9	9	7	8	6	6	
700	7	8	9	8	8	3	5	
800	9	9	9	6	6	3	3	
900	9	8	6	5	4	2	2	
1000								
Test No								
Date Tested								
Test Location								
Start depth (mm)								
100								
200								
300								
400								
500								
600								
700								
800								
900								
1000								

Notes: