



# EQC & information

**Harcourts**  
**Holmwood**  
*my kind of people*

[holmwood.co.nz](http://holmwood.co.nz)



## EQC Full Assessment Report

**Claim Number:** CLM/2011/102777  
**Claimant:** JASON SAIL  
**Property Address:** 26 HEMINGWAY PLACE  
 SPENCERVILLE  
 CHRISTCHURCH 8083

**Assessment Date:** 04/07/2011 17:30  
**Assessor:** Nicholls, Kerry  
**Estimator:** Solomon, Jason  
**Property Occupied By:** Owner Occupied

### Claimant Setup

Type	Name	Home Number	Mobile Number	Work Number	Email Address
Owner	JASON, SAIL				
Owner	Rasmussen-Sail, Anne-Grete				

### Insurance & Mortgage Details

#### Insurance Details - From Claim Centre

Insurer	Policy Type	Policy Number	Insurance Sighted	Insurance Valid
AA Insurance (AA/SIS/Sun Direct)	Dwelling		Yes	

#### Insurance Details - Added in COMET

Insurer	Policy Type	Policy Number	Insurance Sighted	Insurance Valid
---------	-------------	---------------	-------------------	-----------------

#### Insurance Details - Comments

#### Mortgage Details - From Claim Centre

##### Bank

#### Mortgage Details - Added in COMET

##### Bank

NATIONAL BANK OF NEW ZEALAND

#### Mortgage Details - Comments

No money owing but still registered

#### Opt Out

For repairs costing between \$10,000 and \$100,000 the claimant wishes to manage their own repairs? No

### Hazards

**Hazards:** Two very friendly dogs on site

**Property Sticker:** No Sticker

### Building Configurations

Leaky Home Syndrome? No

Building Name	Number of floors	Building Finish	Age of house	Footprint	Area (m2)
Main Building	1	Standard	Post 1980	Rectangular	202.08



## Full Assessment

### Site

Element	Type	Material	Damages	Measure	Rate	Cost
Land	Exposed	Sand	Significant land crack > 100mm			
			Excavate top 500mm soil and 300mm either side of crack. Plate compact at 100mm layers	4.20 m3	904.00	3,796.80
Land	Under dwelling	Sand	No Earthquake Damage			
<b>General Comments:</b> Unable to ascertain damage under dwelling as concrete slab covers area - engineer's report will need to determine if any issues.						

### Services

Element	Type	Material	Damages	Measure	Rate	Cost
Sewerage	Town Connection	PVC Pipe				
Water Supply	Town Connection	Plastic	No Earthquake Damage			
<b>General Comments:</b>						

### Main Building

#### Exterior

##### Elevation (North)

**Damage:** Earthquake damage

**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Wall Cladding	Brick Veneer	Brick	Cracking			
			Grind out and repoint mortar	1.00 l/m	35.00	35.00
			Structural damage			
			Relay and re-bed loose bricks	1.00 m2	85.00	85.00
Wall framing	Timber Frame	Timber	No Earthquake Damage			

**General Comments:**

##### Elevation (South)

**Damage:** Earthquake damage

**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Wall Cladding	Brick Veneer	Brick	Structural damage			
			Relay and re-bed loose bricks	1.00 m2	85.00	85.00
Wall framing	Timber Frame	Timber	No Earthquake Damage			

**General Comments:**

##### Elevation (East)

**Damage:** No damage

**Require Scaffolding?** No

**General Comments:** 14\*2.3 brick cladding

##### Elevation (West)

**Damage:** Earthquake damage

**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Wall Cladding	Brick Veneer	Brick	Cracking			
			Grind out and repoint mortar	5.00 l/m	35.00	175.00
Wall framing	Timber Frame	Timber	No Earthquake Damage			

**General Comments:**

### Foundations

**Damage:** Earthquake damage

**Require Scaffolding?** No



Element	Type	Material	Damages	Measure	Rate	Cost
Slab foundation	Concrete Slab	Concrete	Slab has moved greater than 25mm over 6 metres			
			Refer engineer designed solution	308.00 m2	500.00	154,000.00

**General Comments:****Roof**

**Damage:** No damage  
**Require Scaffolding?** No  
**General Comments:** Trussed metal tile

**Ground Floor - Internal Garage**

**Damage:** Earthquake damage  
**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	Cosmetic Damage			
			Rake out, plaster and paint	36.00 m2	34.00	1,224.00
Door (External)	SG Single	Aluminium	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	No Earthquake Damage			
Floor	Concrete	Concrete	No Earthquake Damage			
Garage door	Sectional Metal	Aluminium	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	57.60 m2	34.00	1,958.40
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Bathroom**

**Damage:** Earthquake damage  
**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Bath	Acrylic	Standard specification	No Earthquake Damage			
Bathroom Sink	Vanity single	Standard specification	No Earthquake Damage			
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	No Earthquake Damage			
Floor	Concrete	Vinyl	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	26.40 m2	34.00	897.60
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Toilet**

**Damage:** Earthquake damage  
**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	No Earthquake Damage			
Floor	Concrete	Concrete	No Earthquake Damage			
Toilet	Standard	Standard Spec	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	14.40 m2	34.00	489.60
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Entry**



**Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (External)	DG Single	Aluminium	No Earthquake Damage			
Floor	Concrete	Vinyl	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	32.16 m2	34.00	1,093.44

**General Comments:****Ground Floor - Lounge****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	No Earthquake Damage			
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	45.12 m2	34.00	1,534.08
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Living****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	Cosmetic Damage			
			Rake out, plaster and paint	21.50 m2	34.00	731.00
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	44.64 m2	34.00	1,517.76
Wall framing	Timber Frame	Timber	No Earthquake Damage			
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Kitchen (Kitchen and dining combined)****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	Cosmetic Damage			
			Rake out, plaster and paint	21.76 m2	34.00	739.84
Door (External)	DG Sliding	Aluminium	Cosmetic damage			
			Realign	1.00 No of	90.00	90.00
Door (Internal)	Single Hollow Core	Timber	Cosmetic damage			
			Ease and repaint door	1.00 No of	130.00	130.00
Floor	Concrete	Vinyl	No Earthquake Damage			
Hob	Electric	Standard Spec	No Earthquake Damage			
Kitchen joinery	Medium Spec	MDF	Structural damage			
			Repair units	1.00 No of	200.00	200.00
Range ( Free standing oven )	Electric	Standard Electric	No Earthquake Damage			
Range Hood	Over Head	Standard spec	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Paint wall	47.04 m2	24.00	1,128.96
			Structural damage			



## Released under the Official Information Act 1982

Wall covering	Gib	Paint	Remove, dispose, replace Gib, stop and undercoat	47.04 m2	99.00	4,656.96
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			
Work top	Kitchen work top	Laminate	No Earthquake Damage			

**General Comments:****Ground Floor - Bedroom (Bed 3)****Damage:** No damage**Require Scaffolding?** No**General Comments:** Painted walls and doors, carpet on floor**Ground Floor - Bedroom (Bed 2)****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	Cosmetic damage			
			Ease and repaint door	1.00 No of	130.00	130.00
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	34.56 m2	34.00	1,175.04
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Office/Study****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	Cosmetic damage			
			Ease and repaint door	1.00 No of	130.00	130.00
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	34.56 m2	34.00	1,175.04
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Bedroom (Bed 1)****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	No Earthquake Damage			
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Paint wall	44.64 m2	24.00	1,071.36
			Structural damage			
			Remove, dispose, replace Gib, stop and undercoat	44.64 m2	99.00	4,419.36
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - En Suite****Damage:** Earthquake damage**Require Scaffolding?** No



Element	Type	Material	Damages	Measure	Rate	Cost
Bathroom Sink	Vanity single	Standard specification				
Ceiling	Gib	Paint	No Earthquake Damage			
Door (Internal)	Single Hollow Core	Timber	Cosmetic damage			
			Ease and repaint door	1.00 No of	130.00	130.00
Floor	Concrete	Vinyl	No Earthquake Damage			
Mirror (Fixed)	Standard Spec	Mirror	No Earthquake Damage			
Shower	Cubical shower unit	Acrylic shower	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	23.04 m2	34.00	783.36
Window	Aluminium Awning	Pane double glazed	No Earthquake Damage			

**General Comments:****Ground Floor - Walk In Wardrobe****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	No Earthquake Damage			
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	16.32 m2	34.00	554.88

**General Comments:****Ground Floor - Hallway****Damage:** Earthquake damage**Require Scaffolding?** No

Element	Type	Material	Damages	Measure	Rate	Cost
Ceiling	Gib	Paint	Cosmetic Damage			
			Rake out, plaster and paint	10.00 m2	34.00	340.00
Door (Internal)	Single Hollow Core	Timber	Cosmetic damage			
			Ease and repaint door	2.00 No of	130.00	260.00
Floor	Concrete	Carpet	No Earthquake Damage			
Wall covering	Gib	Paint	Cosmetic damage			
			Rake out, plaster and paint	52.80 m2	34.00	1,795.20

**General Comments:****Fees**

Name	Duration	Estimate
Engineers report	1.00	3,555.00
Contents movement fee	1.00	808.30

**Overheads**

Name	Estimate
Preliminary and general	14,922.61
Margin	20,581.86
GST	33,960.07



## Scope Of Works Estimate

### Property

Description	Estimate
Site	3,796.80
Services	0.00
	3,796.80

### Main Building

Name	Description	Estimate
Exterior	Foundations	154,000.00
	Roof	0.00
	Elevation (East)	0.00
	Elevation (North)	120.00
	Elevation (South)	85.00
	Elevation (West)	175.00
		154,380.00

Floor	Description	Estimate
Ground Floor	Bathroom	897.60
	Bedroom (Bed 1)	5,490.72
	Bedroom (Bed 2)	1,305.04
	Bedroom (Bed 3)	0.00
	En Suite	913.36
	Entry	1,093.44
	Hallway	2,395.20
	Internal Garage	3,182.40
	Kitchen (Kitchen and dining combined)	6,945.76
	Living	2,248.76
	Lounge	1,534.08
	Office/Study	1,305.04
	Toilet	489.60
	Walk In Wardrobe	554.88
		28,355.88

28,355.88

### Fees

Description	Estimate
Engineers report	3,555.00
Contents movement fee	808.30
	4,363.30

### Overheads

Description	Estimate
Preliminary and general	14,922.61
Margin	20,581.86
GST	33,960.07
	69,464.54

<b>Total Estimate</b>	<b>260,360.52</b>
-----------------------	-------------------



**Inspection Sign Off**

Description	Answer	comments
<b>Land Damage</b>		
Is there land damage?	Yes	Major cracking noted in repair strategy. In orange zone.
<b>Contents Damage</b>		
Has the contents schedule been left with claimant?	Yes	
Have the contents been sighted?	No	
<b>Was a full inspection done?</b>		
In roof space	Yes	
On roof?	No	Weather conditions.
Under sub floor?	No	Concrete floor
<b>Decline Claim</b>		
Recommend Declining Claim	No	
<b>Next Action:</b>		

**Previous Claim Numbers (recorded manually in field)**

- 2010/024869

**File Notes**

**Date Created:** 05/07/2011 09:51  
**Created :** Nicholls, Kerry  
**Subject:** Overview  
**Note:** This property is located in a quiet street, on a flat level section, having suffered minor cosmetic damage although the land suffered approx 10% liquefaction which has been removed by the owner. The damage estimate is September 80% February 20% and is habitable. The land has an easment for a council drain on the property.  
 Lot 30 DP 319911.  
**Next Action:**

**Date Created:** 14/12/2012 06:50  
**Created :** Administrator, Alchemy  
**Subject:** Assessment Address Changed  
**Note:** From:26 HEMINGWAY PLACE, BROOKLANDS, CHRISTCHURCH  
 To:26 HEMINGWAY PLACE, SPENCERVILLE, CHRISTCHURCH  
**Next Action:**

**Urgent Works Items**





22 February 2017

Our Ref: 170050

To: Lena Mercer  
26 Hemingway Place  
Brooklands, 8083  
Christchurch

email: l.teamo@xtra.co.nz

## **RESIDENTIAL ENGINEERING EVALUATION REPORT AND REPAIR METHODOLOGY FOR 26 HEMINGWAY PLACE, BROOKLANDS**

### **1. Introduction**

Frontier Engineers was appointed by the Client to conduct a site inspection and provide an appropriate repair methodology for the Residential Building at 26 Hemingway Place, Brooklands.

### **2. Observations**

#### **2.1. General Layout**

The Single Storey Residential Building and Attached Double Garage consists of a 240 wide x 400 deep Reinforced Concrete Perimeter Beam supporting an internal Unreinforced Concrete Floor Slab on compacted hardfill. The external cladding consists of 70 Series Brick Veneer and the internal cladding consists of 10 mm rated plasterboard. The Timber roof framing supports Colorsteel Colortiles.

The floor plan is an irregular shape with multiple projections. No heavy masses such as chimneys were identified.

## **FRONTIER ENGINEERS Ltd**





## 2.2. Site Observations and Measurements

The Residential Building recorded floor levels are shown in Appendix 1. Appendix 2 contains a map of the recorded cracks in the Concrete Floor Slab and Site Photographs are shown in Appendix 3.

### 2.2.1 Floor Levels

Floor levels were recorded using a Nivcomp level machine at the surface of the Concrete floors as all floor coverings were removed. The maximum differential settlement recorded is 76 mm. The highest level occurs at the Southwestern corner in the en-suite bathroom and the lowest recorded level occurs at the Northeastern corner in the lounge.

The MBIE has guidance around floor levels which takes into consideration non-earthquake related settlement, construction tolerances and serviceability requirements. The guidance recommends that where total differential settlement over the floor plan is between 50 mm and 100 mm, re-levelling is required.

### 2.2.2 Concrete Foundation System

The Residential Building Concrete Floor Slab was inspected and no control joints were identified which is rare for an irregularly shaped floor slab.

Cracks were recorded during the site inspection, most cracks were between 0.4 mm and 0.8 mm wide and typically originate from re-entrant corners. The maximum crack width recorded is 1.9 mm at the master bedroom. A floor plan indicating the recorded cracks is shown in Appendix 2. Due to the absence of adequate control joints, the extent and width of the cracks observed, it is Frontier Engineers opinion that the cracks are predominantly due to drying shrinkage of the irregularly shaped floor slab. It is likely that the cracks may have been exacerbated by the Canterbury Earthquake Sequence, but the crack widths and lack of super-structure damage indicates that exacerbation and widening of the cracks was minimal.

The maximum cumulative crack width recorded in any direction is 5.10 mm which is below the threshold of 20 mm as indicated by the MBIE Guidance for lateral stretch of a Concrete Foundation. Furthermore, the lateral stretch criteria is typically applied to the Concrete Perimeter Foundation Beam which, when observed from the exterior around the perimeter of the Residential Building, did not contain any noticeable cracks.

The perimeter Concrete foundation beam and floor slab are not damaged to an extent that could limit re-levelling





### 2.2.3 Walls and Lining

The verticality of walls were recorded and found to be within construction tolerance except for one garage wall at the Northern elevation and the dining room wall at the western elevation. The recorded verticality of 8 mm/m and 7 mm/m is not a structural concern and does not indicate that the lateral bracing capacity of the Residential Building is compromised. No pattern of racking or creasing in the corners of joining walls and ceilings was noted that would indicate that the ability of the Residential Building to withstand a future seismic event is reduced.

### 2.2.4 Roof

The roof is in a good structural condition as no deflection of the ridgeline or variable slopes in the gutter and valleys was noted. The roof cladding was not loose and downpipes appeared in working order.



### 3. Repair Methodology

Considering the recorded floor levels and observed damage at the Concrete Floor Slab and Concrete Perimeter Foundation Beam, it is Frontier Engineers opinion that the Residential Building may be re-levelled in order to achieve acceptable floor slopes as required by the current New Zealand Building Code and the MBIE Guidance for Residential Buildings damaged by the Canterbury Earthquake Sequence.

With reference to the site specific Geotechnical Investigation Report which was completed for 26 Hemingways by Riley Consultants, 200 kPa is available at 0.45 m<sup>1</sup> below natural ground level. A bearing capacity of 200 kPa is adequate for re-levelling.

Specific Engineering Designed Concrete re-levelling pads may be constructed below the existing Concrete Foundation Beam by a specialist contractor. It is common for further cracking to occur as a result of re-levelling processes which may require additional repairs and needs to be completed prior to completion of works.



---

Stefan Pienaar  
*Senior Engineer, B Eng*



---

Alan Pearson  
*Director, CPEng*

---

<sup>1</sup> 26 Hemingways Place, Geotechnical Investigation Report, Riley Consultants, 4 July 2013 – page 4



## Appendix 1: Floor Level Survey




Figure 1: Floor Level Survey



## Appendix 2: Crack Map




Figure 2: Crack Map



### Appendix 3: Photographs



**Photo 1: Typical Concrete Perimeter**



**Photo 2: Typical damage at internal lining damage**



**Photo 3: Typical crack originating at re-entrant corners**



**Photo 4: Roof in good condition**



14 March 2017

G W Mercer  
2 Riverside Lane  
Christchurch 8083

Dear Grant

**Building Act exemption: BCN/2017/1413**  
**26 Hemingway Place Spencerville**  
**Re-level**

**Building Act exemption approved**

We have considered your application, under Schedule 1, clause 2(a) of the Building Act 2004, for exemption from the requirement to obtain building consent.

We are satisfied that the completed work is likely to comply with the building code, provided it is carried out in accordance with your proposal. Therefore, your application has been approved.


You can download stamped copies of your proposal documents from [onlineservices.ccc.govt.nz](http://onlineservices.ccc.govt.nz). Please forward copies to the building owner.

**Advice**

- All building work must comply with the Building Act, building code, and all other applicable laws.
- This letter does not provide any approval that may be required, other than that stated.
- This approval is valid if the work is completed within two years of **14 March 2017**.

As the Council does not inspect the work, it is recommended that completion verification documents be supplied to the Council on completion of the work. These will be placed on the file for the property, and may prove beneficial for future enquiries (for example, land information memoranda (LIMs) or property file requests).

Yours sincerely



**Gray Packer**  
Building Consent Officer  
Building Certification & Exemption Team  
Consenting & Compliance Group



## Construction Monitoring No.#1 R00

PROJECT NUMBER: 170050	PROJECT NAME: 26 Hemingway Place
ARCHITECT:	BUILDER: Heritage House Relevellers
TOPIC/ITEM: Scala Penetrometer Test	
ISSUE TO: Lena Mercer	
DATE ATTENDED: 15 March 20110	
TIME ATTENDED: 9:00	
FOREMAN ONSITE: Yes	

Test Pit Number	Blows						Average Penetration Per Blow
	0	2	4	6	8	10	
1	1723	1681	1633	1608	1575	1544	18
2	1624	1576	1534	1501	1469	1435	19
3	1700	1677	1647	1616	1583	1553	15
4	1612	1586	1544	1517	1493	1464	15
5							
6							
7							
8							
9							
10							

### FRONTIER ENGINEERS Ltd



## Construction Monitoring No.#1 R00

ISSUE	Y	N	COMMENTS
AVERAGE PENETRATION PER BLOW	Y		Average penetration per blow does not exceed 20 mm for all pits
300 KPa ACHIEVED		N	
200 KPa ACHIEVED	Y		
150 KPa ACHIEVED	Y		
ISSUE WITH TEST PITS		N	PROBLIMATIC TEST PIT NUMBERS: none  KPa ACHIEVED:
BEARING CAPACITY SATISFACTORY	Y		
REMEDIAL WORK REQUIRED	Y		No remedial work required
FURTHER COMMENTS		N	



## Construction Monitoring No.#1 R00

CHECK OFF			
ISSUE	Y	N	COMMENT
CONSTRUCTION SATISFACTORY	Y		
MORE INFORMATION REQUIRED		N	
SITE PHOTOGRAPHS REQUIRED (TO BE PROVIDED BY BUILDER)		N	
ADDITIONAL SITE VISIT REQUIRED		N	
INSPECTION PASSED	Y		
<p>FURTHER COMMENTS: The dugouts were excavated to a minimum of 0.5 m bgl. The dimensions of the dugout exceeded or mated the 600 mm square pads that Frontier Engineers specified. The contractor may now pour the underpinning pads. Water must be pumped out of all pits prior to pouring concrete.</p>			

**FRONTIER ENGINEERS LTD**

Signed:

Engineer: Alexander Zamshin

Date Issued: 15 March 2017

**FRONTIER ENGINEERS Ltd**

PO Box 79183

Avonhead

Christchurch 8446

P | 0508 FRONTIER (0508 376 684)  
www.frontierengineers.co.nz

E | admin@frontierengineers.co.nz



## Construction Monitoring No.#1 R00

### PHOTOS



### FRONTIER ENGINEERS Ltd

PO Box 79183

Avonhead


Christchurch 8446

P | 0508 FRONTIER (0508 376 684)  
www.frontierengineers.co.nz

E | admin@frontierengineers.co.nz



① - Test pits



Jack Pad Approximate Locations  
SCALE 1:100

Schedule	
	PF1 800x600sq. concrete pad footing at max. 2.0m c/s*

- Notes:
1. Contractor is to confirm all dimensions on site before commencing work
  2. Contractor is to confirm floor levels at each pile or bearer support location to be pocketed.
  3. Pad target depth is 0.5m min. below ground level.
  4. Disconnect and reconnect services as required.
  5. Ensure guttering falls to downpipes after relaying.
  6. Ensure all doors open and close properly.
  7. All work to be carried out in accordance with NZS3904:2011.
  8. Contractor to make all walls plumb.
  9. Cracks in all concrete structures are to be repaired using proprietary product crack bond 'UR321G' supplied by adhesives technology corporation or approved equivalent.
- \*Cracks to be repaired up to a maximum of 5mm and any cracks of more than 5mm are to be repaired by using Helibar or any approved equivalent.  
Product to be installed strictly in accordance with manufacturers instructions
- \* Please note, positions of concrete pads are an approximate location setting

**FRONTIER ENGINEERS**  
CIVIL, STRUCTURAL & REMEDIAL

PO Box 79183 Auckland  
Christchurch 8446

Unit 1, 35 Sheffield Crescent, Burnside 8053

Phone: 03 559 8192  
Free Call: 0800 FRONTIER (0800 378 664)  
Email: admin@frontierengineers.co.nz

This drawing was produced for and remains the property of Frontier Engineers Ltd. This drawing shall not be used in any manner without the prior agreement of Frontier Engineers Ltd. Frontier Engineers Ltd does not accept any responsibility or liability to any third party as a result of the content contained on this drawing. The user of this drawing shall be responsible for obtaining all necessary permissions and approvals from the relevant authorities before commencing any work or making any alterations to the dimensions. All dimensions are in millimetres unless noted otherwise. © Frontier Engineers Limited 2012

Rev	Description	Date	Scale at A3	Project	Project Number
00	Issued for Consent	6/03/2017	1:100	Earthquake Repairs 26 Henningway Place, Spenceville Client: Grant & Lena Mercer	170050
	Design by	6/03/2017		Drawn by	Sheet
	DC			DC	S03
	Approved			Approved	Project Status
					Consent Issue

Drawing Title: Ground Floor Jack Pad Approximate Locations



## Construction Monitoring No.#2 R00

PROJECT NUMBER: 170050	PROJECT NAME: 26 Hemingway Place, Spencerville
ARCHITECT: N/A	CONTRACTOR: Heritage House Relevellers Ltd.
TOPIC/ITEM: Post Level Floor Check	PAGES: 1 + Attachment
ISSUE TO: Lena Mercer <a href="mailto:l.teamo@xtra.co.nz">l.teamo@xtra.co.nz</a> , Lindsay Smith: <a href="mailto:hhr@hotmail.co.nz">hhr@hotmail.co.nz</a>	
DATE ATTENDED: 13 April 2017	
TIME ATTENDED: 2.30pm	

REPORT: Frontier Engineers conducted a site inspection located at 26 Hemingway Place as requested by Heritage House Relevellers.

**Post Level Re-inspection:**

Contractor was instructed onsite to apply 6 mm of floor levelling compound to the floor at the bay window in Family Room. After it was done, the result of the post level survey has met the requirements of MBIE guidance of maximum acceptable slope of 0.5% in between any two points more than 2 meters apart in the dwelling.

**FRONTIER ENGINEERS LTD**


Signed:

Engineer: Alexander Zamshin

Date Issued: 8 May 2017

**FRONTIER ENGINEERS Ltd**






**Legend:**

$\frac{x.x\%}{\rightarrow}$  Indicates floor slope

$\pm x$  Indicates floor level above or below datum

----- Indicates change in floor type

1. Following releveling the floor at each unit shall have
  - i. maximum differential height of 50mm overall
  - ii. 10mm within any room.
  - iii. have a maximum slope of 1:200 (0.5%) between any two points more than 2m apart.
2. All levels shown on this plan are relative to the indicated datum.
3. All floor levels locations and slopes approximate



Rev ID	Description	Date	Scale at A3	Project	Project Number
00	Issued for Consent	21/03/2017	1:100	Earthquake Repairs	170050
			Date 21/02/2017	Address 26 Hemingway Place, Brooklands	
			Design by A2	Client	Sheet
			Drawn by DC	Grant & Lena Mercer	S02
			Approved	Drawing Title	Project Status
			Date	Ground Floor Pre-Level Floor	Consent Issued
					Rev ID 00





Building Code Clause(s)...B1.....

## PRODUCER STATEMENT – PS4 – CONSTRUCTION REVIEW

(Guidance notes on the use of this form are printed on page 2)

ISSUED BY: Frontier Engineers Ltd.....  
(Construction Review Firm)

TO: Grant & Lena Mercer.....  
(Owner/Developer)

TO BE SUPPLIED TO: Christchurch City Council I  
(Building Consent Authority)

IN RESPECT OF: Re-level of existing dwelling only  
(Description of Building Work)

AT: ...26 Hemingway Place, Spencerville, Christchurch 8083.....

..... LOT.....30 ..... DP .....319911..... SO .....

Frontier Engineers Ltd ..has been engaged by Liam Brewer.....  
(Construction Review Firm)

To provide ☐ CM1 ☐ CM2 ☐ CM3 ☐ CM4 ☐ CM5 (Engineering Categories) or ☒ observation as per agreement with owner/developer

or ☐ other ...Structural Design of specific building elements and Supervision.....services  
(Extent of Engagement)

in respect of clause(s) .....B1/VM1 .....of the Building Code for the building work described in

documents relating to Building Consent No. BCN/2017/1413..... and those relating to

Building Consent Amendment(s) Nos. ....issued during the

course of the works. We have sighted these Building Consents and the conditions of attached to them.

Authorised instructions / variations(s) No. ...Record of Inspections letter attached.... (copies attached)

or by the attached Schedule ☐ have been issued during the course of the works.

On by the basis of ☐ this ☒ these review(s) and information supplied by the contractor during the course of the works and on behalf of the firm undertaking this Construction Review, I believe on reasonable grounds that ☒ All ☐ Part only of the building works have been completed in accordance with the relevant requirements of the Building Consent and Building Consent Amendments identified above, with respect to Clause(s) ...B1....of the Building Code.

I also believe on reasonable grounds that the persons who have undertaken this construction review have the necessary competency to do so.

I, Alan Pearson.....am: ☒ CPEng No. ...1024104.....

(Name of Construction Review Professional)

☐ Reg Arch No. ....

I am a Member of : ☒ IPENZ ☐ NZIA and hold the following qualifications: .....B.Eng.....

The Construction Review Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000\*.

The Construction Review Firm is a member of ACENZ : ☐

SIGNED BY Alan Pearson..... ON BEHALF OF Frontier Engineers Ltd.....

Date: ...8 May 2017..... Signature: 

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000\*.

This form is to accompany Forms 6 or 8 of the Building (Form) Regulations 2004 for the issue of a Code Compliance Certificate.



## Construction Monitoring No.#2 R00

PROJECT NUMBER: 170050	PROJECT NAME: 26 Hemingway Place, Spencerville
ARCHITECT: N/A	CONTRACTOR: Heritage House Relevellers Ltd.
TOPIC/ITEM: Post Level Floor Check	PAGES: 1 + Attachment
ISSUE TO: Lena Mercer <a href="mailto:l.teamo@xtra.co.nz">l.teamo@xtra.co.nz</a> , Lindsay Smith: <a href="mailto:hhr@hotmail.co.nz">hhr@hotmail.co.nz</a>	
DATE ATTENDED: 13 April 2017	
TIME ATTENDED: 2.30pm	

REPORT: Frontier Engineers conducted a site inspection located at 26 Hemingway Place as requested by Heritage House Relevellers.

**Post Level Re-inspection:**

Contractor was instructed onsite to apply 6 mm of floor levelling compound to the floor at the bay window in Family Room. After it was done, the result of the post level survey has met the requirements of MBIE guidance of maximum acceptable slope of 0.5% in between any two points more than 2 meters apart in the dwelling.

**FRONTIER ENGINEERS LTD**


Signed:

Engineer: Alexander Zamshin

Date Issued: 8 May 2017

**FRONTIER ENGINEERS Ltd**






**Legend:**

$\frac{x.x\%}{\rightarrow}$	Indicates floor slope
$\pm X$	Indicates floor level above or below datum
-----	Indicates change in floor type

1. Following levelling the floor at each unit shall have
  - i. maximum differential height of 50mm overall
  - ii. 10mm within any room.
  - iii. have a maximum slope of 1:200 (0.5%) between any to points more than 2m apart.
2. All levels shown on this plan are relative to the indicated datum.
3. All floor levels locations and slopes approximate



Rev ID	Description	Date	Scale at A5	Project	Project Number
00	Issued for Consent	21/02/2017	1:100	Earthquake Repairs	170050
			Date 21/02/2017	Address	
			Design by AZ	26 Hemingway Place, Brooklands	Sheet
			Drawn by DC	Client	S02
				Grant & Lena Mercer	Rev ID
			Approved Date	Drawing Title	Project Status
				Ground Floor Pre-Level Floor	Consent Issued



# PRODUCER STATEMENT – PS1 – DESIGN

(Guidance notes on the use of this form are printed on page 2)

ISSUED BY: Frontier Engineers Ltd.....

(Design Firm)

TO: Grant &amp; Lena Mercer

(Owner/Developer)

TO BE SUPPLIED TO: Christchurch City Council.....

(Building Consent Authority)

IN RESPECT OF: Re-level of existing dwelling only.

(Description of Building Work)

AT: 26 Hemingway Place, Spencerville, Christchurch 8083

(Address)

..... LOT 30..... DP 319911 SO .....

We have been engaged by the owner/developer referred to above to provide ... Structural Design of specific building elements and Supervision..... services in respect of the requirements of

(Extent of Engagement)

Clause(s) B1/VM1 ..of the Building Code for

All ☐ or Part only ☒ (as specified in the attachment to this statement), of the proposed building work.

The design carried out by us has been prepared in accordance with:

☒ Compliance Documents issued by the Ministry of Business, Innovation & Employment...B1/VM1 ... ..or

(verification method / acceptable solution)

☐ Alternative solution as per the attached schedule ... ..

The proposed building work covered by this producer statement is described on the drawings titled .....

...Earthquake Repairs, 26 Hemingway Place, Spencerville and numbered 170050 S00-S06.....; together with the specification, and other documents set out in the schedule attached to this statement.

On behalf of the Design Firm, and subject to:

(i) Site verification of the following design assumptions ground as per Geotechnical report by Riley Consultants, dated 4 July 2013, ref.13801/83-A and • Penetrometer test report by Fulton Hogan Canterbury Laboratory, dated 6 August 2002, ref.200/1517/30...

(ii) All proprietary products meeting their performance specification requirements;

I believe on reasonable grounds that a) the building, if constructed in accordance with the drawings, specifications, and other documents provided or listed in the attached schedule, will comply with the relevant provisions of the Building Code and that b), the persons who have undertaken the design have the necessary competency to do so. I also recommend the following level of construction monitoring/observation:

☐ CM1 ☐ CM2 ☐ CM3 ☐ CM4 ☐ CM5 (Engineering Categories) or ☒ as per agreement with owner/developer (Architectural)

I, Alan Pearson ... am:

(Name of Design Professional)

☒ CPEng 1024104#

☐ Reg Arch ..... #

I am a Member of : ☒ IPENZ ☐ NZIA and hold the following qualifications B. Eng

The Design Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000\*.

The Design Firm is a member of ACENZ: ☐

SIGNED BY ...Alan Pearson..... ON BEHALF OF Frontier Engineers

(Design Firm)

Date 06/03/2017 ..... (signature).....

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000\*.

This form is to accompany Form 2 of the Building (Forms) Regulations 2004 for the application of a Building Consent.

THIS FORM AND ITS CONDITIONS ARE COPYRIGHT TO ACENZ, IPENZ AND NZIA



**Memorandum from licensed building practitioner: Certificate of design work**  
**Section 45 and Section 30C, Building Act 2004**

Please fill in the form as fully and correctly as possible.

If there is insufficient room on the form for requested details, please continue on another sheet and attach the additional sheet(s) to this form.

**THE BUILDING**

Street address: 26 Hemingway Place

Suburb: Spencerville

Town/City: Christchurch

Postcode: 8083

**THE OWNER**

Name(s): Grant & Lena Mercer

Mailing address: 2 Riverside Lane

Suburb: Halswell

PO Box/Private Bag:

Town/City: Tai Tapu

Postcode: 7672

Phone number:

Email address: L.Team@xtra.co.nz

**BASIS FOR PROVIDING THIS MEMORANDUM**

I am providing this memorandum in my role as the: Please tick the option that applies (✓)	
<input type="checkbox"/>	<b>sole</b> designer of all of the RBW design outlined in this memorandum – I carried out all of the RBW design myself – no other person will be providing any additional memoranda for the project
<input type="checkbox"/>	<b>lead</b> designer who carried out some of the RBW design myself but also supervised other designers – this memorandum covers their RBW design work as well as mine, and no other person will be providing any additional memoranda for the project
<input type="checkbox"/>	<b>lead</b> designer for all but specific elements of RBW – this memorandum only covers the RBW design work that I carried out or supervised and the other designers will provide their own memoranda relating to their specific RBW design
<input checked="" type="checkbox"/>	<b>specialist</b> designer who carried out specific elements of RBW design work as outlined in this memorandum – other designers will be providing a memorandum covering the remaining RBW design work



## IDENTIFICATION OF DESIGN WORK THAT IS RESTRICTED BUILDING WORK (RBW)

I, Alan Pearson, carried out / supervised the following design work that is restricted building work

### PRIMARY STRUCTURE: B1

Design work that is restricted building work	Description	Carried out/ supervised	Reference to plans and specifications
<i>Tick (✓) if included</i> <i>Cross (X) if excluded</i>	<i>[If appropriate, provide details of the restricted building work]</i>	<i>[Specify whether you carried out this design work or supervised someone else carrying out this design work]</i>	<i>[If appropriate, specify references]</i>

### PRIMARY STRUCTURE: B1

All RBW Design work relating to B1	( x )		( ) Carried out ( ) Supervised	
Foundations and subfloor framing	(✓)	Re-level of existing foundation only	(x) Carried out (✓) Supervised	Refer drawing set from Frontier Engineers 170050
Walls	( x )		( ) Carried out ( ) Supervised	
Roof	( x )		( ) Carried out ( ) Supervised	
Columns and beams	( x )		( ) Carried out ( ) Supervised	
Columns and beams	( x )		( ) Carried out ( ) Supervised	
Other	( x )		( ) Carried out ( ) Supervised	

### EXTERNAL MOISTURE MANAGEMENT SYSTEMS: E2

All RBW design work relating to E2	( x )		( ) Carried out ( ) Supervised	
Damp proofing	( x )		( ) Carried out ( ) Supervised	
Roof cladding or roof cladding system	( x )		( ) Carried out ( ) Supervised	
Ventilation system (for example, subfloor or cavity)	( x )		( ) Carried out ( ) Supervised	
Wall cladding or wall cladding system	( x )		( ) Carried out ( ) Supervised	



Waterproofing	( x )		( ) Carried out ( ) Supervised	
Other	( x )		( ) Carried out ( ) Supervised	

#### **FIRE SAFETY SYSTEMS: C1 – C6**

Emergency warning systems, evacuation and fire service operation systems, suppression or control systems, or other	( x )		( ) Carried out ( ) Supervised	
--	-------	--	-----------------------------------	--

**Note:** The design of fire safety systems is only restricted building work when it involves small-to-medium apartment buildings as defined by the Building (Definition of Restricted Building Work) Order 2011.

**Note:** continue on another page if necessary.



## WAIVERS AND MODIFICATIONS

Waivers or modifications of the building code are required ( x ) Yes (✓) No

If Yes, provide details of the waivers or modifications below:

Clause	Waiver/modification required
<i>[List relevant clause numbers of building code]</i>	<i>[Specify nature of waiver or modification of building code]</i>

**Note:** continue on another page if necessary.

## ISSUED BY

Name: Alan Pearson	LBP or Registration number: 1024104
The practitioner is a:	( x ) Design LBP ( x ) Registered architect (✓) Chartered professional engineer
Design Entity or Company (optional): Frontier Engineers Ltd	
Mailing address (if different from below): PO Box 79183, Avonhead, Christchurch, 8446	
Street address / Registered office: 1/35 Sheffield Crescent	
Suburb: Burnside	Town/City: Christchurch
PO Box/Private Bag:	Postcode: 8053
Phone number:	Mobile: 027 923 7888
After Hours:	Fax:
Email address: admin@frontierengineers.co.nz	Website: www.frontierengineers.co.nz

## DECLARATION

I, Alan Pearson, CP Eng 1024104,  
state that I have applied the skill and care reasonably required of a competent design professional in carrying out or supervising the Restricted Building Work (RBW) described in this form, and that based on this, I also state that the RBW:

- Complies with the building code; or
- Complies with the building code subject to any waiver or modification of the building code recorded on this form.

Signature:   
Date: 6/03/2017





## CONSTRUCTION MONITORING SCHEDULE

**JOB LOCATION: 26 HEMINGWAY PLACE, SPENCERVILLE, CHRISTCHURCH 8083**

**FILE NUMBER: 170050**

Construction monitoring site visits relating to compliance with the building consent documentation and for verification of design assumptions are required as follows:

	TIME	NUMBER OF VISITS
1	Base of excavation pads	1-2
2	Post floor level survey	1

A site inspection report will be sent within 24hrs after inspection to the Client. A Producer Statement 4, Construction Review, could be issued once the above monitoring site visits have been completed. It is the Clients responsibility to notify the Engineer to enable the above site visits to be completed.

A handwritten signature in black ink, appearing to read "Alex", with a long horizontal stroke extending to the right.

Alexander Zamshin  
Frontier Engineers Ltd

**FRONTIER ENGINEERS Ltd**

P.O. Box 79183

Christchurch

Christchurch 8140

P 0508 1834444 (0508 376 684)

www.frontierengineers.co.nz

E admin@frontierengineers.co.nz



# Design Feature Report

## Re-level of Existing Residential Building

Location 26 Hemingway Place, Spencerville, Christchurch 8083  
Client Grant & Lena Mercer  
  
Job No: 170050  
Issue Date: 06-March-17  
Revision: 00

**FRONTIER ENGINEERS Ltd**

File Ref: 29181

Assignment

Client Ref: 16-8446

Frontier Engineers 0309 376 684

[www.frontierengineers.co.nz](http://www.frontierengineers.co.nz)

Frontier Engineers Ltd is a registered company in New Zealand





## Document Quality Assurance Record

Document prepared by:

**FRONTIER ENGINEERS LTD**

1/35 Sheffield Crescent  
Burnside  
Christchurch 8053

PO Box 79183  
Avonhead  
Christchurch 8446  
New Zealand

P| 0508 376 684

E| [admin@frontierengineers.co.nz](mailto:admin@frontierengineers.co.nz)

W| [frontierengineers.co.nz](http://frontierengineers.co.nz)




© Frontier Engineers Limited. All rights reserved.

Frontier Engineers has prepared this document for the sole use of the Client and for a specific purpose, each as expressly stated in the document. Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.

Frontier Engineers undertakes no duty, nor accepts any responsibility, to any third party who may rely upon or use this document. Using the documents or data for any purpose not agreed to in writing by Frontier Engineers Ltd.

## Document Transmittal

Rev	Date	Revision Details/Status	Author	Reviewer
00	06 March 2017	Issued to Client	Alexander Zamshin	Stefan Pienaar

<b>Author Signature:</b>		<b>Reviewer Signature:</b>		<b>Approver Signature:</b>	
<b>Name:</b>	Alexander Zamshin	<b>Name:</b>	Stefan Pienaar	<b>Name:</b>	Alan Pearson
<b>Title</b>	Engineer	<b>Title</b>	Eng. Manager	<b>Title</b>	CPEng



### **Introduction:**

The existing Residential Building was damaged in the Canterbury Earthquake Sequence (CES) including differential settlement. The structural integrity of the dwelling is satisfactory; however, re-levelling is required to amend differential settlement of more than 50 mm and floor slopes that exceed 1:200.

### **Scope of work:**

Frontier Engineers has been engaged by Grant & Lena Mercer to prepare technical documentation and certification for the re-level of the existing Residential only:

- Technical drawings of the proposed repairs
- Producer Statement 1
- Memorandum of Works
- Construction Monitoring Schedule
- Site inspection reports
- Producer Statement 4

### **Exclusions:**

- All repair works other than re-levelling or direct repairs to the foundation system
- Strengthening of the Residential Building in anyway
- Future proofing of the Residential Building in anyway
- Any work above foundation level
- The works are assumed to be carried out under a Consent Exemption, and on this basis we refer to the Guidance for Building Work that Does Not Require a Building Consent (Building Act 2004) issued by the MBIE regarding section 42A of the Building Act,

*(a) the building work complies with the building code to the extent required by this Act:*

*(b) after the building work is completed, the building:*

*(i) if it complied with the building code immediately before the building work began, continues to comply with the building code; or*

*(ii) if it did not comply with the building code immediately before the building work began, continues to comply at least to the same extent as it did then comply.*

I.e. where specific parts of the building are modified our intention is to ensure that the building will function structurally to at least the same extent as it did prior to repairs, but may not necessarily be brought up to the current building code requirements.

### **Reference:**

- Updated Geotechnical Report by Riley Consultants, dated 3 March 2017, ref.13801/83-B
- Residential Engineering Evaluation Report by Frontier Engineers, dated 22 February 2017, ref.170050
- NZS3101 Concrete Structures
- MBIE Guidance





### **Building Summary:**

Foundation Type:	Perimeter reinforced concrete foundation and unreinforced concrete slab
Structural Framing:	Timber framing
No. of Storeys:	1
Wall Cladding Weight:	Heavy – clay brick veneer
Roof Cladding Weight:	Light – pressed steel
Technical Category:	TC3, TC2 according to site specific investigation by Riley Consultants
200kPa Bearing:	@ 0.45mbgl
Target Pad Depth:	0.5mbgl
Minimum Pad Size:	600mm x 600mm
Typical Pad Spacing:	2.0m
Max Pad Spacing:	2.0m

### **Design Philosophy:**

#### ***Re-levelling***

Mechanical jacking of the concrete structures using portable jacks and excavations at the lifting locations. The lifting locations are considered temporary until the dwelling is reinstated to its pre-earthquake condition. Any additional material or concrete works that remain on site are not considered to decrease any future performance, nor is it to be relied on as betterment or considered to increase performance during future earthquake events.

It is common for further cracking to occur as a result of re-levelling processes, which may require additional repairs, and needs to be completed prior to completion of works.

The concrete foundations have been assessed based on minimum steel design, but an additional design check has been made to consider the consequences of no reinforcement, and the concrete required to span using the flexure tensile capacity only.

As part of this assessment we have not considered the permanent lateral stretch of the building, or any other complications that may arise from re-levelling the building. Additionally, we do not know the condition of the dwelling prior to re-levelling, or the differential settlement of the foundations prior to the earthquake events. For this reason it may not be practical to re-level the foundations where historical or long term settlement has previously occurred.

As the loading on the re-levelling pads is temporary, we have considered a safety factor of 2 for the ultimate bearing capacity.





---

## **APPENDIX – Design calculations**

- Foundation Loading
- Re-levelling pads
- Concrete beam span
- Concrete slab span



# STANDARD CALCULATION TEMPLATE

**JOB NAME:** 26 Hemingway Place

**JOB NO.:** 170050

**ENGINEER:** A Zamshin

**DATE:** 17/02/2017

## **JOB DESCRIPTION:**

Re-levelling of existing building

- Perimeter reinforced concrete foundation
- Unreinforced concrete floor slab
- Single storey building
- Heavy clay brick veneer cladding
- Light steel sheet roof cladding



## STANDARD NOTATION AND DEFINITIONS

### ACRONYMS

#### Foundations

SF1	Strip Footing
PF1	Pad Footing
EB1	Edge Beam
IB1	Internal Beam
IR1	Internal Rib
WP	Weld Plate
SCJ	Saw Cut Joint
CJ1	Control Joint
CKJ	Connolly Key Joint

#### Floor

FB1	Floor Bearer
FJ1	Floor Joist
SP1	Stringer Plate
FP1	Pile
VCJ	Vertical Control Joint

#### Wall

EW1	External Wall
IW1	Internal Wall
FW1	Fire Wall
L1	Lintel
C1	Column

#### Roof

R1	Rafter
P1	Purlins
VB	Veranda Beam
RB1	Roof Bracing
B1	Beam (steel or timber)
B1	Ridge Beam

#### Other

TC#	Technical Category according to CERA for liquefaction risk
NZS	New Zealand Standard
MBIE	Ministry of Building, Innovation and Employment

### DEFINITIONS

Along	Along the ridge line (Longitudinal)
Across	Across the ridge line (Transverse)

NAME: 26 Hemingway Place  
DATE: 17/02/2017

SHEET No. 2  
REF: 170050



## NZS 1170.0 - DESIGN ACTIONS - PART 0: GENERAL PRINCIPALS

REF

### 3.3 IMPORTANCE LEVEL

T 3.1	Structure designed for importance level	2
T3.1	Consequence of failure	ORDINARY
T3.1	Description: Medium consequence for loss of human life, or considerable economic, social or environmental consequences	
T3.1	Comment: Normal structures and structures not falling into other levels	
T3.2	Importance level description: Normal structures and structures not in other importance levels	

### 3.4 ANNUAL PROBABILITY OF EXCEEDENCE

T3.3	Design working life	< 6 months
------	---------------------	------------

Design annual probability of exceedence

Wind	ULS	1/100
Snow	ULS	1/50
Earthquake	ULS	1/100
SLS1	Service	1/25
SLS2	Service	-

- 3.4.2** *SLS1 — the structure and the non-structural components do not require repair after the SLS1 earthquake, snow or wind event*
- 3.4.2** *SLS2—the structure maintains operational continuity after the SLS2 earthquake (Importance L4 only)*

**NAME: 26 Hemingway Place**  
**DATE: 17/02/2017**

**SHEET No. 3**  
**REF: 170050**



## NZS 1170.1 - PART 1: PERMANENT, IMPOSED AND OTHER LOADS

REF

### 4.2 COMBINATION FACTORS

G	Dead Loads (Permanent)
Q	Live Loads (Imposed)
$\psi$	load factor

#### 4.2.2 Design Combinations for Strength

1.35G	Dominant Permanent Action
1.2G + 1.5Q	Permanent and Imposed Action
1.2G + $W_u$ (Down) + $\psi_c Q$	Permanent, Wind and Imposed Action
0.9G + $W_u$ (Up)	Permanent, Wind Reversal
1.2G + $S_u$ + $\psi_c Q$	Permanent, Snow and Imposed
1.0G + $E_u$ + $\psi_c Q$	Earthquake ULS

T4.1	$\psi_c =$	0.4 for roofs 0.6 storage
	$S_u =$	0.9kPa Minimum for Christchurch

#### 4.3 Design Combinations for Serviceability

G + $\psi_c Q$	Permanent and Imposed Action
$E_s$	Earthquake SLS1

### S5 METHOD OF ANALYSIS

STATIC  
ELASTIC

NAME: 26 Hemingway Place  
DATE: 17/02/2017

SHEET No. 4  
REF: 170050



**NZS 1170.1 - PART 1: PERMANENT, IMPOSED AND OTHER LOADS**  
**NZS 3604 - TIMBER FRAMED BUILDINGS - DESIGN LOADING**

**REF**

**3604 Live Loading (Q)**

<b>T1.2</b>	Dwelling Floor Live Load	1.5	kPa	A1
	Dwelling Balconies/Decks	2.0	kPa	A1
	Dwelling Bathrooms	2.0	kPa	A2
	Communal Kitchens	3.0	kPa	A2
	Offices and Work Areas	3.0	kPa	B
	Dwelling Roof Load	0.25	kPa	

**Dead Loading (G) - including timber framing**

<b>Branz</b>	Light Roof	0.40	kPa		
<b>3604</b>	Heavy Roof	0.85	kPa		
	Light Wall	1.20	kN/m	H=	2.4
	Medium Wall	2.80	kN/m	H=	2.4
	Heavy Wall	6.40	kN/m	H=	2.4
	190 Block Wall	8.40	kN/m	H=	2.4
	190 Block Wall	11.40	kN/m	H=	2.4
	Timber Subfloor	0.40	kPa		
	Suspended Timber Floor	0.40	kPa		

**Material Densities**

$\mu_{\text{Concrete}}$	25.0	kN/m <sup>3</sup>
$\mu_{\text{Timber}}$	6.0	kN/m <sup>3</sup>
$\mu_{\text{Steel}}$	72.5	kN/m <sup>3</sup>

**NAME: 26 Hemingway Place**  
**DATE: 17/02/2017**

**SHEET No. 5**  
**REF: 170050**



## NZS 3604 - TIMBER FRAMED BUILDINGS - DURABILITY

REF

3604 Exposure Zone for Christchurch

C

F4.2



Exposure Zones



NOTE – Zone D includes all offshore islands, the area within 500 m of the coastline of New Zealand, and those areas shown in white. The map shall be read in conjunction with 4.2.2.

T4.1

ZONES B AND C	Treated timber pile connections more than 600 mm from the ground and all subfloor connections	Subfloors vented 7000 mm <sup>2</sup> or less	SHELTERED <sup>®</sup>	Hot-dipped galvanized steel <sup>®</sup>
		Subfloors vented more than 7000 mm <sup>2</sup>	EXPOSED	Type 304 stainless steel <sup>®</sup>
	Treated timber pile connections within 600 mm of the ground	SHELTERED <sup>®</sup> AND EXPOSED		Type 304 stainless steel <sup>®</sup>
	All other structural fixings, except fabricated brackets <sup>®</sup>	SHELTERED <sup>®</sup>		Hot-dipped galvanized steel <sup>®</sup>
ZONE D	All structural fixings	EXPOSED		Type 304 stainless steel <sup>®</sup>
		SHELTERED <sup>®</sup> AND EXPOSED		Type 304 stainless steel <sup>®</sup>

NAME: 26 Hemingway Place  
DATE: 17/02/2017

SHEET No. 6  
REF: 170050



**SPECIFIC ENGINEERING DESIGN - RE-LEVELLING PAD****MBIE - Mechanical Re-levelling of Concrete Perimeter Beam****For Single Storey Area**

Roof Load width	<b>8.0</b>	m	(Worst Case)
First Floor Load Width	<b>0.0</b>	m	
Ground Floor Load With	<b>1.0</b>	m	

<b>Dead Loads</b>		<b>Mass</b>	<b>Load</b>
Roof	<b>Light</b>	0.40	3.20
First Floor Wall	<b>Nil</b>	0.00	0.00
First Floor	<b>Nil</b>	0.00	0.00
Ground Floor Wall	<b>Heavy</b>	2.20	5.28
Ground Floor	<b>Heavy</b>	2.50	2.50
Foundation	<b>Heavy</b>	-	4.50
		<b>Total</b>	<b>15.48</b>

**Live Load**

Roof	<b>Ped Traffic</b>	0.25	2.00
First Floor	<b>Nil</b>	0.00	0.00
Ground Floor	<b>Residential</b>	1.50	1.50
		<b>Total</b>	<b>3.50</b>

<b>Load Case</b>	<b>G + 0.3Q</b>	<b>16.53</b>
------------------	-----------------	--------------

Max Spacing of Jack Points	2.00	m
Design Lift Load	33.06	kN
Min Pad Size	<b>0.6 x 0.6</b>	m
Min Pad Area	0.36	m <sup>2</sup>
Max Bearing Load	91.83	kPa

Min Soil UBC	<b>200</b>	kPa	
Design Soil SBC	100	kPa	L.o.S = 2
<b>Capacity Ratio</b>	<b>1.1</b>		

**NAME: 26 Hemingway Place****DATE: 17/02/2017****SHEET No. 7****REF: 170050**



**SPECIFIC ENGINEERING DESIGN - RE-LEVELLING PAD**

Check temporary span of concrete perimeter beam between relevealling pads

<b>Beam Type</b>	<b>Perimeter Beam</b>		
Assumed Size	400Dx240W		
Assumed No. Reo Bars	1		
Assumed Size of Reo Bars	<b>D16</b>	201.1	mm <sup>2</sup>
Assumed grade of Reo	<b>270</b>		
Assumed concrete strength	<b>20</b>		
<i>For conservative design assumed simply supported conditions</i>			
Design Load	16.53	kN/m	
Design Span	2.00	m	
Design Moment	8.27	kN.m	$wL^2/8$
Design Shear	16.5	kN	$wL/2$
Beam Check 1 - Moment	14.30	kN.m	$\phi Mb = \phi As f_y (d-a/2)$
<b>Capacity Ratio</b>	<b>1.7</b>		
Beam Check 2 - Shear	29.2	kN	$0.08 \sqrt{f'_c} b d$
<b>Capacity Ratio</b>	<b>1.8</b>		NZS 3101 EQ 9-5

**NAME: 26 Hemingway Place**  
**DATE: 17/02/2017**

**SHEET No. 8**  
**REF: 170050**



check slab (temporary span 1 m)

$$d = 100 \text{ mm}, \quad b = 1000 \text{ mm}$$

$$f'_c = 20 \text{ MPa}$$

$$\text{Direct tensile strength: } 0.36 \sqrt{f'_c} = 1.6 \text{ MPa}$$

$$Z = (0.5d)^2 \times 1000 / 6 = 416.7 \times 10^3 \text{ mm}^3$$

$$\phi = 0.85 \quad \text{cl. 2.3.2.2 NZS 3101.1}$$

$$\phi M_n = 0.85 \times 416.7 \times 1.6 = 0.57 \text{ kNm}$$

$$L = 1.0 \text{ m}$$

$$\text{Load: } 1.0 \text{ m} \times 0.1 \text{ m} \times 24 \text{ kN} = 2.4 \text{ kN/m (self-weight)}$$

$$M^* = 2.4 \text{ kN/m} \times 1.0^2 / 8 = 0.3 \text{ kNm (only)}$$

OK



PO Box 79183  
Avonhead  
Christchurch 8446

P. (03) 359 9192 or (0508) 376 664  
E. admin@frontierengineers.co.nz  
W. www.frontierengineers.co.nz

Project

Address

Title

26 Hemingway Pl

Designed

Scale @ A4

Date

Job No

Sheet No

AZ

17/02/2017

9



**AUCKLAND**

4 Fred Thomas Drive, Takapuna, Auckland 0622  
 PO Box 100257, North Shore, Auckland 0745  
 +64 9 489 7872  
 ariey@riley.co.nz  
 www.riley.co.nz

**CHRISTCHURCH**

22 Moorhouse Avenue, Addington, Christchurch 8011  
 PO Box 4355, Christchurch 8140  
 +64 3 379 4402  
 rlinchich@riley.co.nz

**WAIKATO**

19 Reels Crescent, Waiuku 9305  
 +64 3 376 3542  
 rileywka@riley.co.nz



Ms Lena Mercer  
 26 Hemingway Place  
 Brooklands  
 Christchurch 8083

3 March 2017

Our Ref: 13801/83-B

Dear Ms Mercer

## **UPDATED GEOTECHNICAL INVESTIGATION REPORT 26 HEMINGWAY PLACE, BROOKLANDS**

### **1.0 Introduction**

This report, prepared by Riley Consultants Ltd (RILEY), is an update of the original Geotechnical Investigation Report (RILEY Ref: 13801/83-A, dated 4 July 2013), and presents the findings of the geotechnical investigation undertaken at 26 Hemingway Place, Brooklands, following damage sustained to the property from the 2010/2011 Canterbury earthquake events.

At the time of writing the original report, RILEY understood the dwelling had been assessed as a foundation rebuild. However, a residential engineering evaluation report and repair methodology for 26 Hemingway Place was prepared for the homeowner by Frontier Engineers in February 2017, which indicates that a foundation repair is suitable for the dwelling. This updated report includes comments on foundation repair options for the dwelling, as well as foundation rebuild options, and supersedes our previous report (RILEY Ref: 13801/83-A).

The area in which the property is located is designated by the Ministry of Building, Innovation, and Employment (MBIE) as Technical Category 3 (TC3) based, in part, on the potential for future liquefaction causing moderate to significant land deformations.

### **2.0 Scope of Work**

The original scope of geotechnical work undertaken by RILEY, and agreed with AA Insurance Ltd, was to provide a geotechnical report covering:

- An assessment of shaking versus land attributed damage.
- An assessment of the liquefaction susceptibility of the site based on regional data from the Canterbury Geotechnical Database (CGDb), with confirmation of subsurface profile provided by two dynamic probe-heavy (DPH) tests to a target depth of 15m, and hand auger (HA) and Scala penetrometer (Scala) testing to a target depth of 3m.
- A review of the CGDb to assess what ground conditions are likely to be present at greater depths based on available local data.
- A review of the likely peak ground accelerations (PGAs) during the September 2010, February, June and December 2011 earthquakes in Canterbury.
- Confirmation (or otherwise) that superficial soils meet MBIE Guidelines and NZS3604 for standard shallow foundations.



- Provide advice on potential foundation rebuild options consistent with the MBIE Guidance Document for Repairing and Rebuilding Houses affected by the Canterbury Earthquakes (Version 3, dated December 2012).

RILEY was subsequently requested by the homeowner, via email and short form agreement, dated 21 February 2017, to provide:

- Geotechnical advice to assist assessment of suitable repair options.

Development of a construction methodology and design of any remedial measures is beyond the scope of this report.

### 3.0 Regional Geology

The published geological map of the area (Qmap Greater Christchurch, Institute of Geological and Nuclear Sciences, 1:250,000 Geological Map 16, 2008) indicates that the property is underlain by sand of dunes and beaches.

A review of the New Zealand Geotechnical Database (NZGDb)(which supersedes the CGDb) indicates there are 11 cone penetrometer tests (CPTs) within 30m of the property boundary (to final depths of up to 20m), and one machine borehole located 40m north-west of the property boundary (drilled to 11m depth). A review of the ECan wells database also indicated data was available from three wells (south of the property) within 300m of the property.

A review of the borehole log available from the machine borehole and CPT tests (detailed above) indicates that the anticipated geological profile in this area comprises sand of the Christchurch Formation to 20+m depth. Based on the ECan deep well logs, the sand is expected to be present to approximately 28m depth, underlain by a thin layer of peat and gravel to approximately 34+m depth.

Groundwater was recorded at 1.5m depth in the machine borehole. The NZGDb map of median water table elevation indicates groundwater is between 1m and 2m depth.

### 4.0 Visual Inspection and Observed Foundation Damage

A visual inspection of the property was undertaken prior to the field investigations on 3 June 2013. The dwelling is a single-storey, timber-framed house with brick veneer cladding and a metal tiled roof. The dwelling is founded on a Type C foundation (concrete slab-on-grade) as described in the MBIE Guidelines. The property is located on generally level ground with no obvious significant waterways within 200m.

Damage to the dwelling as a result of the Canterbury earthquake sequence, as reported by others via the Building Inspection Report (BIR), includes differential settlement (tilt) and cracking of the concrete floor. The floor level survey in the BIR document is dated 18 February 2011, prior to the main February 2011 earthquake event. The greatest differential settlement recorded on this floor level survey is 70mm over approximately 17m (with a floor slope 0.42%). The concrete floor slab is reported to be tilting towards the north-eastern corner of the dwelling. The BIR indicates that the foundation had three cracks however, the size of the cracks was not recorded in the BIR. The floor slab was not inspected at the site of the original survey due to floor coverings.



Since the issue of our original report, an additional floor level survey has been undertaken by Frontier Engineers in February 2017. This survey shows that the maximum floor level difference recorded across the dwelling is 79mm, sloping towards the north-eastern corner of the dwelling. Cracks have been mapped in the floor slab; these range between hairline in width to a maximum crack width of 1.9mm.

A walkover of the grounds surrounding the dwelling (undertaken in June 2013) did not indicate any obvious evidence of ejected sand on the site due to liquefaction. A review of aerial photographs following the Canterbury earthquake events indicated moderate amounts of ejecta present in the area surrounding the property following the September 2010 and February 2011 events. The EQC aerial photographs indicate moderate to severe liquefaction was observed on-site, and in the surrounding area, following the September 2010 earthquake. Minor observed liquefaction was recorded following the February 2011 earthquake.

No obvious evidence of lateral stretching was observed during the walkover inspection. At the time of preparation of the 2013 report, no ground cracking was reported on the database. However, the map of observed ground crack locations now indicates that there are three ground cracks mapped on-site; two of the cracks are indicated to be <50mm wide and occurred prior to the February 2011 event. The third crack was mapped after the February 2011 event and is indicated to be <10mm wide.

## **5.0 Ground Conditions**

### **5.1 Cone Penetrometer Test Investigation**

A review of NZGDb indicates CPT 14658 is the closest CPT to the site boundary, located 7m to the north-west of the property boundary. Inferred soil conditions from the CPT test indicated topsoil underlain by sand to 10m depth; the full extent of the test.

### **5.2 Dynamic Probe Tests**

Due to access constraints to the rear of the property the DPH test was utilised to investigate the soil strength profile at depth, assess consistency of material strength across the site and assist liquefaction assessment. The two DPH tests were completed on 3 June 2013. The probes were undertaken at the northern and southern end of the property, as shown on the attached plan. In summary, the subsurface soils across the two testing locations indicated generally similar soil strengths.

Data from both DPH1 and DPH2 indicate that predominantly loose ( $N_{1(60)}$  between 4 to 10) soil is present to 1.5m depth, grading to predominantly medium dense ( $N_{1(60)}$  between 10 to 30) soil to 7.5m depth. Between 7.5m and 9.5m depth, dense ( $N_{1(60)}$  between 30 to 50) soil was encountered before grading to very dense ( $N_{1(60)} > 50$ ) soil until 12.5m and 12.0m depth in DPH1 and DPH2, respectively (final depth).

A comparison of the DPH and the CPTs indicates a generally similar soil strength profile suggesting consistency of soil conditions across the site.



### 5.3 Hand Auger Boreholes

In addition to the deep investigations, two HA boreholes were drilled at the site to assess the near surface materials and their strength. Scala testing was carried out in each HA borehole as they were progressed. HA1 was located adjacent to DPH1 at the northern end of the property while HA2 was located adjacent to DPH2 at the southern end of the property. All HA boreholes were completed by RILEY on 3 June 2013 and logged in general accordance with the NZGS guidelines (December 2005).

The materials encountered in HA1 and HA2 comprised topsoil to 0.25m depth underlain by fill material to 0.45m depth (in HA1 only). Beneath the topsoil and fill material, fine to coarse sand was encountered to 1.4m and 1.75m depth in HA1 and HA2, respectively (final depths). Both HA boreholes were terminated prematurely due to collapse of saturated sand.

Groundwater was encountered in both HA boreholes between 1.2m and 1.3m depth.

The Scala tests carried out in HA1 and HA2 were terminated at 3.2m and 3.0m depth, respectively. Scala testing indicated that a geotechnical ultimate bearing capacity of 200kPa is not available above 0.45m depth, with 300kPa geotechnical ultimate bearing capacity consistently available below 1.4m depth.

## 6.0 Geotechnical Considerations

### 6.1 Seismic Design Parameters

The preliminary design PGA for the site, based on the latest MBIE Guidelines (Issue 7), are summarised in Table 1. Since the time of preparation of the original Geotechnical Investigation Report for 26 Hemingway Place, a new Serviceability Limit State (SLS) condition has been proposed. The values in Table 1 are based on Class D soil type (deep or soft soils), which is considered appropriate for the site, and a design life of 50-years for the structure.

**Table 1: MBIE Recommended PGA Values for Geotechnical Design in Canterbury**

Importance Level <sup>(1)</sup> = 2	SLS <sub>1</sub> <sup>(2)</sup>	SLS <sub>2</sub> <sup>(2)</sup>	ULS <sup>(3)</sup>
Moment Magnitude (M <sub>w</sub> )	7.5	6.0	7.5
Annual Probability of Exceedance	1/25	1/25	1/500
Peak Ground Acceleration	0.13g	0.19g	0.35g

Notes:

- 1) Structure has been designated in terms of AS/NZS 1170 as Importance Level 2 structures. These include normal structures, and structures not included in other importance levels.
- 2) As of latest guidance; two SLS cases must be considered.
- 3) ULS – Ultimate Limit State.

Prior to the Darfield earthquake (September 2010), the design PGA for residential buildings in Christchurch was approximately 0.25g for ULS, deep soil sites with a 50-year design life. The design SLS level was 0.11g.

Review of the conditional PGA contours from the NZGDb indicates that during the Canterbury earthquake sequence, the site may have been subject to levels of shaking in excess of the prior ULS. PGA levels for the other earthquake events suggest shaking levels were in excess of current SLS design levels.



## 6.2 Liquefaction Risk and Assessment

The property at 26 Hemingway Place has been zoned as TC3, which is assessed as having a moderate to significant risk of land damage in future significant earthquakes.

Liquefaction typically occurs in recent (i.e. less than 10,000 years old), normally consolidated silt and sand beneath groundwater and is dependent on material density, grain size and soil composition.

Liquefaction analysis has been undertaken on two CPTs, both located within 20m of the property boundary. The assessment was undertaken in accordance with the MBIE Guidelines at the time of writing the original report, using the Zhang, Robertson and Brachman 2002 method, with a 7.5M<sub>w</sub> earthquake. A groundwater level of 1m depth was assumed for the assessment. The results of the analysis undertaken for our previous report are shown in Table 2

**Table 2: Estimated Liquefaction Induced Settlement**

Test	Event	PGA	Settlement (Total) <sup>(1)</sup>	Differential Settlement <sup>(2)</sup>	Index Settlement <sup>(3)</sup>
CPT 14658-CGDb	SLS	0.13g	5mm	2-3mm	5mm
	ULS	0.35g	55mm	25-35mm	55mm
CPT 9479-CGDb	SLS	0.13g	15mm	7-10mm	5mm
	ULS	0.35g	200mm	100-133mm	90mm

Notes:

- 1) Settlements obtained through a liquefaction analysis using data obtained from the CPT.
- 2) Differential settlement is calculated as 1/2 to 2/3 of the total settlement values.
- 3) Index settlement is the estimated vertical settlement in the top 10m of soil under SLS and ULS loadings.

Results of the liquefaction analysis indicate index settlements representative of TC2 type land. Liquefaction analysis was also undertaken using equivalent SPT N data obtained from the DPH testing. This analysis produced settlement values generally consistent with the figures presented in Table 2 above.

## 6.3 Lateral Spread

Lateral spreading occurs where differences in ground level or soil consistency allow liquefied soils to flow laterally. Lateral movement is also possible in an earthquake event due to a lack of lateral support. Site observations do not indicate a significant lateral spreading hazard at this site and the property is located on generally level ground with no obvious significant waterways nearby. However, the map of observed ground crack locations indicates that there are three ground cracks mapped on-site; two of the cracks are indicated to be <50mm wide and occurred prior to the February 2011 event. The third crack was mapped after the February 2011 event and is indicated to be <10mm wide.

The BIR document makes reference to cracks being present in the foundation. The floor slab was not inspected at the time of the inspection due to floor coverings. The Frontier Engineers investigation indicates that there are cracks in the floor slab ranging from hairline to 1.9mm in width.

On the basis of the above information, lateral stretch potential of the ground across the building footprint is considered to be less than 200mm, indicating the threat of lateral stretch is in the minor to moderate category (Table 12.4, MBIE Guidelines).



## 6.4 Damage Mechanism

Based on the floor level surveys indicating very little change in the floor level differential settlements between the September 2010 and the subsequent earthquake events, it is considered that the damage to the dwelling is mainly attributable to shaking induced damage to the structure. Some of the damage observed may be a result of shaking induced consolidation of the shallow soil about the water table, and liquefaction induced settlement.

It should be noted that due to ground conditions at the site comprising sand, and the PGAs that have been experienced at the site, it is considered that the shaking will have densified the shallow soils at the site.

## 7.0 Foundation Recommendations

As a result of the Canterbury earthquake sequence, the dwelling at 26 Hemingway Place has suffered differential settlement of 79mm across the foundation slab. Cracks ranging from hairline to 1.9mm in width were observed by Frontier Engineers during their recent site visit. Based on the damage observed, it is considered that the foundation can be repaired. Foundation repair and rebuild options are presented below.

### 7.1 Foundation Repair

Table 2.3 of the MBIE Guidelines indicates that the floor level difference recorded in the dwelling is within the MBIE Guidelines criteria for a foundation re-level. The MBIE Guidelines state that a geotechnical ultimate bearing capacity of greater than 300kPa is required to undertake re-levelling without specific design. Investigations at the site have not identified soils providing a 300kPa geotechnical ultimate bearing capacity within the shallow soils, therefore, specific engineered design will be required for the re-levelling work to be undertaken. A geotechnical ultimate bearing capacity of 200kPa was consistently recorded at 0.45m across the site.

Reference to Table 3 should be made for foundation repair options at the property.

Table 3: Foundation Repair Options

Foundation Type	Repair Options	MBIE Guidelines Reference
Concrete slab-on-grade	Foundation re-level.	Appendix A1.1.3
	Foundation crack repair (based on aperture).	Appendix A4.4
	Fill voids below concrete slab foundation.	The filling of voids or cavities below the concrete slabs can be carried out with a flowable grout or concrete.

Input from a geotechnical engineer is recommended in the development of a re-levelling strategy. Bearing capacities should be confirmed by a geotechnical engineer once the details of the proposed repair methodology are known.

It should be noted that re-levelling the property will not prevent liquefaction induced settlement of the dwelling in a future earthquake event.

### 7.2 Foundation Rebuild

Should the foundation be considered a rebuild, it is considered that the replacement foundation will comprise a concrete floor.



### **Option A: Deep Pile Foundation**

The results from the liquefaction analysis and the strength profiles obtained from both DPH and CPTs indicate that a suitable piling layer may be present at approximately 10m depth. Notwithstanding this, due to the considerable depth and availability of more suitable economic foundation options (see below), this option was not considered further.

### **Option B: Enhanced Concrete Slab with Hardfill Raft**

The preferred foundation type is to utilise a "hybrid TC2/TC3 foundation" as outlined in the MBIE Guidance document (Section 15.4.6, page 15.44). The SLS settlements less than 50mm indicate that amenity requirements at SLS would be satisfied by the installation of a TC2 foundation, but the level of foundation damage might be unacceptable during an ULS earthquake. A foundation more robust than a TC2 foundation alone is considered more appropriate. The hybrid TC2/TC3 foundation recommended in the MBIE Guidance document consists of a minimum 800mm thick geogrid reinforced gravel raft (i.e. TC2 Option 1), in combination with an overlying 300 to 400mm thick enhanced concrete slab (TC2 Option 2), or waffle-type slab (i.e. TC2 Option 4).

A geotechnical ultimate bearing capacity of 200kPa is available below 0.45m of soil (below the fill), for the gravel raft to be founded on, a requirement as outlined by the MBIE Guidelines.

### **Option C: Re-levellable Concrete Surface Structure**

Another foundation system that could be applicable to this site is a re-levellable concrete surface structure similar to concepts from Section 15.4.8, Part C of the MBIE Guidelines. This type of foundation system is suitable where less than 100mm SLS settlement is expected.

If this option is pursued, it is recommended to implement an excavate and replace geogrid reinforced raft extending to approximately 0.5m depth to where a geotechnical ultimate bearing capacity of 200kPa is available.

A comparison of the relative costs of the foundation systems described above would be recommended in conjunction with the associated future risks for each option in order to aid in the decision of the final foundation design.

Consideration should also be given to the provision of lightweight materials, particularly for roof and wall cladding. These lightweight materials will reduce inertial loading on foundations and can reduce settlement in future seismic events.

It is recommended that the composition and strength of the materials is confirmed at the time of the foundation replacement. The strength of the materials located across the site or directly beneath the existing dwelling may vary from those indicated in the HA boreholes and probe tests.

## **8.0 Limitation**

This report has been prepared solely for the benefit of Ms Lena Mercer as our client with respect to the brief. The reliance by other parties on the information or opinions contained in the report shall, without our prior review and agreement in writing, be at such parties' sole risk.

Recommendations and opinions in this report are based on data from limited test positions. The nature and continuity of subsoil conditions away from the test positions are inferred, and it must be appreciated that actual conditions could vary considerably from the assumed model.



During excavation and construction, the site should be examined by an engineer or engineering geologist competent to judge whether the exposed subsoils are compatible with the inferred conditions on which the report has been based. It is possible that the nature of the exposed subsoils may require further investigation and the modification of the design based upon this report.

Riley Consultants Ltd would be pleased to provide this service to Ms Lena Mercer and believes the project would benefit from such continuity. In any event, it is essential Riley Consultants Ltd is contacted if there is any variation in subsoil conditions from those described in the report as it may affect the design parameters recommended in the report.

Yours faithfully

**RILEY CONSULTANTS LTD**

Prepared by:



Jen Kelly  
**Senior Engineering Geologist**

Reviewed by:



Leah King  
**Senior Engineering Geologist**

Approved for issue by:



Scott Vaughan  
**Managing Director, CPEng**

Enc: Hand Auger Logs, including Scala Penetrometer Results  
Dynamic Probe-Heavy Logs  
Liquefaction Analysis Plots  
Site Plan (RILEY Dwg: 13801/83-1)



# GEOTECHNICAL AND GEOLOGICAL INFORMATION

## SOIL TYPES AND SYMBOLS

	FILL		CLAY
	TOPSOIL		PEAT
	SILT		GROUNDWATER LEVEL
	SAND		SCALA PENETROMETER LAST 3 NUMBER OF BLOWS PER 50mm INCREMENT
	GRAVEL		

## ROCK TYPES AND SYMBOLS

	SANDSTONE		BASALT
	SILTSTONE		TUFF
	MUDSTONE		IGNIMBRITE
	LIMESTONE		GREYWACKE

## SOIL STRENGTH CLASSIFICATION

### FINE GRAINED COHESIVE SOILS

TERM	FIELD IDENTIFICATION	UNDRAINED SHEAR STRENGTH (KPa)
Very Soft (Vs)	Exudes between fingers when squeezed	<12
Soft (S)	Easily indented by fingers.	12 – 25
Firm (F)	Indented only by strong finger pressure.	25 – 50
Stiff (St)	Indented by thumb pressure	50 – 100
Very Stiff (VSt)	Indented by thumbnail	100 – 200
Hard (H)	Difficult to indent by thumbnail.	200+

## SPT & SCALA PENETROMETER RESULTS

TERM	SPT VALUE No. of BLOWS/300mm	SCALA PENETROMETER No. of BLOWS/100mm
very dense	>50	17+
dense	30 – 50	7 – 17
medium dense	10 – 30	3 – 7
loose	4 – 10	1 – 3
very loose	0 – 4	0 – 2

## ROCK STRENGTH CLASSIFICATION

TERM	FIELD IDENTIFICATION	UNCONFINED UNIAXIAL COMPRESSIVE STRENGTH (MPa)
Extremely weak (EW)	Indented by thumbnail.	< 1
Very weak (VW)	Cumbles under firm blows with point of geological hammer. Can be peeled with pocket knife.	1 – 5
Weak (W)	Difficult to peel with pocket knife.	5 – 20
Moderately strong (MS)	Cannot be scraped or peeled with pocket knife.	20 – 50
Strong (S)	More than one blow of geological hammer to fracture.	50 – 100
Very strong (VS)	Many blows of geological hammer to break.	100 – 250
Extremely strong (ES)	Can only be chipped with geological hammer.	250+

## MOISTURE CONDITION

Dry (D)	Looks and feels dry; powdery and friable.
Moist (M)	Feels cool; darkened in colour; no free water when remoulded
Wet (W)	Feels cool; darkened in colour; free water forms on hands
Saturated (S)	Free water is present on sample.

## SAMPLE TYPES

	UNDISTURBED
	MACHINE AUGER DISTURBED
	HAND AUGER DISTURBED
	STANDARD PENETRATION TEST (solid cone)
	STANDARD PENETRATION TEST (hollow cone)

## DRILLING METHOD

OB	OPEN BARREL
TT	TRIPLE TUBE
WB	WASH BORE
SH	UNDISTURBED SHELBY TUBE
RC	ROCK CORE
SPT	STANDARD PENETRATION TEST

## FIELD TESTS

V	SHEAR VANE (corrected to BS:1377)
R	REMOULDED STRENGTH
P	POCKET PENETROMETER
CH	CLEGG HAMMER

INFORMATION BASED ON THE NZ GEOTECHNICAL SOCIETY INC GUIDELINES FOR THE CLASSIFICATION AND DESCRIPTION OF SOIL AND ROCK FOR ENGINEERING PURPOSES

**RILEY**  
CONSULTANTS

P.O. BOX 4355  
CHRISTCHURCH  
TEL. 03-3794402  
FAX. 03-3794403

GEOLOGICALINFO-chch.DWG REV 1 June 2010





Riley Consultants Limited  
395 Madras St  
Christchurch 8013  
Tel: 03 3794402  
Fax: 03 3794403

## HAND AUGER LOG

Project: 26 Hemingway Place		Location: Brooklands, Christchurch		Hole position: Refer to site plan		No.: <b>HA1</b>
Job No.: 13801/83	Start Date: 03-06-13 Finish Date: 03-06-13	Ground Level (m LINZ): 1.00	Co-Ordinates (NZTM2000): E 1,575,604.0 N 5,191,451.0			
Client: MWH Recovery			Hole Depth: 1.40 m			Sheet: 1 of 1

Elevation (m LINZ)	Depth (m)	Geological Unit	Geological Description (refer to separate Geotechnical and Geological Information sheet for further information)	Legend	Soil Shear Strength (kPa)	Scala Penetrometer (blows / 50 mm)	Groundwater	Soil Moisture	Samples	Tests	Instrument/ Backfill
+1.00					50 100 150 200	3 6 9 12 15					
-0.85	0.15		Slightly organic sandy SILT with trace rootlets; dark brown. Soft; moist; non-plastic; sand, fine. (TOPSOIL)							No. 1 1, 0, 1, 0, 1, 1, 2, 2, 4, 3, 3, 4, 5, 4, 4, 3, 3, 3, 3, 2	
+0.55	0.45		SILT with some sand and minor gravel; dark brown. Firm; moist; non-plastic; sand, fine; gravel, fine, subrounded, greywacke (NON-ENGINEERED FILL?)								
		1	Fine to coarse SAND with trace silt; light brownish grey Medium dense; moist. (CHRISTCHURCH FORMATION)  0.55m - 0.75m Grades to a dense layer  0.80m Grades to grey  1.20m Grades to saturated							No. 2 2, 2, 1, 3, 2, 2, 3, 2, 2, 3, 3, 3, 4, 3, 3, 4, 4, 4, 3, 3	
-0.40	1.40		EOH @ 1.40 m								
		2								No. 3 4, 4, 4, 3, 4, 3, 4, 4, 4, 4, 3, 3, 4, 4, 5, 5, 5, 5, 5, 4, 3, 4, 4, 5	
		3									

### Explanations:

Rock Mass Weathering - unweathered, slightly  
weathered, moderately weathered, highly weathered,  
completely weathered, residually weathered  
Relative soil Strength - very soft/very loose, soft/loose,  
firm/medium dense, stiff/dense, very stiff/very dense

- Small Disturbed Sample
- Large Disturbed Sample
- U100 Undisturbed Sample



Scala Penetrometer - blows/50mm  
Permeability Test  
Schmidt Hammer  
Insitu Vane Shear Strength (kPa)  
V=Peak, R=Residual, UTP=Unable  
to penetrate  
Water Strike (1st, 2nd ...)  
Water Rise (1st, 2nd ...) and  
Rise Time (minutes)

### GROUNDWATER

- ☐ None
- ☒ Slow Seep (depth 1.2 m)
- ☐ Rapid Inflow (depth )

### HOLE TERMINATED DUE TO:

- ☐ Target depth
- ☐ Refusal
- ☒ Collapse

### Remarks

1. Ground level and coordinates are  
approximate and subject to survey  
confirmation.  
2. Scala test terminated due to collapse  
of saturated sand.

All dimensions in metres  
Scale 1:20

Contractor:

Rig/Plant Used:  
Hand Auger 70 mm

Logged by: FB  
Checked by: AvD

RILEY AGS 3\_1 NZ 18 13 GLB Log RILEY HA CHCH (NO MAP) 13801-83 26 HEMINGWAY PL GP3 03/06/13 17:11 Produced by gmat Professional




## HAND AUGER LOG

Project: 26 Hemingway Place		Location: Brooklands, Christchurch		Hole position: Refer to site plan		No.:  <b>HA2</b>
Job No.: 13801/83	Start Date: 03-06-13 Finish Date: 03-06-13	Ground Level (m LINZ): 1.00	Co-Ordinates (NZTM2000): E 1,575,606.0 N 5,191,424.0			
Client: MWH Recovery		Hole Depth: 1.75 m		Sheet:  1 of 1		

[illegible]

**Explanations:**

Rock Mass Weathering - unweathered, slightly weathered, moderately weathered, highly weathered, completely weathered, residually weathered  
Relative soil Strength - very soft/very loose, soft/loose, firm/medium dense, stiff/dense, very stiff/very dense

-  Small Disturbed Sample  
 Large Disturbed Sample  
 U100 Undisturbed Sample



Scala Penetrometer - blows/50mm  
 Permeability Test  
 Schmidt Hammer  
 Insitu Vane Shear Strength (kPa)  
 V=Peak, R=Residual, UTP=Unable  
 to penetrate  
 Water Strike (1st, 2nd ...)  
 Water Rise (1st, 2nd ) and  
 Rise Time (minutes)

## GROUNDWATER

- ☐ None  
☒ Slow Seep (depth 1.3 m)  
☐ Rapid Inflow (depth )

HOLE TERMINATED DUE TO:


- Target depth ☐ Refusal ☒ Collapse ☐

## Remarks

1. Ground level and coordinates are approximate and subject to survey confirmation
2. Scafe test terminated due to collapse of saturated sand

All dimensions in metres Scale 1:20	Contractor:	Rig/Plant Used: Hand Auger 70 mm	Logged by: CJO	Checked by: AvD
--	-------------	-------------------------------------	-------------------	--------------------







		DYNAMIC PROBE TEST		DPH1	
Project Number	13801/83	Hammer Weight	50 kg		
Project:	26 Hemingway Pla	Hammer Drop	500 mm		
		Tip Diameter	43.7 mm		
Location:	Brooklands, Christ	Hammer Efficiency	91%		
Page 2 of 2					


Depth (m)	DPN <sub>100</sub>	Equiv. SPT N	Torque	DPN <sub>100</sub> (Blows per 100mm)	Equiv. SPT N <sub>60</sub> (Incl torque correction)	Torque (kgm)
10.1	29	72.3				
10.2	30	68.9				
10.3	30	68.9				
10.4	30	68.9				
10.5	32	71.5				
10.6	35	75.7				
10.7	35	80.8				
10.8	35	83.4				
10.9	35	83.4				
11.0	35	83.4	5			
11.1	34	82.4				
11.2	32	79.6				
11.3	32	76.3				
11.4	30	72.9				
11.5	30	71.1				
11.6	32	71.0				
11.7	33	73.5				
11.8	34	76.8				
11.9	36	80.1				
12.0	29	76.7	10			
12.1	28	71.6				
12.2	28	84.8				
12.3	28	83.9				
12.4	27	83.1				
12.5	27	82.2	10			
12.6						
12.7						
12.8						
12.9						
13.0						
13.1						
13.2						
13.3						
13.4						
13.5						
13.6						
13.7						
13.8						
13.9						
14.0						
14.1						
14.2						
14.3						
14.4						
14.5						
14.6						
14.7						
14.8						
14.9						
15.0						
15.1						
15.2						
15.3						
15.4						
15.5						
15.6						
15.7						
15.8						
15.9						
16.0						
16.1						
16.2						
16.3						
16.4						
16.5						
16.6						
16.7						
16.8						
16.9						
17.0						
17.1						
17.2						
17.3						
17.4						
17.5						
17.6						
17.7						
17.8						
17.9						
18.0						
18.1						
18.2						
18.3						
18.4						
18.5						
18.6						
18.7						
18.8						
18.9						
19.0						
19.1						
19.2						
19.3						
19.4						
19.5						
19.6						
19.7						
19.8						
19.9						
20.0						

Date Logged	3/06/2013
Logged By	FB/CO
Testing Based on	BS 1377



P.O. BOX 4355  
CHRISTCHURCH  
TEL. 03-379 4402  
FAX. 03-379 4403







DYNAMIC PROBE TEST				DPH2
Project Number	13801/83	Hammer Weight	50 kg	
Project:	26 Hemingway Pl	Hammer Drop	500 mm	
		Tip Diameter	43.7 mm	
Location:	Brooklands, Christ	Hammer Efficiency	91%	
Page 2 of 2				


Depth (m)	DPN <sub>100</sub>	Equiv. SPT N <sub>60</sub>	Torque (kgm)	DPN <sub>100</sub> (Blows per 100mm)	Equiv. SPT N <sub>60</sub> (Incl torque correction)	Torque (kgm)
10.1	20	70.5				
10.2	29	67.8				
10.3	25	63.6				
10.4	24	59.1				
10.5	23	53.9				
10.6	23	52.1				
10.7	26	53.7				
10.8	28	57.8				
10.9	33	86.2				
11.0	32	71.2				
11.1	32	74.8				
11.2	29	71.3				
11.3	28	67.9				
11.4	26	62.9				
11.5	25	59.5				
11.6	24	56.1				
11.7	27	57.0				
11.8	26	57.9				
11.9	27	60.5				
12.0						
12.1						
12.2						
12.3						
12.4						
12.5						
12.6						
12.7						
12.8						
12.9						
13.0						
13.1						
13.2						
13.3						
13.4						
13.5						
13.6						
13.7						
13.8						
13.9						
14.0						
14.1						
14.2						
14.3						
14.4						
14.5						
14.6						
14.7						
14.8						
14.9						
15.0						
15.1						
15.2						
15.3						
15.4						
15.5						
15.6						
15.7						
15.8						
15.9						
16.0						
16.1						
16.2						
16.3						
16.4						
16.5						
16.6						
16.7						
16.8						
16.9						
17.0						
17.1						
17.2						
17.3						
17.4						
17.5						
17.6						
17.7						
17.8						
17.9						
18.0						
18.1						
18.2						
18.3						
18.4						
18.5						
18.6						
18.7						
18.8						
18.9						
19.0						
19.1						
19.2						
19.3						
19.4						
19.5						
19.6						
19.7						
19.8						
19.9						
20.0						


Date Logged	3/06/2013	
Logged By	FB/CO	
Testing Based on	BS 1377	

P.O. BOX 4355  
 CHRISTCHURCH  
 TEL. 03-379 4402  
 FAX. 03-379 4403









5/07/2013

Calculation Sheet Rev 8





### LEGEND



HAND AUGER HOLE LOCATION



DYNAMIC PROBE (HEAVY)  
TEST LOCATION



CONE PENETRATION TEST LOCATION  
(SOURCED FROM CANTERBURY  
GEOTECHNICAL DATABASE)


PROPERTY BOUNDARY

SCALE 1:250 (A3)



### NOTES:-

1. PHOTO SOURCED FROM CHRISTCHURCH POST EARTHQUAKE AERIAL PHOTOS (24TH FEB 2011), LINZ
2. ORIGINAL SCALE A3
3. PARCELS SOURCED FROM QUICKMAP CANTERBURY (OCT 2012)
4. HOLE/TEST LOCATIONS ACCURATE TO  $\pm 1m$



2	CPT ADDED	12 JUN 2013	12 JUN 2013
3	NOTE 4 ADDED	12 JUN 2013	12 JUN 2013
4	HA1 & DPH1	12 JUN 2013	12 JUN 2013
5	HA2 & DPH2	12 JUN 2013	12 JUN 2013
6	HA3 & DPH3	12 JUN 2013	12 JUN 2013
7	HA4 & DPH4	12 JUN 2013	12 JUN 2013
8	HA5 & DPH5	12 JUN 2013	12 JUN 2013
9	HA6 & DPH6	12 JUN 2013	12 JUN 2013
10	HA7 & DPH7	12 JUN 2013	12 JUN 2013
11	HA8 & DPH8	12 JUN 2013	12 JUN 2013
12	HA9 & DPH9	12 JUN 2013	12 JUN 2013
13	HA10 & DPH10	12 JUN 2013	12 JUN 2013
14	HA11 & DPH11	12 JUN 2013	12 JUN 2013
15	HA12 & DPH12	12 JUN 2013	12 JUN 2013
16	HA13 & DPH13	12 JUN 2013	12 JUN 2013
17	HA14 & DPH14	12 JUN 2013	12 JUN 2013
18	HA15 & DPH15	12 JUN 2013	12 JUN 2013
19	HA16 & DPH16	12 JUN 2013	12 JUN 2013
20	HA17 & DPH17	12 JUN 2013	12 JUN 2013
21	HA18 & DPH18	12 JUN 2013	12 JUN 2013
22	HA19 & DPH19	12 JUN 2013	12 JUN 2013
23	HA20 & DPH20	12 JUN 2013	12 JUN 2013
24	HA21 & DPH21	12 JUN 2013	12 JUN 2013
25	HA22 & DPH22	12 JUN 2013	12 JUN 2013
26	HA23 & DPH23	12 JUN 2013	12 JUN 2013
27	HA24 & DPH24	12 JUN 2013	12 JUN 2013
28	HA25 & DPH25	12 JUN 2013	12 JUN 2013
29	HA26 & DPH26	12 JUN 2013	12 JUN 2013
30	HA27 & DPH27	12 JUN 2013	12 JUN 2013
31	HA28 & DPH28	12 JUN 2013	12 JUN 2013
32	HA29 & DPH29	12 JUN 2013	12 JUN 2013
33	HA30 & DPH30	12 JUN 2013	12 JUN 2013
34	HA31 & DPH31	12 JUN 2013	12 JUN 2013
35	HA32 & DPH32	12 JUN 2013	12 JUN 2013
36	HA33 & DPH33	12 JUN 2013	12 JUN 2013
37	HA34 & DPH34	12 JUN 2013	12 JUN 2013
38	HA35 & DPH35	12 JUN 2013	12 JUN 2013
39	HA36 & DPH36	12 JUN 2013	12 JUN 2013
40	HA37 & DPH37	12 JUN 2013	12 JUN 2013
41	HA38 & DPH38	12 JUN 2013	12 JUN 2013
42	HA39 & DPH39	12 JUN 2013	12 JUN 2013
43	HA40 & DPH40	12 JUN 2013	12 JUN 2013
44	HA41 & DPH41	12 JUN 2013	12 JUN 2013
45	HA42 & DPH42	12 JUN 2013	12 JUN 2013
46	HA43 & DPH43	12 JUN 2013	12 JUN 2013
47	HA44 & DPH44	12 JUN 2013	12 JUN 2013
48	HA45 & DPH45	12 JUN 2013	12 JUN 2013
49	HA46 & DPH46	12 JUN 2013	12 JUN 2013
50	HA47 & DPH47	12 JUN 2013	12 JUN 2013
51	HA48 & DPH48	12 JUN 2013	12 JUN 2013
52	HA49 & DPH49	12 JUN 2013	12 JUN 2013
53	HA50 & DPH50	12 JUN 2013	12 JUN 2013
54	HA51 & DPH51	12 JUN 2013	12 JUN 2013
55	HA52 & DPH52	12 JUN 2013	12 JUN 2013
56	HA53 & DPH53	12 JUN 2013	12 JUN 2013
57	HA54 & DPH54	12 JUN 2013	12 JUN 2013
58	HA55 & DPH55	12 JUN 2013	12 JUN 2013
59	HA56 & DPH56	12 JUN 2013	12 JUN 2013
60	HA57 & DPH57	12 JUN 2013	12 JUN 2013
61	HA58 & DPH58	12 JUN 2013	12 JUN 2013
62	HA59 & DPH59	12 JUN 2013	12 JUN 2013
63	HA60 & DPH60	12 JUN 2013	12 JUN 2013
64	HA61 & DPH61	12 JUN 2013	12 JUN 2013
65	HA62 & DPH62	12 JUN 2013	12 JUN 2013
66	HA63 & DPH63	12 JUN 2013	12 JUN 2013
67	HA64 & DPH64	12 JUN 2013	12 JUN 2013
68	HA65 & DPH65	12 JUN 2013	12 JUN 2013
69	HA66 & DPH66	12 JUN 2013	12 JUN 2013
70	HA67 & DPH67	12 JUN 2013	12 JUN 2013
71	HA68 & DPH68	12 JUN 2013	12 JUN 2013
72	HA69 & DPH69	12 JUN 2013	12 JUN 2013
73	HA70 & DPH70	12 JUN 2013	12 JUN 2013
74	HA71 & DPH71	12 JUN 2013	12 JUN 2013
75	HA72 & DPH72	12 JUN 2013	12 JUN 2013
76	HA73 & DPH73	12 JUN 2013	12 JUN 2013
77	HA74 & DPH74	12 JUN 2013	12 JUN 2013
78	HA75 & DPH75	12 JUN 2013	12 JUN 2013
79	HA76 & DPH76	12 JUN 2013	12 JUN 2013
80	HA77 & DPH77	12 JUN 2013	12 JUN 2013
81	HA78 & DPH78	12 JUN 2013	12 JUN 2013
82	HA79 & DPH79	12 JUN 2013	12 JUN 2013
83	HA80 & DPH80	12 JUN 2013	12 JUN 2013
84	HA81 & DPH81	12 JUN 2013	12 JUN 2013
85	HA82 & DPH82	12 JUN 2013	12 JUN 2013
86	HA83 & DPH83	12 JUN 2013	12 JUN 2013
87	HA84 & DPH84	12 JUN 2013	12 JUN 2013
88	HA85 & DPH85	12 JUN 2013	12 JUN 2013
89	HA86 & DPH86	12 JUN 2013	12 JUN 2013
90	HA87 & DPH87	12 JUN 2013	12 JUN 2013
91	HA88 & DPH88	12 JUN 2013	12 JUN 2013
92	HA89 & DPH89	12 JUN 2013	12 JUN 2013
93	HA90 & DPH90	12 JUN 2013	12 JUN 2013
94	HA91 & DPH91	12 JUN 2013	12 JUN 2013
95	HA92 & DPH92	12 JUN 2013	12 JUN 2013
96	HA93 & DPH93	12 JUN 2013	12 JUN 2013
97	HA94 & DPH94	12 JUN 2013	12 JUN 2013
98	HA95 & DPH95	12 JUN 2013	12 JUN 2013
99	HA96 & DPH96	12 JUN 2013	12 JUN 2013
100	HA97 & DPH97	12 JUN 2013	12 JUN 2013
101	HA98 & DPH98	12 JUN 2013	12 JUN 2013
102	HA99 & DPH99	12 JUN 2013	12 JUN 2013
103	HA100 & DPH100	12 JUN 2013	12 JUN 2013
104	HA101 & DPH101	12 JUN 2013	12 JUN 2013
105	HA102 & DPH102	12 JUN 2013	12 JUN 2013
106	HA103 & DPH103	12 JUN 2013	12 JUN 2013
107	HA104 & DPH104	12 JUN 2013	12 JUN 2013
108	HA105 & DPH105	12 JUN 2013	12 JUN 2013
109	HA106 & DPH106	12 JUN 2013	12 JUN 2013
110	HA107 & DPH107	12 JUN 2013	12 JUN 2013
111	HA108 & DPH108	12 JUN 2013	12 JUN 2013
112	HA109 & DPH109	12 JUN 2013	12 JUN 2013
113	HA110 & DPH110	12 JUN 2013	12 JUN 2013
114	HA111 & DPH111	12 JUN 2013	12 JUN 2013
115	HA112 & DPH112	12 JUN 2013	12 JUN 2013
116	HA113 & DPH113	12 JUN 2013	12 JUN 2013
117	HA114 & DPH114	12 JUN 2013	12 JUN 2013
118	HA115 & DPH115	12 JUN 2013	12 JUN 2013
119	HA116 & DPH116	12 JUN 2013	12 JUN 2013
120	HA117 & DPH117	12 JUN 2013	12 JUN 2013
121	HA118 & DPH118	12 JUN 2013	12 JUN 2013
122	HA119 & DPH119	12 JUN 2013	12 JUN 2013
123	HA120 & DPH120	12 JUN 2013	12 JUN 2013
124	HA121 & DPH121	12 JUN 2013	12 JUN 2013
125	HA122 & DPH122	12 JUN 2013	12 JUN 2013
126	HA123 & DPH123	12 JUN 2013	12 JUN 2013
127	HA124 & DPH124	12 JUN 2013	12 JUN 2013
128	HA125 & DPH125	12 JUN 2013	12 JUN 2013
129	HA126 & DPH126	12 JUN 2013	12 JUN 2013
130	HA127 & DPH127	12 JUN 2013	12 JUN 2013
131	HA128 & DPH128	12 JUN 2013	12 JUN 2013
132	HA129 & DPH129	12 JUN 2013	12 JUN 2013
133	HA130 & DPH130	12 JUN 2013	12 JUN 2013
134	HA131 & DPH131	12 JUN 2013	12 JUN 2013
135	HA132 & DPH132	12 JUN 2013	12 JUN 2013
136	HA133 & DPH133	12 JUN 2013	12 JUN 2013
137	HA134 & DPH134	12 JUN 2013	12 JUN 2013
138	HA135 & DPH135	12 JUN 2013	12 JUN 2013
139	HA136 & DPH136	12 JUN 2013	12 JUN 2013
140	HA137 & DPH137	12 JUN 2013	12 JUN 2013
141	HA138 & DPH138	12 JUN 2013	12 JUN 2013
142	HA139 & DPH139	12 JUN 2013	12 JUN 2013
143	HA140 & DPH140	12 JUN 2013	12 JUN 2013
144	HA141 & DPH141	12 JUN 2013	12 JUN 2013
145	HA142 & DPH142	12 JUN 2013	12 JUN 2013
146	HA143 & DPH143	12 JUN 2013	12 JUN 2013
147	HA144 & DPH144	12 JUN 2013	12 JUN 2013
148	HA145 & DPH145	12 JUN 2013	12 JUN 2013
149	HA146 & DPH146	12 JUN 2013	12 JUN 2013
150	HA147 & DPH147	12 JUN 2013	12 JUN 2013
151	HA148 & DPH148	12 JUN 2013	12 JUN 2013
152	HA149 & DPH149	12 JUN 2013	12 JUN 2013
153	HA150 & DPH150	12 JUN 2013	12 JUN 2013
154	HA151 & DPH151	12 JUN 2013	12 JUN 2013
155	HA152 & DPH152	12 JUN 2013	12 JUN 2013
156	HA153 & DPH153	12 JUN 2013	12 JUN 2013
157	HA154 & DPH154	12 JUN 2013	12 JUN 2013
158	HA155 & DPH155	12 JUN 2013	12 JUN 2013
159	HA156 & DPH156	12 JUN 2013	12 JUN 2013
160	HA157 & DPH157	12 JUN 2013	12 JUN 2013
161	HA158 & DPH158	12 JUN 2013	12 JUN 2013
162	HA159 & DPH159	12 JUN 2013	12 JUN 2013
163	HA160 & DPH160	12 JUN 2013	12 JUN 2013
164	HA161 & DPH161	12 JUN 2013	12 JUN 2013
165	HA162 & DPH162	12 JUN 2013	12 JUN 2013
166	HA163 & DPH163	12 JUN 2013	12 JUN 2013
167	HA164 & DPH164	12 JUN 2013	12 JUN 2013
168	HA165 & DPH165	12 JUN 2013	12 JUN 2013
169	HA166 & DPH166	12 JUN 2013	12 JUN 2013
170	HA167 & DPH167	12 JUN 2013	12 JUN 2013
171	HA168 & DPH168	12 JUN 2013	12 JUN 2013
172	HA169 & DPH169	12 JUN 2013	12 JUN 2013
173	HA170 & DPH170	12 JUN 2013	12 JUN 2013
174	HA171 & DPH171	12 JUN 2013	12 JUN 2013
175	HA172 & DPH172	12 JUN 2013	12 JUN 2013
176	HA173 & DPH173	12 JUN 2013	12 JUN 2013
177	HA174 & DPH174	12 JUN 2013	12 JUN 2013
178	HA175 & DPH175	12 JUN 2013	12 JUN 2013
179	HA176 & DPH176	12 JUN 2013	12 JUN 2013
180	HA177 & DPH177	12 JUN 2013	12 JUN 2013
181	HA178 & DPH178	12 JUN 2013	12 JUN 2013
182	HA179 & DPH179	12 JUN 2013	12 JUN 2013
183	HA180 & DPH180	12 JUN 2013	12 JUN 2013
184	HA181 & DPH181	12 JUN 2013	12 JUN 2013
185	HA182 & DPH182	12 JUN 2013	12 JUN 2013
186	HA183 & DPH183	12 JUN 2013	12 JUN 2013
187	HA184 & DPH184	12 JUN 2013	12 JUN 2013
188	HA185 & DPH185	12 JUN 2013	12 JUN 2013
189	HA186 & DPH186	12 JUN 2013	12 JUN 2013
190	HA187 & DPH187	12 JUN 2013	12 JUN 2013
191	HA188 & DPH188	12 JUN 2013	12 JUN 2013
192	HA189 & DPH189	12 JUN 2013	12 JUN 2013
193	HA190 & DPH190	12 JUN 2013	12 JUN 2013
194	HA191 & DPH191	12 JUN 2013	12 JUN 2013
195	HA192 & DPH192	12 JUN 2013	12 JUN 2013
196	HA193 & DPH193	12 JUN 2013	12 JUN 2013
197	HA194 & DPH194	12 JUN 2013	12 JUN 2013
198	HA195 & DPH195	12 JUN 2013	12 JUN 2013
199	HA196 & DPH196	12 JUN 2013	12 JUN 2013
200	HA197 & DPH197	12 JUN 2013	12 JUN 2013
201	HA198 & DPH198	12 JUN 2013	12 JUN 2013
202	HA199 & DPH199	12 JUN 2013	12 JUN 2013
203	HA200 & DPH200	12 JUN 2013	12 JUN 2013
204	HA201 & DPH201	12 JUN 2013	12 JUN 2013
205	HA202 & DPH202	12 JUN 2013	12 JUN 2013
206	HA203 & DPH203	12 JUN 2013	12 JUN 2013
207	HA204 & DPH204	12 JUN 2013	12 JUN 2013
208	HA205 & DPH205	12 JUN 2013	12 JUN 2013
209	HA206 & DPH206	12 JUN 2013	12 JUN 2013
210	HA207 & DPH207	12 JUN 2013	12 JUN 2013
211	HA208 & DPH208	12 JUN 2013	12 JUN 2013
212	HA209 & DPH209	12 JUN 2013	12 JUN 2013
213	HA210 & DPH210	12 JUN 2013	12 JUN 2013
214	HA211 & DPH211	12 JUN 2013	12 JUN 2013
215	HA212 & DPH212	12 JUN 2013	12 JUN 2013
216	HA213 & DPH213	12 JUN 2013	12 JUN 2013
217	HA214 & DPH214	12 JUN 2013	12 JUN 2013
218	HA215 & DPH215	12 JUN 2013	12 JUN